

**SCHEDULE OF ESTIMATED QUANTITIES AND BID PRICES**  
**Mountainbrook Road @ Chunns Cove Road Project No. 2010112**  
**METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY**

ITEM NO.	DESCRIPTION	QTY	UNITS	BID	TOTAL
MP-5.01	MOBILIZATION (3% MAX)	1	LS	\$	\$
MP-5.02.8(d)	8" DIP (CLASS 350) ALL DEPTHS	2,713	LF	\$	\$
MP-5.02.8(pb)	8" HDPE DIPS (DR 17) ALL DEPTHS BY PIPE BURSTING	491	LF	\$	\$
MP-5.02.6(p)	6" PVC ALL DEPTHS, INCLUDING BEDDING	80	LF	\$	\$
MP-5.02.4(p)	4" PVC (SCH 40) ALL DEPTHS, INCLUDING BEDDING	350	LF	\$	\$
MP-5.03.4(s)	4' DIAMETER STANDARD MANHOLE 0-6 FT.	18	EA	\$	\$
MP-5.03.4(d)	4' DIAMETER DROP MANHOLE 0-6 FT.	1	EA	\$	\$
MP-5.03.4(sh1)	4' DIAMETER SHALLOW MANHOLE TYPE I	5	EA	\$	\$
MP-5.04.4(s)	4' ADDITIONAL STANDARD MANHOLE DEPTH	6	VF	\$	\$
MP-5.04.4(d)	4' ADDITIONAL DROP MANHOLE DEPTH	3	VF	\$	\$
MP-5.05.4	8" X 8" X 4" DUCTILE IRON WYE	9	EA	\$	\$
MP-5.05.6	8" X 8" X 6" DUCTILE IRON WYE	2	EA	\$	\$
MP-5.06.4	4" CLEANOUT ASSEMBLY	22	EA	\$	\$
MP-5.06.6	6" CLEANOUT ASSEMBLY	4	EA	\$	\$
MP-5.07	PLUG AND ABANDON SEWERLINE	10	EA	\$	\$
MP-5.07.1	PLUG AND REMOVE SEWERLINE	1	EA	\$	\$
MP-5.08	ABANDON MANHOLE, INCLUDING PLUGS	7	EA	\$	\$
MP-5.12	PIPE EMBEDMENT MATERIAL	200	CY	\$	\$
MP-5.13	COMPACTED AGGREGATE BASE COURSE	200	CY	\$	\$
MP-5.14	SELECT BACKFILL MATERIAL	1,000	CY	\$	\$
MP-5.15	ROCK EXCAVATION	300	CY	\$	\$

**SCHEDULE OF ESTIMATED QUANTITIES AND BID PRICES**  
**Mountainbrook Road @ Chunns Cove Road Project No. 2010112**  
**METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY**

ITEM NO.	DESCRIPTION	QTY	UNITS	BID	TOTAL
MP-5.18.2	INLET PROTECTION	3	EA	\$	\$
MP-5.18.3	COIR MATTING	200	SY	\$	\$
MP-5.20	SERVICE LINE EXPLORATORY DIG	2	EA	\$	\$
MP-5.21.6(b)	BITUMINOUS PAVEMENT REPAIRS TYPE I-19.0 B) 6" DEPTH	125	SY	\$	\$
MP-5.21.8(b)	BITUMINOUS PAVEMENT REPAIRS 8" DEPTH	775	SY	\$	\$
MP-5.21.2(s)	BITUMINOUS ASPHALT RESURFACING (TYPE SF 9.5A) 2" MIN. DEPTH	6,200	SY	\$	\$
MP-5.21.1.5(s)	BITUMINOUS ASPHALT RESURFACING 1.5" MIN.DEPTH	200	SY	\$	\$
MP-5.24.1	CONCRETE CURB TO MATCH EXISTING	50	LF	\$	\$
MP-5.25	HAND PLACED ASPHALT CURB	20	LF	\$	\$
MP-5.27	PAVEMENT MILLING 2"	5,600	SY	\$	\$
MP-5.30	REPLACEMENT OF EXISTING PROPERTY MONUMENTS DISTURBED BY CONSTRUCTION	2	EA	\$	\$
MP-5.33	REMOVE MANHOLE, PLUG LINES	3	EA	\$	\$
MP-5.36	TREE REMOVAL LARGE PINE (SEE SPECIAL PROVISIONS DETAIL SHEETS )	2	EA	\$	\$
MP-6.04	SERVICE RECONNECTION BY EXCAVATION INCLUDING SADDLE OR COMP. FITTING TO PIPELINE OR CORED CONNECTION TO A MANHOLE, ALL COMPLETE	4	EA	\$	\$
	<b>TOTAL BID PRICE</b>			\$	
<b>TOTAL WRITTEN BID PRICE</b> _____					
_____ <b>and</b> _____ <b>/100 dollars.</b>					