# Fiscal Years 2026-2035



Metropolitan Sewerage District of Buncombe County, North Carolina

2028 Riverside Drive W.H. Mull Building Asheville, NC 28804

Phone: (828) 254-9646

Website: www.msdbc.org

# Metropolitan Sewerage District Of Buncombe County, North Carolina Fiscal Years 2026—2035



### Board of Directors

**Board Member** Representative of

**Town of Woodfin** M. Jerry Vehaun, Chairman

Al Whitesides, Vice-Chairman **County of Buncombe** 

Jackie W. Bryson, Secretary/Treasurer **Town of Woodfin** 

Matt Ashley, Jr. **Town of Montreat** 

**Douglas Dearth Town of Weaverville** 

**Sheila Franklin Cane Creek Water & Sewer District** 

William G. Lapsley **Cane Creek Water & Sewer District** 

**Esther Manheimer** City of Asheville

**Martin Moore County of Buncombe** 

**Chris Pelly City of Asheville** 

**Nathan Pennington County of Buncombe** 

**Allan Tarleton Town of Biltmore Forest** 

**Town of Black Mountain Robert C. Watts** 

**Gwen Wisler** City of Asheville

### CIP Committee Members

Robert C. Watts, Chairman

Matt Ashley, Jr.

William G. Lapsley

**Chris Pelly** 

**Nathan Pennington** 

**Allan Tarleton** 

City of Asheville

**Town of Biltmore Forest Town of Black Mountain** 

**Buncombe County** 

Henderson County/Cane Creek Water & Sewer District

**Town of Montreat Town of Weaverville Town of Woodfin** 

**Woodfin Sanitary Water & Sewer District** 

**Debra Campbell Jonathan Kanipe** 

Josh Harrold **Avril Pinder** 


Marcus Jones, P.E. **Savannah Parrish** 

**Scottie Harris Shannon Tuch** 

**Seth Eckard** 

**General Manager Director of Engineering** 


Thomas E. Hartye, P.E. Hunter Carson, P.E.



Fiscal Years 2026—2035

# **Overview**





NCDEQ-DWR has requested that the following information be provided in this document, in accordance with the Performance Standards as defined in MSD's Collection System Permit WQCS00004.

#### **Goal Statement**

The mission of the MSD Capital Improvement Program is to produce, manage, and complete engineering projects for the repair and rehabilitation of the District's collection system and Water Reclamation Facility (WRF). This shall be undertaken in the most efficient and effective manner necessary to ensure the reliable delivery and treatment of wastewater at an equitable price and in an environmentally sensitive manner.

#### **Description of the Project Area & Existing Facilities**

#### **Collection System**

The MSD service area covers approximately 264 square miles. MSD provides service to areas within the French Broad River Valley and the Swannanoa River Valley. There are over 1,165 miles of public sanitary sewer line, 39 pump stations within the collection system, and approximately 35,039 manholes system-wide. Approximately 81 miles are large interceptors with diameters ranging from 24" to 66". Approximately 244 miles are small lines with diameters 6" or less and the remainder are medium size lines ranging from 8" up to 21". Much of this pipe is between 50 and 100 years old and is in significant need of rehabilitation or replacement. The District currently provides service to approximately 60,000 accounts and 207,100 people.

#### **Water Reclamation Facility**

The Water Reclamation Facility (WRF) is a 40MGD secondary treatment plant serving Buncombe County (specifically Asheville, Biltmore Forest, Black Mountain, Montreat, Weaverville, Woodfin and Buncombe County at large), and northern Henderson County (formerly the Cane Creek Water and Sewer District, which merged with MSD on July 1, 2020).

Overall, MSD serves a combined customer population of 207,100 and over 30 separately billed industries. The facility treats a current average daily flow of approximately 20.1 MGD. The WRF is an attached growth design, comprised of 152 rotating biological contactors (RBC's), which provide full secondary treatment. These RBC's provide 450-500 acres (3+ acres each unit) of surface area for biological growth. MSD's facility is believed to be the largest RBC plant in the world. The plant consists of:

#### **Preliminary Treatment Components**

- Influent Multirake Barscreens (2 units, ½ inch Bar Spacing, 40 mgd each) with screenings washer/compactor and shaftless screw conveyer
- Influent Pumps (3 units) 35 MGD rated capacity each
- Perforated Plate Fine Screens (3 units, ¼ inch openings, 40 mgd each) with screenings washer/compactor
- Vortex Grit Removal (2 units, 50 mgd each) Removal Rate 95% of Grit > 140 Mesh
- Storm Surge System Utilizes (3) 5mgd pumps and (2) 2.1 million gallon tanks to temporarily store storm surge flows over 65 mgd, for temporary peak shaving.

#### **Primary Treatment Components**

Primary Clarification - Chemically Enhanced Kruger ACTIFLO system

#### **Secondary Treatment Components**

- 1st Stage RBC's (44 units)
- 2<sup>nd</sup> Stage RBC's (72 units)
- 3<sup>rd</sup> Stage RBC's (36 units)
- Intermediate Pumps (3 units) pump water to clarifier from 3<sup>rd</sup> RBC stage
- Intermediate Clarifier (4 cells total volume 2 MG)
- Microfiltration via AASI AquaDisk Units (16 units)

#### **Disinfection Components**

 Sodium Hypochlorite solution - average feed 1000 gallons/day at 6.5% solution strength

#### **Residuals Handling Components**

- Gravity Thickeners (2 units) 100 foot-diameter each
- 2.5 Meter Belt Presses (2 units)
- Fluidized Bed Incinerator (designed for 3,317 dry tons per hour, or 39.8DT/day)

#### **Energy Management Components**

- Two separate power circuits from Duke Energy for plant, with Automatic Transfer Switch if one fails
- 4 Megawatt total from three Diesel Generators (emergency backup power for WRF; will maintain full treatment processes during a power outage)
- 850 Kilowatt Hydro Turbines (3 units) induction units (French Broad River source). These generate power using the District's dam/flume.

#### **Automation Components**

SCADA (Supervisory Control and Data Acquisition) - full automated control of WRF


#### **Sludge Management Plan**

 MSD utilizes its fluidized bed incinerator as its primary residual management option. MSD also maintains an arrangement with the Buncombe County Landfill (lined) for planned maintenance and emergencies. Presently the facility is managing 17-20 DT's per day of residuals. The facilities are designed for 39.8 DT's per day. Sludge generated at the facility is primary and secondary in nature, with secondary sludge consisting of sloughings from the RBCs.

Sludge is thickened in on-site gravity thickeners to a consistency of 2-5% solids at which time it is then pumped to the 2 1/2-meter belt presses. These units dewater the sludge to approximately over 22% solids and then it is pumped to the incinerator. Air emissions from the incinerator are of excellent quality. Incinerator ash is thickened on-site via a gravity ash thickener and then pumped to an on-site lagoon. Groundwater is monitored in accordance with NCDEQ requirements (up & down gradient).

The incinerator system provides the most cost-effective method for sludge management. Supplementary fuel is sometimes required due to the 22% solids content - natural gas via Enbridge Gas North Carolina is utilized for this purpose.


As stated above, MSD maintains an agreement with the local county landfill (lined) to dispose of dewatered sludge during emergency and/or maintenance activities. This provides a second residuals management alternative, when or if needed.



Fiscal Years 2026—2035

# **Program Summary**





### TEN YEAR CAPITAL IMPROVEMENT PROGRAM

PROJECT NAME	LOCATION OF PROJECT		PROJECT NUMBER		PROJECT FOOTAGE	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS THRU FY 25	FY 25-2	6	FY 26-	27	FY 27-28	FY 28	-29	FY 29-	-30	FY 30	-31	FY 31	-32	FY 32-	33	FY 33-	-34	FY 34-	-35
							IHKU FT 25	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE
INTERCEPTOR AND WET W	EATHER REHAB	ILITATI	ON																							
Beaverdam Creek WW (CDM #10)	Buncombe County	BD	2001191	14	5,500	\$2,405,200	\$0	\$0		\$0		\$38,500	\$18,000		\$145,700		\$2,000		\$2,201,000	5,500	\$0		\$0		\$0	
Biltmore WW (CDM #3)	Biltmore	BD	2001192	24	2,200	\$1,220,250	\$0	\$0		\$15,400		\$3,400	\$155,850		\$1,045,600	2,200	\$0		\$0		\$0		\$0		\$0	
Dingle Creek Interceptor	Asheville	TH	2006010	8	7,871	\$3,120,957	\$92,957	\$0		\$0		\$0	\$0		\$0		\$0		\$0		\$3,028,000	7,871	\$0		\$0	
Four Mile Creek WW (CDM #1)	Biltmore Forest	BD	2001193	8	3,400	\$1,423,400	\$0	\$0		\$0		\$0	\$0		\$0		\$24,000		\$3,400		\$45,000		\$1,351,000	3,400	\$0	
Lower Swannanoa Interceptor	Asheville	BD	2004040	9	6,980	\$18,538,379	\$250,717	\$0		\$0		\$0	\$436,250		\$130,000		\$8,850,206	3,490	\$8,871,206	3,490	\$0		\$0		\$0	
Middle Beaverdam Crk. @ I-26	Woodfin	TH	2010002	8	2,930	\$1,392,430	\$7,430	\$0		\$0		\$0	\$0		\$0		\$0		\$48,500		\$25,000		\$1,311,500	2,930	\$0	
South Swannanoa WW (CDM #4)	Asheville	BD	2001195	36	8,040	\$6,074,460	\$0	\$0		\$57,000		\$6,000	\$102,350		\$1,467,700	2,000	\$4,441,410	6,040	\$0		\$0		\$0		\$0	
Swannanoa Equalization Tank	Swannanoa	нс	2019046	N/A	0	\$35,047,859	\$8,748	\$75,000		\$516,111		\$0	\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Town Branch Int - Phase III	Asheville	DP	2017158	10	3,600	\$2,710,850	\$0	\$0		\$0		\$0	\$0		\$0		\$28,000		\$9,000		\$160,850		\$2,513,000	3,600	\$0	
SUBTOTAL					40,521	\$71,933,785	\$359,852	\$75,000	0	\$588,511	0	\$47,900 0	\$712,450	0	\$2,789,000	4,200	\$13,345,616	9,530	\$11,133,106	8,990	\$3,258,850	7,871	\$5,175,500	9,930	\$0	0
Inflation per ENR Const. Cost Index	3.32%					1.0000	1.0000	1.0000		1.0332		1.0675	1.1029		1.1396		1.1774		1.2165		1.2569		1.2986		1.3417	
SUBTOTAL with inflation					40,521	\$71,933,785	\$359,852	\$75,000	0	\$608,050	0	\$51,133 0	\$785,792	0	\$3,178,236	4,200	\$15,713,054	9,530	\$13,543,245	8,990	\$4,095,955	7,871	\$6,720,901	9,930	\$0	0

PROJECT NAME	LOCATION OF PROJECT	PROJ. MGR.	PROJECT NUMBER	PIPE RATING	PROJECT FOOTAGE E	TOTAL STIMATED COST	TOTAL EST. EXPENDS THRU FY 24	FY 25-26		FY 26-27	FY 27-28	FY 28-	-29	FY 29-3	30	FY 30-	31	FY 31-	-32	FY 32	-33	FY 33	3-34	FY 34-	-35
							THRU FY 24	BUDGET FO	OTAGE	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE
GENERAL SEWER REHABIL	ITATION																								
Antique Lane @ Canie Creek	Asheville	DP	2022023	14	6,039	\$2,471,000	\$0	\$50,000		\$1,000	\$213,300	\$34,700		\$2,172,000	6,039	\$0		\$0		\$0		\$0		\$0	
Adams Street	Asheville	SA	2012126	12	2,630	\$1,157,800	\$11,800	\$0		\$0	\$0	\$0		\$16,000		\$18,000		\$80,000		\$1,032,000	2,630	\$0		\$0	
Arlington Street	Asheville	DP	2015008	15	3,230	\$1,452,000	\$0	\$0		\$0	\$0	\$0		\$20,000		\$1,000		\$15,000		\$1,416,000	3,230	\$0		\$0	
Asheville Rd. @ US Hwy 70	Swannanoa	TH	2023005	17	5,470	\$2,458,210	\$0	\$0		\$0	\$43,760	\$15,000		\$114,900		\$22,850		\$2,261,700	5,470	\$0		\$0		\$0	
Atkins Street	Arden	BD	2014012	19	1,833	\$771,930	\$5,480	\$0		\$0	\$0	\$2,600		\$49,850		\$714,000	1,833	\$0		\$0		\$0		\$0	
Avena Rd. @ Flat Creek Rd.	Black Mountain	TH	2021009	43	1,985	\$840,182	\$0	\$0		\$13,000	\$32,950	\$794,232	1,985	\$0		\$0		\$0		\$0		\$0		\$0	
Avon Ave. @ Haywood Rd.	West Asheville	BD	2021003	65	218	\$206,550	\$57,450	\$149,100	218	\$0	\$0	\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Beale Road at Copney Lane	Asheville	DP	2009129	40	5,430	\$2,344,375	\$24,025	\$185,000		\$116,350	\$2,019,000 5,430	\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Bear Creek Road	W. Asheville	SA	2011117	6	2,800	\$1,269,900	\$7,900	\$0		\$0	\$0	\$0		\$0		\$1,500		\$16,500		\$138,500		\$0		\$1,105,500	2,800
Bellevue Road	S. Asheville	DP	2015175	15	1,100	\$753,336	\$34,950	\$71,386		\$16,000	\$631,000 1,100	\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Bent Tree Rd. @ Old Toll Rd.	Asheville	DP	2024034	NA	. 0	\$24,000	\$12,500	\$11,500		\$0	\$0	\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Braddock Way - PRP 20002	Asheville	TH	2006025	22	3,199	\$1,923,853	\$40,603	\$137,350		\$78,500	\$1,667,400 3,199	\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Broadway St. at Bordeau Place	Asheville	DP	2009034	22	475	\$259,750	\$6,250	\$0		\$0	\$0	\$253,500	475	\$0		\$0		\$0		\$0		\$0		\$0	
Central Ave. @ I-240	Asheville	SA	2014180	37	1,224	\$1,020,750	\$6,000	\$2,000		\$25,500	\$987,250 1,224	\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Chatham Road	Asheville	SA	2015019	19	1,330	\$627,925	\$4,800	\$53,500		\$16,000	\$553,625 1,330	\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Chester Pl. @ Cranford Rd.	Asheville	TH	2019026	7	1,025	\$426,100	\$0	\$0		\$0	\$0	\$0		\$0		\$0		\$90,900		\$45,700		\$0		\$289,500	1,025
Covewood Trail @ Chunns Cove Rd.	Asheville	DP	2021005	17	1,120	\$455,500	\$0	\$0		\$0	\$8,500	\$9,150		\$33,850		\$404,000	1,120	\$0		\$0		\$0		\$0	
Cub Road	Asheville	TH	2018027	15	1,204	\$455,300	\$0	\$0		\$0	\$0	\$10,100		\$78,200		\$2,500		\$364,500	1,204	\$0		\$0		\$0	
Dover St. @ Merrimon Ave.	Asheville	TH	2023006	29	223	\$118,600	\$0	\$0		\$1,900	\$15,000	\$0		\$101,700	223	\$0		\$0		\$0		\$0		\$0	
Druid Drive	W. Asheville	SA	2020006	10	500	\$204,000	\$0	\$0		\$0	\$0	\$0		\$0		\$0		\$20,000		\$32,000		\$152,000	500	\$0	
East Chestnut Ave. @ Five Points	N. Asheville	SA	2015192	29	5,225	\$2,097,121	\$19,321	\$3,500		\$92,550	\$145,000	\$1,836,750	5,225	\$0		\$0		\$0		\$0		\$0		\$0	
Edgewood Rd. S @ Sweeten Crk Rd.	Asheville	TH	2021007	10	500	\$186,300	\$0	\$0		\$0	\$0	\$4,000		\$0		\$29,050		\$0		\$153,250	500	\$0		\$0	
Edwards Ave. @ US 70 Hwy.	Swannanoa	BD	2021004	29	2,400	\$963,750	\$11,000	\$0		\$6,800	\$40,350	\$905,600	2,400	\$0		\$0		\$0		\$0		\$0		\$0	
Elk Park Drive - PRP 35001	Woodfin	SA	2006028	8	2,242	\$767,046	\$50,046	\$0		\$0	\$0	\$0		\$0		\$0		\$0		\$0		\$0		\$717,000	2,242
Elkwood Ave. @ Norman Austin Dr.	Woodfin	DP	2014008	22	600	\$266,350	\$0	\$0		\$3,500	\$2,000	\$7,850		\$253,000	600	\$0		\$0		\$0		\$0		0	
Fairmont Road	N. Asheville	DP	2015017	4	3,900	\$1,715,850	\$0	\$0		\$0	\$0	\$0		\$0		\$25,000		\$0		\$10,000		\$164,850		\$1,516,000	3,900
Forestdale Drive	S. Asheville	DP	2014002	14	2,900	\$1,456,050	\$25,500	\$0		\$0	\$0	\$500		\$154,000		\$14,050		\$1,262,000	2,900	\$0		\$0		\$0	
Forest Hill Dr. @ Warwick Rd.	Asheville	SA	2014020	10	3,400	\$1,481,000	\$0	\$0		\$0	\$0	\$0		\$0		\$0		\$24,000		\$1,000		\$1,456,000	3,400	\$0	
Harmony Lane	Asheville	DP	2016103	28	670	\$308,500	\$0	\$0		\$5,000	\$0	\$303,500	670	\$0		\$0		\$0		\$0		\$0		\$0	
Hazel Mill Rd. @ Richland St.	Asheville	SA	2014016	41	3,858	\$2,528,050	\$70,350	\$124,700		\$2,333,000 3,858	\$0	\$0		\$0		\$0		\$0		\$0		\$0		\$0	

# METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY, NORTH CAROLINA TEN YEAR CAPITAL IMPROVEMENT PROGRAM

PROJECT NAME	LOCATION OF PROJECT		PROJECT NUMBER		PROJECT FOOTAGE	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS	FY 25-26	i	FY 26-27	FY 27-28	FY 28-29	FY 29-30	FY 30-	-31	FY 31-32	FY 32-33	FY 33-34	FY 34-35
							THRU FY 24	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET FOOTAGE
GENERAL SEWER REHABILI	ITATION Continue	ed																	
Hemphill Rd. @ Charlotte Hwy.	Asheville	TH	2021006	7	2,550	\$887,725	\$0	\$0		\$0	\$0	\$0	\$0	\$0		\$15,300	\$33,450	\$1,850	\$837,125 2,550
Herron Avenue	W. Asheville	SA	2014186	9	2,060	\$908,950	\$1,700	\$0		\$0	\$0	\$0	\$0	\$13,000		\$12,500	\$3,000	\$878,750 2,060	\$0
Hill Street @ Cross Place	Asheville	TH	2016249	42	641	\$299,355	\$1,525	\$2,350		\$29,550	\$265,930 641	\$0	\$0	\$0		\$0	\$0	\$0	0
Howland Rd. @ Sunset Trail	Asheville	DP	2012134	51	994	\$494,350	\$12,500	\$77,850		\$404,000 994	\$0	\$0	\$0	\$0		\$0	\$0	\$0	\$0
Innsbrook Rd. @ GPI	North Asheville	BD	2023256	28	5,730	\$2,492,875	\$40,100	\$0		\$0	\$97,000	\$306,200	\$2,049,575 5,730	\$0		\$0	\$0	\$0	\$0
Johnston Blvd. @ Providence Rd.	W. Asheville	DP	2014013	11	2,086	\$918,650	\$8,150	\$0		\$0	\$0	\$0	\$0	\$13,300		\$90,200	\$807,000 2,086	\$0	\$0
Jonestown Road @ Riverside Drive	Woodfin	тн	2018028	52	1,992	\$794,500	\$63,000	\$725,000	1,992	\$6,500	\$0	\$0	\$0	\$0		\$0	\$0	\$0	\$0
Kimberly Ave. @ Sedley Avenue	Asheville	TH	2018029	51	2,947	\$1,148,622	\$131,122	\$1,017,500	2,947	\$0	\$0	\$0	\$0	\$0		\$0	\$0	\$0	\$0
Lakeview @ Glen Falls Rd.	N. Asheville	DP	2014007	39	3,070	\$1,721,200	\$6,000	\$0	,-	\$261,500	\$190,700	\$1,263,000 3,070	\$0	\$0		\$0	\$0	\$0	\$0
Lakewood Drive @ Dudley Ave.	Asheville	BD	2015016	7	280	\$122,050	\$0	\$0		\$0	\$0	\$0	\$0	\$0		\$2,000	\$2,600	\$24,350	\$93,100 280
Lincoln Avenue	Asheville	BD	2013103	4	1,415	\$609,570	\$2,870	\$0		\$0	\$0	\$0	\$0	\$0		\$0	\$0	\$0	\$606,700 1,415
Lining Contract #10	Various	TH	2024035	NA NA	12,015	\$3,604,500	\$0	\$0		\$3,604,500 12,015	\$0	\$0	\$0	\$0		\$0	\$0	\$0	\$0
Logan Avenue	W. Asheville	SA	2017256	48	1,623	\$962,137	\$59,200	\$87,437		\$815,500 1,623	90	\$0	<b>\$</b> 0	\$0		\$0	\$0	\$0	<b>%</b> 0
Louisiana Avenue	W. Asheville	DP	2015174	12	2,150	\$1,023,500	\$0	\$0		\$0	\$0	\$0	\$0	\$15.000		\$0	\$1,008,500 2,150	\$0	\$0
Lower Glendale Ave.	E. Asheville	BD	2012083	23	2,716	\$1,449,700	\$6,650	\$0		\$0	\$16,800	\$0	\$47,850	\$1,378,400	2,716	1	\$0	\$0	\$0
Manetta Rd. @ Johnson Dr.	N. Asheville	TH	2014022	24	5,340	\$2,898,787	\$364,594	\$141,150		\$224,700	\$2,168,343 5,340	\$0	φ47,000 «n	\$1,575,400	2,710	\$0	\$0	90	¢0
Maplewood Rd. @ Griffing Circle	N. Asheville	SA	2025000	51	1,850	\$884,500	\$004,354	\$15,000		\$91,600	\$777,900 1,850	\$0	\$0	90		\$0	\$0	\$0	¢0
McDowell St. @ Lily Carmichael Dr.	Asheville	SA	2023000	21	1,660	\$721,500	\$0	\$15,000		\$91,000	\$777,900 1,650	\$1,000	\$0	\$709,500	1,660	\$0	\$0	\$0	\$0
McDowell St. @ Myrtle St.	Asheville	DP	2019257	10	465	\$308,850	90	\$0		\$11,000	\$3,500	\$4,000	\$98,850	\$202,500		\$0	\$0 \$0	\$0	\$0
Meadow Road @ Train Yard	Asheville	BD	2019257	19	2,001	\$2,271,350	\$7,000	\$0		\$0	\$3,500	\$4,000	\$96,630	\$202,500	403	\$0	\$3,000	\$95,350	\$2,166,000 2,001
	Asheville	TH	2013207	0	500	\$313,950	\$6,044	\$0		\$0	\$0	\$0	\$0	\$0		\$68,360	\$4,546	\$95,550	\$235,000 500
Merrimon Ave. @ Clearview Terrace  Merrimon Ave. @ Coleman Ave.	N. Asheville	DP	2007012	6	2,800	\$313,950 \$1,282,000	\$0,044	\$0		\$0	\$0	\$0	\$0	\$0		\$08,360	\$4,546	\$0	\$1,262,000 2,800
		SA	2014109			\$1,282,000 \$1,518,750	\$0	\$0		\$0	\$0	\$0	\$0	\$24,000		\$9,500	\$20,000	\$0	\$1,262,000 2,800
Mitchell Avenue	W. Asheville	BD		8	3,360		\$0	\$0	4 400	\$0	\$0	\$0	\$0	\$24,000		\$9,500	\$79,500	\$1,405,750 3,360	\$0
Montford Ave. @ Montford Park	Asheville	BD	2017144	59	1,129	\$754,739	\$95,179	\$659,560	1,129	\$0 \$71,000	\$234 500 700	\$0	\$0	\$0		\$0	\$0	\$0	\$0
New Haw Creek @ Cisco Rd.	Asheville		2025002	54	700	\$316,200	\$0	\$10,700		\$71,000	\$234,500 700	\$0	\$0	\$0		\$0	\$0	\$0	\$0
New Haw Creek Rd. @ Dogwood Grove	E. Asheville	SA	2014021	8	3,000	\$982,775	\$8,525	\$0		\$0	\$0	\$46,000	\$20,750	\$3,000		\$0	\$0	\$904,500 3,000	\$0
New Stock Road	Weaverville	DP	2015011	23	9,020	\$5,520,900	\$36,000	\$0		\$97,000	\$97,900	\$5,290,000 9,020	\$0	\$0		\$0	\$0	\$0	\$0
North Market Street	Asheville	SA	2014019	6	1,064	\$443,300	\$3,875	\$0		\$0	\$0	\$0	\$0	\$0		\$1,425	\$500	\$0	\$437,500 1,064
North Street @ Broadway Street	Asheville	TH	2018030	12	1,067	\$459,500	\$0	\$0		\$0	\$0	\$13,000	\$0	\$42,500		\$0	\$404,000 1,067		\$0
Oakland Drive @ Church Street	Black Mountain	DP	2015177	9	575	\$241,500	\$0	\$0		\$0	\$0	\$0	\$0	\$5,000		\$3,650	\$30,350	\$202,500 575	\$0
Oakwood Street	W. Asheville	BD	2014155	9	976	\$445,350	\$0	\$0		\$0	\$0	\$0	\$7,000	\$2,600		\$0	\$41,350	\$394,400 976	\$0
Old Toll Rd. @ Blue Briar Rd.	Asheville	TH	2018032	14	185	\$81,000	\$0	\$0		\$0	\$0	\$0	\$0	\$3,500		\$10,000	\$67,500 185	\$0	\$0
Old Turnpike Rd. @ Azalea	Arden	TH	2023255	35	1,168	\$497,900	\$10,000	\$66,050		\$46,850	\$375,000 1,168	\$0	\$0	\$0		\$0	\$0	\$0	\$0
Parkwood Avenue	Woodfin	TH	2021286	31	1,165	\$453,685	\$0	\$0		\$11,485	\$9,350	\$77,850	\$355,000 1,165	\$0		\$0	\$0	\$0	\$0
Riverside Dr. @ Woodfin Ave.	Woodfin	SA	2019005	13	684	\$293,000	\$0	\$0		\$0	\$6,000	\$24,500	\$262,500 684	\$0		\$0	\$0	\$0	\$0
Riverview Drive	Asheville	BD	2013104		2,507	\$1,566,080	\$17,380	\$0		\$1,548,700 2,507	\$0	\$0	\$0	\$0		\$0	\$0	\$0	\$0
Rosewood Ave. @ Riverside Cemetery	Montford	BD	2019023	25	180	\$90,850	\$0	\$1,300		\$2,600	\$24,850	\$62,100 180	\$0	\$0		\$0	\$0	\$0	\$0
Royal Pines Drive - PRP 47009	Arden	SA	2007020	18	7,050	\$3,093,100	\$10,100	\$0		\$30,000	\$14,000	\$33,000	\$0	\$3,006,000	7,050	\$0	\$0	\$0	\$0
Sand Hill Road @ Baker Place	W. Asheville	SA	2015223	56	1,582	\$943,000	\$749,000	\$194,000	395		\$0	\$0	\$0	\$0		\$0	\$0	\$0	\$0
Starmount Drive	Asheville	SA	2023007	19	775	\$275,100	\$0	\$0		\$0	\$6,000	\$18,600	\$16,000	\$0		\$234,500 775	\$0	\$0	\$0
Starnes Avenue	Asheville	BD	2014154	7	2,871	\$1,297,700	\$0	\$0		\$0	\$0	\$0	\$0	\$17,500		\$3,400	\$0	\$84,700	\$1,192,100 2,871
Stratford Road	N. Asheville	DP	2015013	13	1,820	\$834,500	\$0	\$0		\$0	\$14,000	\$60,150	\$102,850	\$0		\$657,500 1,820	\$0	\$0	\$0
Sulphur Springs Rd. @ Covington	W. Asheville	DP	2014006	44	1,350	\$774,200	\$7,500	\$17,850		\$50,850	\$92,000	\$606,000 1,350	\$0	\$0		\$0	\$0	\$0	\$0
Sweeten Creek Rd. @ Buck Shoals Rd.	S. Asheville	BD	2014015	51	790	\$520,705	\$53,501	\$467,204	790	\$0	\$0	\$0	\$0	\$0		\$0	\$0	\$0	\$0
Sweeten Creek Rd. @ Holiday Dr.	Asheville	DP	2022022	43	3,053	\$1,229,000	\$0	\$24,000		\$18,300	\$37,000	\$38,700	\$1,111,000 3,053	\$0		\$0	\$0	\$0	\$0
Sweeten Creek Rd. @ Mills Gap Rd.	Asheville	SA	2014189	4	2,572	\$1,512,300	\$11,300	\$0		\$0	\$0	\$0	\$0	\$65,000		\$101,500	\$27,500	\$0	\$1,307,000 2,572
Tunnel Rd. @ Pleasant Ridge Dr.	E. Asheville	SA	2019006	22	350	\$127,750	\$0	\$0		\$2,500	\$1,000	\$0	\$124,250 350	\$0		\$0	\$0	\$0	\$0

### TEN YEAR CAPITAL IMPROVEMENT PROGRAM

PROJECT NAME	LOCATION OF PROJECT		PROJECT NUMBER		PROJECT FOOTAGE	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS	FY 25-2	6	FY 26	-27	FY 27-28		FY 28-2	29	FY 29-	30	FY 30	-31	FY 31	-32	FY 32-	33	FY 33	-34	FY 34-3	35
							THRU FY 24	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET FO	OTAGE	BUDGET	FOOTAGE												
GENERAL SEWER REHABI	LITATION Continu	ed										•		•													
US 70 @ Jordan Road	Swannanoa	DP	2015014	2	4,550	\$2,048,500	\$0	\$0		\$35,000		\$0		\$34,300		\$131,700		\$30,000		\$1,817,500	4,550	\$0		\$0		\$0	
Walnut St. @ N. Lexington Ave.	Asheville	DP	2017008	38	1,300	\$666,526	\$526	\$0		\$10,000		\$0		\$656,000	1,300	\$0		\$0		\$0		\$0		\$0		\$0	
Waynesville Ave. @ Brownwood Ave.	W. Asheville	SA	2014183	21	3,022	\$1,465,650	\$0	\$19,000		\$500		\$214,000		\$223,650		\$1,008,500	3,022	\$0		\$0		\$0		\$0		\$0	
Weaverville Rd. @ Reynolds Mtn.	Weaverville	TH	2018036	10	415	\$159,000	\$0	\$0		\$0		\$0		\$0		\$6,500		\$0		\$0		\$152,500	415	\$0		\$0	
W. City View Dr. @ Riverside Dr.	Asheville	DP	2024020	1;	735	\$364,630	\$33,500	\$331,130	735	\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Weston Road @ Tampa Blvd.	Skyland	BD	2015208		400	\$156,000	\$0	\$0		\$0		\$0		\$0		\$3,000		\$2,550		\$0		\$18,350		\$132,100	400	\$0	
Wildwood Park	Weaverville	DP	2015194	10	2,300	\$821,380	\$2,380	\$0		\$0		\$0		\$0		\$0		\$10,000		\$0		\$809,000	2,300	\$0		\$0	
SSD Rehab. & Replacement	Various	MS	2002101	N/A	150,000	\$51,425,000	\$5,142,500	\$5,142,500	15,000	\$5,142,500	15,000	\$5,142,500	15,000	\$5,142,500	15,000	\$5,142,500	15,000	\$5,142,500	15,000	\$5,142,500	15,000	\$5,142,500	15,000	\$5,142,500	15,000	\$5,142,500	15,000
Surveys for Design	Various	нс	2002060	N/A	N/A	\$500,000	\$0	\$50,000		\$50,000		\$50,000		\$50,000		\$50,000		\$50,000		\$50,000		\$50,000		\$50,000		\$50,000	
SUBTOTAL					335,330	\$139,009,269	\$7,279,696	\$9,837,617	23,206	\$15,275,235	35,997	\$16,197,408	36,982	\$18,128,032	40,675	\$13,531,325	35,866	\$11,967,800	29,844	\$12,354,435	31,719	\$11,533,596	29,563	\$11,089,600	29,271	\$16,957,025	41,020
Inflation per ENR Const. Cost Index	3.32%					1.0000	1.0000	1.0000		1.0332		1.0675		1.1029		1.1396		1.1774		1.2165		1.2569		1.2986		1.3417	
SUBTOTAL with inflation					335,330	\$139,009,269	\$7,279,696	\$9,837,617	23,206	\$15,782,373	35,997	\$17,290,769	36,982	\$19,994,192	40,675	\$15,419,771	35,866	\$14,090,821	29,844	\$15,028,972	31,719	\$14,496,245	29,563	\$14,400,947	29,271	\$22,751,458	41,020

PROJECT NAME	LOCATION OF PROJECT				PROJECT FOOTAGE	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS	FY 25-2	6	FY 26-	-27	FY 27	-28	FY 28	3-29	FY 29	-30	FY 30	-31	FY 31	-32	FY 32-	33	FY 33	-34	FY 34-	-35
							THRU FY 24	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE
PRIVATE SEWER REHABILIT	TATION																										
Carver Ave. @ Owenby Lane	Asheville	DP	2022253	71	0	\$57,350	\$5,000	\$47,000		\$2,850		\$2,500		\$0	0	\$0		\$0		\$0		\$0		\$0		\$0	
Douglas Place PSR	Asheville	SA	2011116	12	588	\$240,230	\$4,980	\$0		\$0		\$0		\$8,000		\$0		\$0		\$0		\$0		\$227,250	588	\$0	
Homeland Park	Asheville	TH	2016248	51	921	\$511,730	\$7,250	\$16,650		\$77,700		\$410,130	921	\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Old County Home Rd PSR	W. Asheville	SA	2015221	55	4,592	\$3,225,300	\$179,300	\$3,046,000	4,592	\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Patton Mountain - PSR	Asheville	BD	2000084	11	3,500	\$1,095,400	\$0	\$0		\$0		\$0		\$0		\$24,500		\$12,000		\$0		\$1,058,900	3,500	\$0		\$0	
SUBTOTAL					9,601	\$5,130,010	\$196,530	\$3,109,650	4,592	\$80,550	0	\$412,630	921	\$8,000	0	\$24,500	0	\$12,000	0	\$0	0	\$1,058,900	3,500	\$227,250	588	\$0	0
Inflation per ENR Const. Cost Index	3.32%					1.0000	1.0000	1.0000		1.0332	2	1.0675		1.1029		1.1396		1.1774		1.2165		1.2569		1.2986		1.3417	
SUBTOTAL with inflation					9,601	\$5,130,010	\$196,530	\$3,109,650	4,592	\$83,224	0	\$440,483	921	\$8,824	0	\$27,919	0	\$14,129	0	\$0	0	\$1,330,901	3,500	\$295,107	588	\$0	0

PROJECT NAME	LOCATION OF PROJECT		PROJECT NUMBER		PROJECT FOOTAGE	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS THRU FY 24	FY 25-26	6	FY 26	i-27	FY 27	-28	FY 28	3-29	FY 29-30	FY 30-31	FY 31-32	FY 3	2-33	FY 33	3-34	FY 34-	-35
							INKU FT 24	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAG	BUDGET FOOTAGE	BUDGET FOOT	AGE BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE
TREATMENT PLANT, PUMP	STATIONS & GEI	VERAL	CAPITAL	IMPROVE	EMENTS																			
Arc Flash Labeling	District-Wide	BD	2023008	N/A	0	\$355,225	\$205,225	\$15,000		\$15,000		\$15,000		\$15,000		\$15,000	\$15,000	\$15,000	\$15,00	0	\$15,000		\$15,000	
Ash Lagoon Overflow Rehab	MSD-Treatment Plant	НС	2025031	N/A	0	\$185,000	\$0	\$185,000		\$0		\$0		\$0		\$0	\$0	\$0	S	0	\$0		\$0	
Biological Treatment	MSD-Treatment Plant	нс	2016063	N/A	0	\$247,821,725	\$699,725	\$300,500		\$(		\$0		\$0		\$0	\$50,000	\$101,500	\$25,160,00	0	\$51,635,000		\$55,475,000	
Building and Facility Rehabilitation	MSD-Treatment Plant	нс	2002068	N/A	0	\$600,000	\$60,000	\$60,000		\$60,000		\$60,000		\$60,000		\$60,000	\$60,000	\$60,000	\$60,00	0	\$60,000		\$60,000	
Carrier Bridge PS Replacement	Asheville	DP	2019045	N/A	2,800	\$110,162,227	\$2,453,927	\$14,693,300		\$34,135,000	)	\$31,100,000	2,800	\$27,780,000		\$0	\$0	\$0	\$	0	\$0		\$0	
Collection System Master Plan Update	District-Wide	НС	2020011	N/A	. 0	\$299,500	\$49,500	\$0		\$125,000	)	\$125,000		\$0		\$0	\$0	\$0	\$	0	\$0		\$0	
Flow Monitoring	MSD-Treatment Plant	SA	2008013	N/A	. 0	\$1,000,000	\$75,000	\$100,000		\$100,000	)	\$100,000		\$100,000		\$100,000	\$100,000	\$100,000	\$100,00	0	\$100,000		\$100,000	
Headworks-HRPT Facility Improv	MSD-Treatment Plant	нс	2025028	N/A	0	\$325,000	\$0	\$325,000		\$0	)	\$0		\$0		\$0	\$0	\$0	\$	0	\$0		\$0	
HVAC Rehabilitation	MSD-Treatment Plant	нс	2020051	N/A	. 0	\$110,000	\$70,000	\$20,000		\$10,000	)	\$10,000		\$10,000		\$10,000	\$10,000	\$10,000	\$10,00	0	\$10,000		\$10,000	
Hydroelectric Power Plant Rehab	MSD-Treatment Plant	TH	2021016	N/A	. 0	\$3,641,350	\$301,350	\$285,000		\$375,000	)	\$335,000		\$335,000		\$335,000	\$335,000	\$335,000	\$335,00	0	\$335,000		\$335,000	
Incinerator Rehabilitation	MSD-Treatment Plant	DP	2022057	N/A	. 0	\$5,383,225	\$3,383,225	\$2,000,000		\$0	)	\$0		\$0		\$0	\$0	\$0	\$	0	\$0		\$0	
Incinerator Ash Line Replacement	MSD-Treatment Plant	нс	2025030	N/A	500	\$400,000	\$0	\$400,000	500	\$0	)	\$0		\$0		\$0	\$0	\$0	\$	0	\$0		\$0	
Incinerator Sand Transport System	MSD Treatment Plant	TH	2024036	N/A	. 0	\$400,125	\$275,125	\$125,000		\$0		\$0		\$0		\$0	\$0	\$0	\$	0	\$0		\$0	
Interceptor Line Assess and Cleaning	District Wide	НС	2025029	N/A	143,000	\$5,180,000	\$0	\$2,590,000		\$2,590,000		\$0		\$0		\$0	\$0	\$0	\$	0	\$0		\$0	

### TEN YEAR CAPITAL IMPROVEMENT PROGRAM

PROJECT NAME	LOCATION OF PROJECT		PROJECT NUMBER		PROJECT FOOTAGE	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS	FY 25-26	•	FY 26-	-27	FY 27-28	FY 2	3-29	FY 29-30	FY 30	-31	FY 31-32	FY 32-33	FY 33-	-34	FY 34-35	
							THRU FY 24	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAG	E BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET FOO	AGE BUDGET	FOOTAGE	BUDGET FO	OOTAGE
TREATMENT PLANT, PUMP	STATIONS & GEI	VERAL	CAPITAL	IMPROVE	MENTS Co	ntinued																	
Int. Clarifier Eff. Trough Rehab	MSD - Treatment Plant	SA	2022024	N/A	0	\$4,753,849	\$1,653,849	\$2,750,000		\$350,000		\$0	\$0		\$0	\$0		\$0	\$0	\$0		\$0	
ITT Pump Station Upgrade	Henderson County	SA	2020061	N/A	2,750	\$5,779,411	\$296,649	\$825,762		\$4,425,000	2,750	\$232,000	\$0		\$0	\$0		\$0	\$0	\$0		\$0	
MSD Fleet/Warehouse Resurface	Asheville	SA	2025035	N/A	0	\$1,500,000	\$0	\$1,500,000		\$0		\$0	\$0		\$0	\$0		\$0	\$0	\$0		\$0	
Mud Creek PS Replacement	Henderson County	TH	2021073	N/A	0	\$830,000	\$120,000	\$0		\$15,000		\$95,000	\$600,000		\$0	\$0		\$0	\$0	\$0		\$0	
Plant NPW Filter System	Asheville	SA	2023011	N/A	0	\$325,000	\$100,000	\$0		\$0		\$225,000	\$0		\$0	\$0		\$0	\$0	\$0		\$0	
RBC Removal and Replacement	MSD-Treatment Plant	нс	2023029	N/A	0	\$2,357,750	\$677,750	\$840,000		\$840,000		\$0	\$0		\$0	\$0		\$0	\$0	\$0		\$0	
Solids Handling Capacity Improvements	MSD-Treatment Plant	нс	2019087	N/A	0	\$171,156,500	\$0	\$0		\$5,976,500		\$34,900,000	\$75,100,000		\$36,100,000	\$19,080,000		\$0	\$0	\$0		\$0	
South Storage Building	Arden	DP	2023009	N/A	0	\$1,646,000	\$0	\$130,000		\$1,516,000		\$0	\$0		\$0	\$0		\$0	\$0	\$0		\$0	
Weaverville PS Replacement	Weaverville	SA	2019080	N/A	18,174	\$24,479,509	\$12,090,934	\$12,388,575	12,000	\$0		\$0	\$0		\$0	\$0		\$0	\$0	\$0		\$0	
General Capital Equipment	Varies	нс	2016072	N/A	0	\$1,550,000	\$150,000	\$200,000		\$150,000		\$150,000	\$150,000		\$150,000	\$150,000		\$150,000	\$150,000	\$150,000		\$150,000	
SUBTOTAL					167,224	\$590,241,396	\$22,662,259	\$39,733,137	12,500	\$50,682,500	2,750	\$67,347,000 2,800	\$104,150,000	0	\$36,770,000	0 \$19,800,000	0	\$771,500	\$25,830,000	0 \$52,305,000	0	\$56,145,000	0
Inflation per ENR Const. Cost Index	3.32%					1.0000	1.0000	1.0000		1.0332		1.0675	1.1029		1.1396	1.1774		1.2165	1.2569	1.2986		1.3417	
SUBTOTAL with inflation					167,224	\$590,241,396	\$22,662,259	\$39,733,137	12,500	\$52,365,159	2,750	\$71,893,073 2,800	\$114,871,546	0	\$41,901,659	0 \$23,312,410	0	\$938,517	\$32,464,984	0 \$67,923,239	0	\$75,330,468	0

PROJECT NAME	LOCATION OF PROJECT		PROJECT NUMBER		PROJECT FOOTAGE	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS	FY 25-26	5	FY 26	-27	FY 27	-28	FY 2	3-29	FY 29	)-30	FY 30	-31	FY 31	1-32	FY 32	-33	FY 33	3-34	FY 34-	-35
							111101124	BUDGET	FOOTAGE																		
DESIGN, ROW, & CONSTRUC	TION MANAGEI	NENT E	XPENSES	3																							
Design, ROW, & Const. Mgmt. Exp.	MSD/ENG	HC	N/A	N/A	. 0	\$39,301,241	\$3,404,838	\$3,415,227		\$3,550,455	5	\$3,645,320		\$3,742,990		\$3,907,762	2	\$4,002,864		\$4,100,723	3	\$4,201,326	5	\$4,304,780		\$4,429,794	
SUBTOTAL					0	\$39,301,241	\$3,404,838	\$3,415,227	0	\$3,550,45	0	\$3,645,320	0	\$3,742,990	0	\$3,907,762	2 0	\$4,002,864	0	\$4,100,723	3 0	\$4,201,326	0	\$4,304,780	0	\$4,429,794	0

PROJECT NAME	LOCATION OF PROJECT		PROJECT NUMBER		PROJECT FOOTAGE	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS THRU FY 24	FY 25-2	6	FY 26	3-27	FY 27	-28	FY 2	3-29	FY 29	)-30	FY 30-	-31	FY 31	1-32	FY 32	-33	FY 33	-34	FY 34	-35
							11111011124	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE
DEVELOPER REIMBURSEME	NTS																										
Black Mtn. Annex Craigmont Rd.	Black Mountain	нс	1992173	N/A	. 0	\$0	\$0	\$0		\$	0	\$0		\$0		\$0		\$0		\$0	0	\$0		\$0		\$0	
Developer Reimbursements	Various	нс	2004051	N/A	0	\$1,083,000	\$183,000	\$100,000		\$100,00	0	\$100,000		\$100,000		\$100,000		\$100,000		\$100,000	0	\$100,000		\$100,000		\$100,000	
SUBTOTAL					0	\$1,083,000	\$183,000	\$100,000	0	\$100,00	0 0	\$100,000	0	\$100,000	0	\$100,000	0 0	\$100,000	0	\$100,000	0 0	\$100,000	0	\$100,000	0	\$100,000	0

BUDGET SUMMARY																									
PROJECT NAME		PROJECT NUMBER	PROJECT FOOTAGE	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS	FY 25-26	6	FY 26	-27	FY 27	-28	FY 2	B-29	FY 29	-30	FY 30	-31	FY 31	-32	FY 32	-33	FY 33	-34	FY 34	-35
					THRU FY 24	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE
SUBTOTAL with Inflation			552,676	\$846,698,701	\$34,086,175	\$56,270,631	40,298	\$72,489,260	38,747	\$93,420,779	40,703	\$139,503,344	40,675	\$64,535,347	40,066	\$57,233,279	39,374	\$33,711,457	40,709	\$56,689,411	40,934	\$93,744,973	39,789	\$102,611,720	41,020
CONTINGENCY						\$1,000,000																			
TOTAL			552,676	\$846,698,701	\$34,086,175	\$57,270,631	40,298	\$72,489,260	38,747	\$93,420,779	40,703	\$139,503,344	40,675	\$64,535,347	40,066	\$57,233,279	39,374	\$33,711,457	40,709	\$56,689,411	40,934	\$93,744,973	39,789	\$102,611,720	41,020

#### TEN YEAR CAPITAL IMPROVEMENT PROGRAM

FY 2025-2026 through 2034-2035

#### **MUNICIPAL SUMMARIES**

2024034

2006025

2009034

Asheville

Asheville

\$24,000

\$1,923,853

\$259,750 \$110,162,227 \$12,500

\$40,603

\$6,250

\$11,500

\$137,350

\$14,693,300

Bent Tree Rd. @ Old Toll Rd.

Braddock Way - PRP 20002

Carrier Bridge PS Replacement

PROJECT NAME	LOCATION OF PROJECT		PROJECT NUMBER	PIPE RATING	PROJECT FOOTAGE	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS THRU FY 25	FY 25-26	FY 26-27	FY 27-28		FY 28-29	FY 29-30	FY 30-31	FY 31-32	FY 32-33	FY 33-34	FY 34-	-35
							THRO FT 25	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET FOO	TAGE	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET FOOTAG	E BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE
TOWN OF BLACK MOUNTAIL	ı																		
Avena Rd. @ Flat Creek Rd.	Black Mountain	TH	2021009	43	1,985	\$840,182	\$0	\$0	\$13,000	\$32,950		\$794,232 1,985	\$0	\$0	\$0	\$0	\$0	\$0	
Black Mtn. Annex Craigmont Rd.	Black Mountain	НС	1992173	N/A	0	\$0	\$0	\$0	\$0	\$0		\$0	\$0	\$0	\$0	\$0	\$0	\$0	
Oakland Drive @ Church Street	Black Mountain	DP	2015177	9	575	\$241,500	\$0	\$0	\$0	\$0		\$0	\$0	\$5,000	\$3,650	\$30,350	\$202,500 575	\$0	
Inflation per ENR Const. Cost Index	3.32%					1.0000	1.0000	1.0000	1.0332	1.0675		1.1029	1.1396	1.1774	1.2165	1.2569	1.2986	1.3417	
SUBTOTAL with inflation					2,560	\$1,081,682	\$0	\$0 0	\$13,432 0	\$35,174	0	\$875,993 1,985	\$0 0	\$5,887	0 \$4,440 0	\$38,146	\$262,966 575	\$0	0
PROJECT NAME	LOCATION OF PROJECT		PROJECT NUMBER	PIPE RATING	PROJECT FOOTAGE	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS THRU FY 25	FY 25-26	FY 26-27	FY 27-28		FY 28-29	FY 29-30	FY 30-31	FY 31-32	FY 32-33	FY 33-34	FY 34-	-35
							11111011120	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET FOO	TAGE	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET FOOTAG	E BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE
TOWN OF BILTMORE FORES	T													•	·	•	· .		
Four Mile Creek WW (CDM #1)	Biltmore Forest	BD	2001193	8	3,400	\$1,423,400	\$0	\$0	\$0	\$0		\$0	\$0	\$24,000	\$3,400	\$45,000	\$1,351,000 3,400	\$0	
Inflation per ENR Const. Cost Index	3.32%					1.0000	1.0000	1.0000	1.0332	1.0675		1.1029	1.1396	1.1774	1.2165	1.2569	1.2986	1.3417	
SUBTOTAL with inflation					3,400	\$1,423,400	\$0	\$0 0	\$0 0	\$0	0	\$0 0	\$0 0	\$28,257	0 \$4,136 0	\$56,559 0	\$1,754,408 3,400	\$0	0
PROJECT NAME	LOCATION OF PROJECT		PROJECT NUMBER	PIPE RATING	PROJECT FOOTAGE	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS THRU FY 24	FY 25-26	FY 26-27	FY 27-28		FY 28-29	FY 29-30	FY 30-31	FY 31-32	FY 32-33	FY 33-34	FY 34-	-35
BUNCOMBE COUNTY								BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET FOO	TAGE	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET FOOTAG	E BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE
Atkins Street	Arden	BD	2014012	40	1.833	\$771,930	85 400	<u></u>	60			\$2,600	\$49,850	\$714,000 1,83	0 00	1 00	1 0	00	
Old Turnpike Rd. @ Azalea	Arden	TH	2023255	19	1,168	\$497,900	\$5,480 \$10,000	\$66,050	\$46,850	\$375,000	1 160	\$2,000	\$49,650	\$714,000 1,63	5 \$0	\$0	\$0	\$0	
Royal Pines Drive - PRP 47009	Arden	SA	2007020	10	7.050	\$3,093,100	\$10,000	\$00,000	\$30,000	\$14,000	1,100	\$33,000	\$0	\$3,006,000 7,05	0 \$0	\$0 \$0	\$0	\$0	
South Storage Building	Arden	DP	2023009	N/A	7,000	\$1,646,000	\$0	\$130,000	\$1,516,000	\$0		\$0	\$0	\$0,000,000	\$0	\$0	\$0	\$0	
Biltmore WW (CDM #3)	Biltmore	BD	2001192	24	2,200	\$1,220,250	\$0	\$0	\$15,400	\$3,400		\$155,850	\$1,045,600 2,200	\$0	\$0	\$0	\$0	90	
Beaverdam Creek WW (CDM #10)	Buncombe County	BD	2001191	14	5,500	\$2,405,200	\$0	\$0	\$0	\$38,500		\$18,000	\$145,700	\$2,000	\$2,201,000 5,500	\$0	\$0	\$0	
Weston Road @ Tampa Blvd.	Skyland	BD	2015208	9	400	\$156,000	\$0	\$0	\$0	\$0		\$0	\$3.000	\$2.550	\$0	\$18.350	\$132.100 400	\$0	
Swannanoa Equalization Tank	Swannanoa	HC	2019046	N/A	0	\$35,047,859	\$8,748	\$75,000	\$516,111	\$0		\$0	\$0	\$0	\$0	\$0	\$0	\$0	
Asheville Rd. @ US Hwy 70	Swannanoa	TH	2023005	17	5,470	\$2,458,210	\$0	\$0	\$0	\$43,760		\$15,000	\$114,900	\$22,850	\$2,261,700 5,470	\$0	\$0	\$0	
Edwards Ave. @ US 70 Hwy.	Swannanoa	BD	2021004	29	2,400	\$963,750	\$11,000	\$0	\$6,800	\$40,350		\$905,600 2,400	\$0	\$0	\$0	\$0	\$0	\$0	
US 70 @ Jordan Road	Swannanoa	DP	2015014	23	4,550	\$2,048,500	\$0	\$0	\$35,000	\$0		\$34,300	\$131,700	\$30,000	\$1,817,500 4,550	\$0	\$0	\$0	
Inflation per ENR Const. Cost Index	3.32%					1.0000	1.0000	1.0000	1.0332	1.0675		1.1029	1.1396	1.1774	1.2165	1.2569	1.2986	1.3417	
SUBTOTAL with inflation					30,571	\$50,308,699	\$45,328	\$271,050 0	\$2,238,078	\$549,774	1,168	\$1,284,212 2,400	\$1,698,801 2,200	\$4,447,490 8,88	3 \$7,639,763 15,520	\$23,064 0	\$171,545 400	\$0	0
PROJECT NAME	LOCATION OF PROJECT		PROJECT NUMBER	PIPE RATING	PROJECT FOOTAGE	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS THRU FY 24	FY 25-26	FY 26-27	FY 27-28		FY 28-29	FY 29-30	FY 30-31	FY 31-32	FY 32-33	FY 33-34	FY 34-	
								BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET FOO	TAGE	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET FOOTAG	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE
CITY OF ASHEVILLE																			
Adams Street	Asheville	SA	2012126	12	2,630	\$1,157,800	\$11,800	\$0	\$0	\$0		\$0	\$16,000	\$18,000	\$80,000	\$1,032,000 2,630	\$0	\$0	
Antique Lane @ Canie Creek	Asheville	DP	2022023	14	6,039	\$2,471,000	\$0	\$50,000	\$1,000	\$213,300		\$34,700	\$2,172,000 6,039	\$0	\$0	\$0	\$0	\$0	
Arlington Street	Asheville	DP	2015008	15	3,230	\$1,452,000	\$0	\$0	\$0	\$0		\$0	\$20,000	\$1,000	\$15,000	\$1,416,000 3,230	\$0	\$0	
Beale Road at Copney Lane	Asheville	DP	2009129	40	5,430	\$2,344,375	\$24,025	\$185,000	\$116,350	\$2,019,000	5,430	\$0	\$0	\$0	\$0	\$0	\$0	\$0	

\$1,667,400

\$253,500

\$78,500

#### TEN YEAR CAPITAL IMPROVEMENT PROGRAM

FY 2025-2026 through 2034-2035

#### MUNICIPAL SUMMARIES

PROJECT NAME	LOCATION OF PROJECT		PROJECT NUMBER	PIPE	PROJECT	TOTAL ESTIMATED COST	TOTAL EST.	FY 25-	26	FY 26-27	FY 27-28		FY 28	3-29	FY 29-	30	FY 30-3	1	FY 31-32	FY 32	2-33	FY 33-34	FY 34-35
	PROJECT	WGK.	NUMBER	RATING	FOOTAGE	ESTIMATED COST	THRU FY 24	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET FO	OOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET F	OOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAG	BUDGET FOOTAGE
CITY OF ASHEVILLE Contin	nued																						
Carver Ave. @ Owenby Lane	Asheville	DP	2022253	71	1 (	\$57,350	\$5,000	\$47,000		\$2,850	\$2,500		\$0	0	\$0		\$0		\$0	\$(		\$0	\$0
Central Ave. @ I-240	Asheville	SA	2014180	37	7 1,224	\$1,020,750	\$6,000	\$2,000		\$25,500	\$987,250	1,224	\$0		\$0		\$0		\$0	\$(	)	\$0	\$0
Chatham Road	Asheville	SA	2015019	19	9 1,330	\$627,925	\$4,800	\$53,500		\$16,000	\$553,625	1,330	\$0		\$0		\$0		\$0	\$(	)	\$0	\$0
Chester Pl. @ Cranford Rd.	Asheville	TH	2019026	7	7 1,025	\$426,100	\$0	\$0		\$0	\$0		\$0		\$0		\$0		\$90,900	\$45,700	)	\$0	\$289,500 1,025
Covewood Trail @ Chunns Cove Rd.	Asheville	DP	2021005	17	7 1,120	\$455,500	\$0	\$0		\$0	\$8,500		\$9,150		\$33,850		\$404,000	1,120	\$0	\$0	)	\$0	\$0
Cub Road	Asheville	TH	2018027	15	5 1,204	\$455,300	\$0	\$0		\$0	\$0		\$10,100		\$78,200		\$2,500		\$364,500 1,204	\$0	)	\$0	\$0
Dingle Creek Interceptor	Asheville	TH	2006010	8	8 7,871	\$3,120,957	\$92,957	\$0		\$0	\$0		\$0		\$0		\$0		\$0	\$3,028,000	7,871	\$0	\$0
Douglas Place PSR	Asheville	SA	2011116	12	2 588	\$240,230	\$4,980	\$0		\$0	\$0		\$8,000		\$0		\$0		\$0	\$(	)	\$227,250 58	\$0
Dover St. @ Merrimon Ave.	Asheville	TH	2023006	29	9 223	\$118,600	\$0	\$0		\$1,900	\$15,000		\$0		\$101,700	223	\$0		\$0	\$0		\$0	\$0
Edgewood Rd. S @ Sweeten Crk Rd.	Asheville	TH	2021007	10	0 500	\$186,300	\$0	\$0		\$0	\$0		\$4,000		\$0		\$29,050		\$0	\$153,250	500	\$0	\$0
Forest Hill Dr. @ Warwick Rd.	Asheville	SA	2014020	10	0 3,400	\$1,481,000	\$0	\$0		\$0	\$0		\$0		\$0		\$0		\$24,000	\$1,000	D	\$1,456,000 3,40	\$0
Harmony Lane	Asheville	DP	2016103	28	8 670	\$308,500	\$0	\$0		\$5,000	\$0		\$303,500	670	\$0		\$0		\$0	\$(	)	\$0	\$0
Hazel Mill Rd. @ Richland St.	Asheville	SA	2014016	41	1 3,858	\$2,528,050	\$70,350	\$124,700		\$2,333,000 3,858	\$0		\$0		\$0		\$0		\$0	\$6	D	\$0	\$0
Hemphill Rd. @ Charlotte Hwy.	Asheville	TH	2021006	7	7 2,550	\$887,725	\$0	\$0		\$0	\$0		\$0		\$0		\$0		\$15,300	\$33,450		\$1,850	\$837,125 2,550
Hill Street @ Cross Place	Asheville	TH	2016249	42	2 641	\$299,355	\$1,525	\$2,350		\$29,550	\$265,930	641	\$0		\$0		\$0		\$0	\$0		\$0	0
Homeland Park	Asheville	TH	2016248	51	1 921	\$511,730	\$7,250	\$16,650		\$77,700	\$410,130	921	\$0		\$0		\$0		\$0	\$0		\$0	\$0
Howland Rd. @ Sunset Trail	Asheville	DP	2012134	51	1 994	\$494,350	\$12,500	\$77,850		\$404,000 994	\$0		\$0		\$0		\$0		\$0	\$0		\$0	\$0
Kimberly Ave. @ Sedley Avenue	Asheville	TH	2018029	51	1 2,947	\$1,148,622	\$131,122	\$1,017,500	2,947	\$0	\$0		\$0		\$0		\$0		\$0	\$(	)	\$0	\$0
Lakewood Drive @ Dudley Ave.	Asheville	BD	2015016	7	7 280	\$122,050	\$0	\$0		\$0	\$0		\$0		\$0		\$0		\$2,000	\$2,600		\$24,350	\$93,100 280
Lincoln Avenue	Asheville	BD	2013103	4	4 1,415	\$609,570	\$2,870	\$0		\$0	\$0		\$0		\$0		\$0		\$0	\$(		\$0	\$606,700 1,415
Lower Swannanoa Interceptor	Asheville	BD	2004040		9 6,980	\$18,538,379		\$0		\$0	so		\$436,250		\$130,000		\$8,850,206	3,490	\$8,871,206 3,490	S		\$0	\$0
McDowell St. @ Lily Carmichael Dr.	Asheville	SA	2021011	21	1 1,660			\$0		\$11,000	\$0		\$1,000		\$0		\$709,500	1.660	\$0	\$(		\$0	\$0
McDowell St. @ Myrtle St.	Asheville	DP	2019257	10	9 465	\$308,850		\$0		\$0	\$3,500		\$4,000		\$98,850		\$202,500	465	\$0	\$(		\$0	\$0
Meadow Road @ Train Yard	Asheville	BD	2015207	1	6 2.001			00		\$0	\$0		φ+,000 \$0		\$0,000		\$0	400	\$0	\$3.000		\$95,350	\$2,166,000 2,001
Merrimon Ave. @ Clearview Terrace	Asheville	TH	2007012		6 500	.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		00		\$0	\$0		\$0		90		\$0		\$68,360	\$4,546		\$0	\$235,000 500
Montford Ave. @ Montford Park	Asheville	BD	2017144	50	9 1,129			\$659,560	1,129	\$0	\$0		\$0		90		\$0		\$0	\$1,540		\$0	\$0
	Asheville	BD	2025002	5.	4 700			\$10,700	1,120	\$71,000	\$234,500	700	e0		60		00		¢0	0,	,	ф0 Ф0	60
New Haw Creek @ Cisco Rd.  North Market Street	Asheville	SA	2014019	32	6 1,064			\$10,700		\$71,000	\$234,500	700	\$0		\$0 en		Φ0		\$1,425	\$500		\$0	\$437,500 1,064
		TH	2014019	4	2 1,067			\$0		\$0	\$0		\$13,000		\$0 en		\$42,500		\$1,425	\$404,000		\$0	\$437,500 1,004
North Street @ Broadway Street  Old Toll Rd. @ Blue Briar Rd.	Asheville Asheville	TH	2018032	12	4 185			\$0		\$0	\$0		\$13,000		\$0 en		\$42,500		\$10,000	\$404,000		\$0	\$0
Patton Mountain - PSR	Asheville	BD	2010032	12	1 3,500	,		\$0		\$0	\$0		\$0		\$24,500		\$12,000		\$10,000	\$1,058,900		\$0	\$0
	Asheville	BD	2013104	-	4 2,507			\$0		\$1,548,700 2,507	50		\$0		\$24,500		\$12,000		\$0	\$1,050,900	3,500	\$0	\$0
Riverview Drive		BD		54				\$0					\$0		\$0	0.000	\$0	0.040	\$0	30	,	\$0	\$0
South Swannanoa WW (CDM #4)	Asheville		2001195	36	6 8,040			\$0		\$57,000	\$6,000		\$102,350		\$1,467,700	2,000	\$4,441,410	6,040	\$0	\$(	,	\$0	\$0
Starmount Drive	Asheville	SA	2023007	15	9 775			\$0		\$0	\$6,000		\$18,600		\$16,000		\$0		\$234,500 775	\$(	,	\$0	\$0
Starnes Avenue	Asheville	BD	2014154	1	7 2,871			\$0		\$0	\$0		\$0		\$0		\$17,500		\$3,400	\$(	,	\$84,700	\$1,192,100 2,871
Sweeten Creek Rd. @ Mills Gap Rd.	Asheville	SA	2014189	4	4 2,572					\$0	\$0		\$0		\$0		\$65,000		\$101,500	\$27,500	,	\$0	\$1,307,000 2,572
Sweeten Creek Rd. @ Holiday Dr.	Asheville	DP	2022022	43	3 3,053			\$24,000		\$18,300	\$37,000		\$38,700		\$1,111,000	3,053	\$0		\$0	\$0	,	\$0	\$0
Town Branch Int - Phase III	Asheville	DP	2017158	10	0 3,600			\$0		\$0	\$0		\$0		\$0		\$28,000		\$9,000	\$160,850	)	\$2,513,000 3,60	
W. City View Dr. @ Riverside Dr.	Asheville	DP	2024020	13	3 735			\$331,130	735	\$0	\$0		\$0		\$0		\$0		\$0	\$(	J	\$0	\$0
Walnut St. @ N. Lexington Ave.	Asheville	DP	2017008	38	8 1,300			\$0		\$10,000	\$0		\$656,000	1,300	\$0		\$0		\$0	\$(		\$0	\$0
Lower Glendale Ave.	E. Asheville	BD	2012083	23	3 2,716					\$0	\$16,800		\$0		\$47,850		\$1,378,400	2,716	\$0	\$(		\$0	\$0
New Haw Creek Rd. @ Dogwood Grove	E. Asheville	SA	2014021		8 3,000			\$0		\$0	\$0		\$46,000		\$20,750		\$3,000		\$0	\$(	0	\$904,500 3,00	
Tunnel Rd. @ Pleasant Ridge Dr.	E. Asheville	SA	2019006	22	2 350			\$0		\$2,500	\$1,000		\$0		\$124,250	350	\$0		\$0	\$(		\$0	\$0
Rosewood Ave. @ Riverside Cemetery	Montford	BD	2019023	25	5 180	, , , , , , , , , , , , , , , , , , , ,		\$1,300		\$2,600	\$24,850		\$62,100		\$0		\$0		\$0	\$0		\$0	\$0
East Chestnut Ave. @ Five Points	N. Asheville	SA	2015192	29	9 5,225			\$3,500		\$92,550	\$145,000		\$1,836,750	5,225	\$0		\$0		\$0	\$0		\$0	\$0
Fairmont Road	N. Asheville	DP	2015017	- 4	4 3,900			\$0		\$0	\$0		\$0		\$0		\$25,000		\$0	\$10,000	D	\$164,850	\$1,516,000 3,900
Innsbrook Rd. @ GPI	N. Asheville	BD	2023256	28	8 5,730			\$0		\$0	\$97,000		\$306,200		\$2,049,575	5,730	\$0		\$0	\$(	D	\$0	\$0
Lakeview @ Glen Falls Rd.	N. Asheville	DP	2014007	39	9 3,070	\$1,721,200		\$0		\$261,500	\$190,700		\$1,263,000	3,070	\$0		\$0		\$0	\$0	D	\$0	\$0
Manetta Rd. @ Johnson Dr.	N. Asheville	TH	2014022	24	4 5,340	\$2,898,787	\$364,594	\$141,150		\$224,700	\$2,168,343	5,340	\$0		\$0		\$0		\$0	\$(		\$0	\$0
Maplewood Rd. @ Griffing Circle	N. Asheville	SA	2025000	51	1 1,850	\$884,500	\$0	\$15,000		\$91,600	\$777,900	1,850	\$0		\$0		\$0		\$0	\$0		\$0	\$0
Merrimon Ave. @ Coleman Ave.	N. Asheville	DP	2014009		6 2,800	\$1,282,000	\$0	\$0		\$0	\$0		\$0		\$0		\$0		\$0	\$20,000		\$0	\$1,262,000 2,800
Stratford Road	N. Asheville	DP	2015013	13	3 1,820	\$834,500	\$0	\$0		\$0	\$14,000		\$60,150		\$102,850		\$0		\$657,500 1,820	\$(	D	\$0	\$0

### TEN YEAR CAPITAL IMPROVEMENT PROGRAM

FY 2025-2026 through 2034-2035

MUNICIPAL SUMMARIES

PROJECT NAME	LOCATION OF PROJECT		PROJECT NUMBER		ROJECT	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS	FY 25-2	26	FY 26-27	FY 27	-28	FY 28	3-29	FY 29-30	FY 30	)-31	FY 31-32	FY 32	2-33	FY 33-34	FY 34	-35
	1						THRU FY 24	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE
CITY OF ASHEVILLE Continu	ıed							•								•				•			•
Bellevue Road	S. Asheville	DP	2015175	15	1,100	\$753,336	\$34,950	\$71,386		\$16,000	\$631,000	1,100	\$0		\$0	\$0		\$0	\$(	0	\$0	\$0	
Forestdale Drive	S. Asheville	DP	2014002	14	2,900	\$1,456,050	\$25,500	\$0		\$0	\$0		\$500		\$154,000	\$14,050		\$1,262,000 2,900	\$0	0	\$0	\$0	
Sweeten Creek Rd. @ Buck Shoals Rd.	S. Asheville	BD	2014015	51	790	\$520,705	\$53,501	\$467,204	790	\$0	\$0		\$0		\$0	\$0		\$0	\$0	0	\$0	\$0	
Avon Ave. @ Haywood Rd.	W. Asheville	BD	2021003	65	218	\$206,550	\$57,450	\$149,100	218	\$0	\$0		\$0		\$0	\$0		\$0	\$0	0	\$0	\$0	
Bear Creek Road	W. Asheville	SA	2011117	6	2,800	\$1,269,900	\$7,900	\$0		\$0	\$0	)	\$0		\$0	\$1,500		\$16,500	\$138,500	0	\$0	\$1,105,500	2,800
Druid Drive	W. Asheville	SA	2020006	10	500	\$204,000	\$0	\$0		\$0	\$0	)	\$0		\$0	\$0		\$20,000	\$32,000	0	\$152,000 500	\$0	
Herron Avenue	W. Asheville	SA	2014186	9	2,060	\$908,950	\$1,700	\$0		\$0	\$0		\$0		\$0	\$13,000		\$12,500	\$3,000	0	\$878,750 2,060	\$0	
Johnston Blvd. @ Providence Rd.	W. Asheville	DP	2014013	11	2,086	\$918,650	\$8,150	\$0		\$0	\$0		\$0		\$0	\$13,300		\$90,200	\$807,000	0 2,086	\$0	\$0	
Logan Avenue	W. Asheville	SA	2017256	48	1,623	\$962,137	\$59,200	\$87,437		\$815,500 1,623	\$0		\$0		\$0	\$0		\$0	\$(	0	\$0	\$0	
Louisiana Avenue	W. Asheville	DP	2015174	12	2,150	\$1,023,500	\$0	\$0		\$0	\$0		\$0		\$0	\$15,000		\$0	\$1,008,500	0 2,150	\$0	\$0	
Mitchell Avenue	W. Asheville	SA	2014185	8	3,360	\$1,518,750	\$0	\$0		\$0	\$0		\$0		\$0	\$24,000		\$9,500	\$79,500	0	\$1,405,750 3,360	\$0	
Oakwood Street	W. Asheville	BD	2014155	9	976	\$445,350	\$0	\$0		\$0	\$0		\$0		\$7,000	\$2,600		\$0	\$41,350	0	\$394,400 976	\$0	
Old County Home Rd PSR	W. Asheville	SA	2015221	55	4,592	\$3,225,300	\$179,300	\$3,046,000	4,592	\$0	\$0	)	\$0		\$0	\$0		\$0	\$0	0	\$0	\$0	
Sand Hill Road @ Baker Place	W. Asheville	SA	2015223	56	1,582	\$943,000	\$749,000	\$194,000	395		\$0	)	\$0		\$0	\$0		\$0	\$0	0	\$0	\$0	
Sulphur Springs Rd. @ Covington	W. Asheville	DP	2014006	44	1,350	\$774,200	\$7,500	\$17,850		\$50,850	\$92,000	)	\$606,000	1,350	\$0	\$0		\$0	\$0	0	\$0	\$0	
Waynesville Ave. @ Brownwood Ave.	W. Asheville	SA	2014183	28	3,022	\$1,465,650	\$0	\$19,000		\$500	\$214,000		\$223,650		\$1,008,500 3,022	\$0		\$0	\$(	0	\$0	\$0	
Inflation per ENR Const. Cost Index	3.32%					1.0000	1.0000	1.0000		1.0332	1.0675	3	1.1029		1.1396	1.1774	1	1.2165	1.2569	9	1.2986	1.3417	
SUBTOTAL with inflation					168,358	\$209,069,719	\$4,943,321	\$21,657,017	10,806	<b>\$41,845,272</b> 8,982	\$44,730,722	24,535	\$37,585,220	12,270	\$10,010,559 20,417	\$19,210,976	15,491	\$14,548,286 10,189	\$12,039,125	5 23,219	\$10,781,946 17,484	\$14,822,606	23,778
											1				ı								
PROJECT NAME	LOCATION OF PROJECT		PROJECT NUMBER		ROJECT	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS	FY 25-2	26	FY 26-27	FY 27	-28	FY 28	3-29	FY 29-30	FY 30	)-31	FY 31-32	FY 32	2-33	FY 33-34	FY 34	-35
	1 KOSES 1		NO III DEIX	TOTAL TO	OOTAGE	TOTAL AT LES GOOT	THRU FY 24	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE
HENDERSON COUNTY																							
ITT Pump Station Upgrade	Henderson County	SA	2020061	N/A	2,750	\$5,779,411	\$296,649	\$825,762		\$4,425,000 2,750	\$232,000	)	\$0		\$0	\$0		\$0	\$0	0	\$0	\$0	
Mud Creek PS Replacement	Henderson County	TH	2021073	N/A	0	\$830,000	\$120,000	\$0		\$15,000	\$95,000		\$600,000		\$0	\$0		\$0	\$0	0	\$0	\$0	
Inflation per ENR Const. Cost Index	3.32%					1.0000	1.0000	1.0000		1.0332	1.0675		1.1029		1.1396	1.1774		1.2165	1.2569	9	1.2986	1.3417	
SUBTOTAL with inflation					2,750	\$6,609,411	\$416,649	\$825,762	0	\$4,587,408 2,750	\$349,073	0	\$661,766	0	\$0 0	\$0	0	\$0 0	\$0	0 0	\$0 0	\$0	0
PROJECT NAME	LOCATION OF PROJECT	PROJ. P	PROJECT NUMBER		ROJECT OOTAGE E	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS THRU FY 24	FY 25-2	26	FY 26-27	FY 27	-28	FY 28	3-29	FY 29-30	FY 30	)-31	FY 31-32	FY 32	2-33	FY 33-34	FY 34	-35
							INKU FT 24	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE
TOWN OF WEAVERVILLE	•		'																				
New Stock Road	Weaverville	DP	2015011	23	9,020	\$5,520,900	\$36,000	\$0		\$97,000	\$97,900		\$5,290,000	9,020	\$0	\$0		\$0	\$(	0	\$0	\$0	
Weaverville PS Replacement	Weaverville	SA	2019080	N/A	18,174	\$24,479,509	\$12,090,934	\$12,388,575	12,000	\$0	\$0		\$0		\$0	\$0		\$0	\$(	0	\$0	\$0	
Weaverville Rd. @ Reynolds Mtn.	Weaverville	TH	2018036	13	415	\$159,000	\$0	\$0		\$0	\$0		\$0		\$6,500	\$0		\$0	\$152,500	0 415	\$0	\$0	
Wildwood Park	Weaverville	DP	2015194	16	2,300	\$821,380	\$2,380	\$0		\$0	\$0		\$0		\$0	\$10,000		\$0	\$809,000	0 2,300	\$0	\$0	
Inflation per ENR Const. Cost Index	3.32%					1.0000	1.0000	1.0000		1.0332	1.0675	5	1.1029		1.1396	1.1774	1	1.2165	1.2569	9	1.2986	1.3417	
SUBTOTAL with inflation					29,909	\$30,980,789	\$12,129,314	\$12,388,575	12,000	\$100,220 0	\$104,508	0	\$5,834,570	9,020	\$7,407	\$11,774	1 0	\$0 0	\$1,208,482	2 2,715	\$0 0	\$0	0
															1								1
PROJECT NAME	LOCATION OF PROJECT				ROJECT OOTAGE E	TOTAL ESTIMATED COST	TOTAL EST. EXPENDS THRU FY 24	FY 25-2	26	FY 26-27	FY 27	-28	FY 28	3-29	FY 29-30	FY 30	)-31	FY 31-32	FY 32	2-33	FY 33-34	FY 34	-35
							111101124	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE	BUDGET FOOTAGE	BUDGET	FOOTAGE
TOWN OF WOODFIN																							
Elk Park Drive - PRP 35001	Woodfin	SA	2006028	8	2,242	\$767,046	\$50,046	\$0		\$0	\$0		\$0		\$0	\$0		\$0	\$(	0	\$0	\$717,000	2,242
Elkwood Ave. @ Norman Austin Dr.	Woodfin	DP	2014008	22	600	\$266,350	\$0	\$0		\$3,500	\$2,000		\$7,850		\$253,000 600	\$0		\$0	\$(	0	\$0	\$0	
Jonestown Road @ Riverside Drive	Woodfin	TH	2018028	52	1,992	\$794,500	\$63,000	\$725,000	1,992	\$6,500	\$0		\$0		\$0	\$0		\$0	\$(	0	\$0	\$0	
Middle Beaverdam Crk. @ I-26	Woodfin	TH	2010002	8	2,930	\$1,392,430	\$7,430	\$0		\$0	\$0		\$0		\$0	\$0		\$48,500	\$25,000	0	\$1,311,500 2,930	\$0	
Parkwood Avenue	Woodfin	TH	2021286	31	1,165	\$453,685	\$0	\$0		\$11,485	\$9,350		\$77,850		\$355,000 1,165	\$0		\$0	\$1	0	\$0	\$0	
Riverside Dr. @ Woodfin Ave.	Woodfin	SA	2019005	13	684	\$293,000	\$0	\$0		\$0	\$6,000		\$24,500		\$262,500 684	\$0		\$0	\$0	U	\$0	\$0	
Riverside Dr. @ Woodfin Ave.  Inflation per ENR Const. Cost Index	Woodfin 3.32%	SA	2019005	13	684	\$293,000 1.0000	\$0 1.0000	1.0000		1.0332	\$6,000 1.0675		\$24,500 1.1029		\$262,500 684 1.1396	1.1774	<u> </u>	1.2165	1.2569	9	\$0 1.2986	1.3417	
		SA	2019005	13	9,613		ΨΟ	\$5	1,992	i						40	1	\$0 1.2165 \$58,999 0	+	9	40	\$0 1.3417 \$962,008	2,242

### TEN YEAR CAPITAL IMPROVEMENT PROGRAM

FY 2025-2026 through 2034-2035

### MUNICIPAL SUMMARIES


PROJECT NAME	LOCATION OF PROJECT	PROJ. MGR.	PROJECT NUMBER	PIPE RATING	PROJECT FOOTAGE E	TOTAL STIMATED COST	TOTAL EST. EXPENDS THRU FY 24	FY 25-26		FY 26-27		FY 27-28		FY 28-29		FY 29-30		FY 30-31		FY 31-32		FY 32-33		FY 33-34		FY 34-35	
							11111011124	BUDGET	FOOTAGE	BUDGET FO	OTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET FO	OOTAGE								
DESIGN, ROW, & CONSTRUC	CTION MANAGEM	IENT E	XPENSES																								
Design, ROW, & Const. Mgmt. Exp.	MSD/ENG	HC	N/A	N/A	0	\$39,301,241	\$3,404,838	\$3,415,227		\$3,550,455		\$3,645,320		\$3,742,990		\$3,907,762		\$4,002,864		\$4,100,723		\$4,201,326	3	\$4,304,780		\$4,429,794	
Developer Reimbursements	Various	HC	2004051	N/A	0	\$1,083,000	\$183,000	\$100,000		\$100,000		\$100,000		\$100,000		\$100,000		\$100,000		\$100,000		\$100,000		\$100,000		\$100,000	
SUBTOTAL					0	\$40,384,241	\$3,587,838	\$3,515,227	0	\$3,650,455	0	\$3,745,320	0	\$3,842,990	0	\$4,007,762	0	\$4,102,864	0	\$4,200,723	0	\$4,301,326	0	\$4,404,780	0	\$4,529,794	0
PROJECT NAME	LOCATION OF PROJECT	PROJ. MGR.	PROJECT NUMBER	PIPE RATING	PROJECT FOOTAGE E	TOTAL STIMATED COST	TOTAL EST. EXPENDS THRU FY 24	FY 25-	26	FY 26-	27	FY 27-	28	FY 28	3-29	FY 29-	30	FY 30-31		FY 31-3	32	FY 32	-33	FY 33-	-34	FY 34-35	5
								BUDGET	FOOTAGE	BUDGET FO	OTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET FO	OOTAGE								
MISCELLANEOUS PROJECT	S AND LINE ITEM	1S																									
Arc Flash Labeling	District-Wide	BD	2023008	N/A	0	\$355,225	\$205,225	\$15,000		\$15,000		\$15,000		\$15,000		\$15,000		\$15,000		\$15,000		\$15,000		\$15,000		\$15,000	
Ash Lagoon Overflow Rehab	MSD-Treatment Plant	нс	2025031	N/A	0	\$185,000	\$0	\$185,000		\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Biological Treatment	MSD-Treatment Plant	нс	2016063	N/A	0	\$247,821,725	\$699,725	\$300,500		\$0		\$0		\$0		\$0		\$50,000		\$101,500		\$25,160,000	,	\$51,635,000		\$55,475,000	
Building and Facility Rehabilitation	MSD-Treatment Plant	нс	2002068	N/A	0	\$600,000	\$60,000	\$60,000		\$60,000		\$60,000		\$60,000		\$60,000		\$60,000		\$60,000		\$60,000	,	\$60,000		\$60,000	
Collection System Master Plan Update	District-Wide	нс	2020011	N/A	0	\$299,500	\$49,500	\$0		\$125,000		\$125,000		\$0		\$0		\$0		\$0		\$0	,	\$0		\$0	
Flow Monitoring	MSD-Treatment Plant	SA	2008013	N/A	0	\$1,000,000	\$75,000	\$100,000		\$100,000		\$100,000		\$100,000		\$100,000		\$100,000		\$100,000		\$100,000	,	\$100,000		\$100,000	
General Capital Equipment	Various	нс	2016072	N/A	0	\$1,550,000	\$150,000	\$200,000		\$150,000		\$150,000		\$150,000		\$150,000		\$150,000		\$150,000		\$150,000		\$150,000		\$150,000	
Headworks-HRPT Facility Improv	MSD-Treatment Plant	нс	2025028	N/A	0	\$325,000	\$0	\$325,000		\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0	
HVAC Rehabilitation	MSD-Treatment Plant	нс	2020051	N/A	0	\$110,000	\$70,000	\$20,000		\$10,000		\$10,000		\$10,000		\$10,000		\$10,000		\$10,000		\$10,000		\$10,000		\$10,000	
Hydroelectric Power Plant Rehab	MSD-Treatment Plant	TH	2021016	N/A	0	\$3,641,350	\$301,350	\$285,000		\$375,000		\$335,000		\$335,000		\$335,000		\$335,000		\$335,000		\$335,000		\$335,000		\$335,000	
Incinerator Ash Line Replacement	MSD-Treatment Plant	нс	2025030	N/A	500	\$400,000	\$0	\$400,000	500	\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Incinerator Rehabilitation	MSD-Treatment Plant	DP	2022057	N/A	0	\$5,383,225	\$3,383,225	\$2,000,000		\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Incinerator Sand Transport System	MSD Treatment Plant	TH	2024036	N/A	0	\$400,125	\$275,125	\$125,000		\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Int. Clarifier Eff. Trough Rehab	MSD - Treatment Plant	SA	2022024	N/A	0	\$4,753,849	\$1,653,849	\$2,750,000		\$350,000		\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Interceptor Line Assess and Cleaning	District Wide	нс	2025029	N/A	143,000	\$5,180,000	\$0	\$2,590,000		\$2,590,000		\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Lining Contract #10	Various	TH	2024035	NA	12,015	\$3,604,500	\$0	\$0		\$3,604,500	12,015	\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0	
MSD Fleet/Warehouse Resurface	District-Wide	SA	2025035	N/A	0	\$1,500,000	\$0	\$1,500,000		\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Plant NPW Filter System	MSD-Treatment Plant	SA	2023011	N/A	0	\$325,000	\$100,000	\$0		\$0		\$225,000		\$0		\$0		\$0		\$0		\$0		\$0		\$0	
RBC Removal and Replacement	MSD-Treatment Plant	нс	2023029	N/A	0	\$2,357,750	\$677,750	\$840,000		\$840,000		\$0		\$0		\$0		\$0		\$0		\$0		\$0		\$0	
Solids Handling Capacity Improvements	MSD-Treatment Plant	нс	2019087	N/A	0	\$171,156,500	\$0	\$0		\$5,976,500		\$34,900,000		\$75,100,000		\$36,100,000		\$19,080,000		\$0		\$0		\$0		\$0	
SSD Rehab. & Replacement	Various	MS	2002101	N/A	150,000	\$51,425,000	\$5,142,500	\$5,142,500	15,000	\$5,142,500	15,000	\$5,142,500	15,000	\$5,142,500	15,000	\$5,142,500	15,000	\$5,142,500	15,000	\$5,142,500	15,000	\$5,142,500	15,000	\$5,142,500	15,000	\$5,142,500	15,000
Surveys for Design	Various	нс	2002060	N/A	N/A	\$500,000	\$0	\$50,000		\$50,000		\$50,000		\$50,000		\$50,000		\$50,000		\$50,000		\$50,000		\$50,000		\$50,000	
Inflation per ENR Const. Cost Index	3.32%					1.0000	1.0000	1.0000		1.0332		1.0675		1.1029		1.1396		1.1774		1.2165		1.2569		1.2986		1.3417	
SUBTOTAL with inflation					305,515	\$502,873,749	\$12,843,249	\$16,888,000	15,500	\$20,032,198	27,015	\$43,887,686	15,000	\$89,297,048	15,000	\$47,818,830	15,000	\$29,426,031	15,000	\$7,255,110	15,000	\$38,991,287	15,000	\$74,666,216	15,000	\$82,297,312	15,000


E	BUDGET SUMMARY																											
	PROJECT NAME	PROJECT NAME LOCATION OF PROJ. PROJECT MGR. NUMBER	DJ. PROJECT	PIPE RATING	PROJECT FOOTAGE	TOTAL ESTIMATED COS	TOTAL EST.			FY 26-27		FY 27-28		FY 28-29		FY 29-30		FY 30-31		FY 31-32		FY 32-33		FY 33-34		FY 34-35		
								IHRU FT 24	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE	BUDGET	FOOTAGE
s	UBTOTAL with Inflation					552,676	\$846,698,701	\$34,086,175	\$56,270,631	40,298	\$72,489,260	38,747	\$93,420,779	40,703	\$139,503,344	40,675	\$64,535,347	40,066	\$57,233,279	39,374	\$33,711,457	40,709	\$56,689,411	40,934	\$93,744,973	39,789	\$102,611,720	41,020
С	ONTINGENCY								\$1,000,000																			
	TOTAL					552,676	\$846,698,701	\$34,086,175	\$57,270,631	40,298	\$72,489,260	38,747	\$93,420,779	40,703	\$139,503,344	40,675	\$64,535,347	40,066	\$57,233,279	39,374	\$33,711,457	40,709	\$56,689,411	40,934	\$93,744,973	39,789	\$102,611,720	41,020


Fiscal Years 2026—2035


# **Project Schedule**






















Fiscal Years 2026—2035

# Interceptor & Wet Weather Projects








# Metropolitan Sewerage District of Buncombe County, North Carolina CAPITAL IMPROVEMENT PROGRAM

#### BUDGET DATA SHEET - FY 2025 - 2026


			<u> </u>	
PROJECT:	Beaverdam Creek WW (CDM #10)	LOCATION:	Buncombe County	
TYPE:	Wet Weather Int.	PIPE RATING:	14	
PROJECT NO.	2001191	TOTAL LF:	5,500	
PROJECT BUDGET:	\$2,405,200.00	PROJECT ORIGIN:	CDM Master Plan	
		<u>''</u>		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING			T T	
55320 - SURVEY - DESIGN	#20 F00 00			
55330 - DESIGN	\$38,500.00			
55340 - PERMITS	\$2,000.00			
55350 - SPECIAL STUDIES	Ψ2,000.00			
55360 - EASEMENT PLATS	\$19,700.00			
55370 - LEGAL FEES	\$24,000.00			
55380 - ACQUISITION SERVICES	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,			
55390 - COMPENSATION	\$120,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$2,190,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$5,000.00			
55450 - SURVEY - ASBUILT	\$6,000.00			
TOTAL AMOUNT	\$2,405,200.00	\$0.00	\$0.00	\$0.00
ENGINEER:	MSD	BD	ESTIMATED BUD	GETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 21 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$38,500.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$18,000.00
INSPECTION:	MSD		FY 29-30	\$145,700.00
			FY 30-31	\$2,000.00
			FY 31-32	\$2,201,000.00
	identified as a potential rehabilitation projec Master Plan developed by CDM. It is local			\$0.00
	Representation of the first of	ted iii tile NOITII ASHEVIIIE	FY 33-34	\$0.00
			FY 34-35	\$0.00
SPECIAL PROJECT NOTES:	CDM Master Plan Project #10			



# Metropolitan Sewerage District of Buncombe County, North Carolina CAPITAL IMPROVEMENT PROGRAM

#### BUDGET DATA SHEET - FY 2025 - 2026


PROJECT:	Biltmore WW (CDM #3)	LOCATION:	Biltmore	
	Entinois VVV (OEM #O)	200AHOH.	Bitanore	
TYPE:	Wet Weather Int.	PIPE RATING:	24	
PROJECT NO.	2001192	TOTAL L.F.:	2,200	
PROJECT BUDGET:	\$1,220,250.00	PROJECT ORIGIN:	CDM Master Plan	
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		ì	1	
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN 55330 - DESIGN	\$15,400.00			
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	04.050.00			
55370 - LEGAL FEES	\$4,250.00 \$5,000.00			
55380 - ACQUISITION SERVICES	\$5,000.00			
55390 - COMPENSATION	\$150,000.00			
55400 - APPRAISAL	7.51,000.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,037,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$5,000.00			
55450 - SURVEY - ASBUILT	\$3,600.00			
TOTAL AMOUNT	\$1,220,250.00	\$0.00	\$0.00	\$0.00
			II	
ENGINEER:	MSD	BD		GETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	#PLATS: [ 4 ]	FY 26-27	\$15,400.00
CONTRACTOR:	MCD		FY 27-28	\$3,400.00
CONSTRUCTION ADM: INSPECTION:	MSD		FY 28-29 FY 29-30	\$155,850.00
INSPECTION.	INIOD		FY 30-31	\$1,045,600.00
			FY 31-32	\$0.00
PROJECT DESCRIPTION: This was	dentified as a potential rehabilitation projec	t to improve wet weather		\$0.00
flow conveyance, as specified in the	e Master Plan developed by CDM. It is local tis comprised of 2,200 LF of 18-inch diameter	ated in the Biltmore area		\$0.00 \$0.00
поат пе оманнаноа ппетоерког, апс	ins comprised of 2,200 LF of To-Intel diameter	ы ыре.	FY 34-35	\$0.00
SPECIAL PROJECT NOTES:	CDM Master Plan Project #3. This project o	verlaps with Caledonia Roa	d (MSD Project # 2014153), v	
I	was completed 2023.			




# Metropolitan Sewerage District of Buncombe County, North Carolina CAPITAL IMPROVEMENT PROGRAM

#### BUDGET DATA SHEET - FY 2025 - 2026


PROJECT:	Dingle Creek Interceptor	LOCATION:	Asheville	
PROJECT.	Diligie Creek interceptor	LOCATION.	Asheville	
TYPE:	Interceptor	PIPE RATING:	8	
PROJECT NO.	2006010	TOTAL LF:	7,871	
PROJECT BUDGET:	\$3,120,957.00	PROJECT ORIGIN:	SSO's, Work Orders, Line	e Condition
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$7,516.00	\$7,516.00		
55330 - DESIGN				
55340 - PERMITS	\$610.00	\$610.00		
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS 55370 - LEGAL FEES	\$3,982.00			
55380 - ACQUISITION SERVICES	\$7,313.00	\$7,313.00		
55390 - ACQUISITION SERVICES	400.047.00			
55400 - APPRAISAL	\$66,947.00			
55410 - CONDEMNATION	\$1,250.00			
55420 - CONSTRUCTION	\$5,339.00 \$3,000,000.00			
55430 - CONST. CONTRACT ADM.	ψ5,000,000.00			
55440 - TESTING	\$8,000.00			
55450 - SURVEY - ASBUILT	\$20,000.00			
TOTAL AMOUNT	\$3,120,957.00	1	\$0.00	\$0.00
ENGINEER:	MSD	TH	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 10 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
DDO IFOT DECODIDATION. This prois	et is leasted along Dingle Creek between the	Dive Didge Deglevery and	FY 31-32	\$0.00
the Ramble Subdivision. The existing	ct is located along Dingle Creek between the ng 18-inch vitrified clay pipe main will be rep	выие кіаде Рагкway and blaced with a new 18-inch		\$3,028,000.00
	nate length of this project is 7,871 LF.		FY 33-34	\$0.00
			FY 34-35	\$0.00




PROJECT:	Four Mile Creek WW (CDM #1)	LOCATION:	Biltmore Forest	
TYPE:	Wet Weather Int.	PIPE RATING:	8	
PROJECT NO.	2001193	TOTAL LF:	3,400	
PROJECT BUDGET:	\$1,423,400.00	PROJECT ORIGIN:	CDM Master Plan	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$24,000.00			
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$3,400.00			
55370 - LEGAL FEES	\$5,000.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$40,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,342,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$7,000.00			
TOTAL AMOUNT	\$1,423,400.00	\$0.00	\$0.00	\$0.00
ENGINEER:	MSD	BD	ESTIMATED BUD	GETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 4 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$24,000.00
			FY 31-32	\$3,400.00
PROJECT DESCRIPTION: This was flow conveyance as specified in the	identified as a potential rehabilitation projectine Master Plan developed by CDM. It is l	t to improve wet weather	FY 32-33	\$45,000.00
	s comprised of 3,400 LF of 12-inch diameter		FY 33-34	\$1,351,000.00
			FY 34-35	\$0.00
SPECIAL PROJECT NOTES:	2001 CDM Master Plan Project #1			




PROJECT:	Lower Swannanoa Interceptor	LOCATION:	Asheville	
	· ·			
ГҮРЕ:	Interceptor	PIPE RATING:	9	
PROJECT NO.	2004040	TOTAL LF:	6,980	
PROJECT BUDGET:	\$18,538,379.00	PROJECT ORIGIN:	WW SSO's at Splitter bo	х
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
5310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$61,879.00	\$14,879.00	\$47,000.00	
55330 - DESIGN	\$436,250.00			
55340 - PERMITS	\$100,000.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES	\$30,000.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$17,879,000.00	\$188,588.00		
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$10,250.00	\$250.00		
55450 - SURVEY - ASBUILT	\$21,000.00			
TOTAL AMOUNT	\$18,538,379.00	\$203,717.00	\$47,000.00	\$0.0
ENGINEER:	MSD	BD	ESTIMATED BUDG	SETS - FY 27 - 35
R.O.W. ACQUISITION:		# PLATS: [ 0 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$436,250.0
NSPECTION:	MSD		FY 29-30	\$130,000.0
			FY 30-31	\$8,850,206.0
	ct is to eliminate problems associated with		FY 31-32	\$8,871,206.0
CDM Master Plan. The 2019 CDM F	tions of the line were identified for replacem PER identified approx. 6,980LF of existing 36	6-inch line to be replaced	FY 32-33	\$0.0
with new 60-inch pipe to improve co	nveyance around the confluence of the Swa	nnanoa gravity main and	FY 33-34	\$0.
Carrier Bridge force main.			FY 34-35	\$0.0




PROJECT:	Middle Beaverdam Crk. @ I-26	LOCATION:	Woodfin	
TYPE:	Interceptor	PIPE RATING:	8	
PROJECT NO.	2010002	TOTAL LF:	2,930	
	24 000 400 00		COOL- MiIr Oudous Line	O madiatana
PROJECT BUDGET:	\$1,392,430.00	PROJECT ORIGIN:	SSO's, Work Orders, Line	Condition
	FOTIMATED	TOTAL EXPENDS	FOT 2007	PUDGET
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING			T	
55320 - SURVEY - DESIGN	\$7,430.00	\$7,430.00		
55330 - DESIGN	φ1,-υυ.υυ	ψ1,700.00	+	
55340 - PERMITS	\$20,000.00			
55350 - SPECIAL STUDIES	Ψ20,000.00			
55360 - EASEMENT PLATS	\$7,500.00			
55370 - LEGAL FEES	\$7,000.00			
55380 - ACQUISITION SERVICES			1	
55390 - COMPENSATION	\$39,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,300,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$4,000.00			
55450 - SURVEY - ASBUILT	\$7,500.00			
TOTAL AMOUNT	\$1,392,430.00	\$7,430.00	\$0.00	\$0.00
			11	
ENGINEER:	MSD	ТН	ESTIMATED BUDGE	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 6 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
PROJECT DESCRIPTION: This proje	ect is located along both sides of I-26 alor	ng Beaverdam Creek. It	FY 31-32	\$48,500.00
consists of replacing a portion the 24	4-inch interceptor along Beaverdam Creek ar ceptor. These lines are in poor condition		lr .	\$25,000.0
undersized.	ceptor. These lines are in poor condition a	and the 4-inch lines are	1 1 00-04	\$1,311,500.0
			FY 34-35	\$0.00



PROJECT:	South Swannanoa WW (CDM #4)	LOCATION:	Asheville	
TYPE:	Wet Weather Int.	PIPE RATING:	36	
PROJECT NO.	2001195	TOTAL LF:	8,040	
PROJECT BUDGET:	\$6,074,460.00	PROJECT ORIGIN:	CDM Master Plan	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$57,000.00			
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$6,850.00			
55370 - LEGAL FEES	\$8,500.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$93,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$5,895,110.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$5,000.00			
55450 - SURVEY - ASBUILT	\$9,000.00			
TOTAL AMOUNT	\$6,074,460.00	\$0.00	\$0.00	\$0.00
ENGINEER:	MSD	BD	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 7 ]	FY 26-27	\$57,000.00
CONTRACTOR:			FY 27-28	\$6,000.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$102,350.00
INSPECTION:	MSD		FY 29-30	\$1,467,700.00
			FY 30-31	\$4,441,410.00
			FY 31-32	\$0.00
PROJECT DESCRIPTION: This was flow conveyance, as specified in the	identified as a potential rehabilitation projecte Master Plan developed by CDM. It is located by CDM.	t to improve wet weather ated in the Biltmore area	FY 32-33	\$0.00
	ed of 8,040 LF of 18-inch through 42-inch dia		FY 33-34	\$0.00
			FY 34-35	\$0.00



PROJECT:	Swannanoa Equalization Tank	LOCATION:	Swannanoa	
1100201.	Gwainianoa Equalization Tank	LOGATION.	Owarmanoa	
TYPE:	Wet Weather	PIPE RATING:	N/A	
PROJECT NO.	2019046	TOTAL LF:	0	
PROJECT BUDGET:	\$35,047,859.00	PROJECT ORIGIN:	CDM Preliminary Engineer	ring Report
	FOTIMATED	TOTAL EXPENDS	FOT COST	PUDCET
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING	\$51,946.00	\$1,946.00		5000
55320 - SURVEY - DESIGN	\$20,113.00	\$113.00		\$20,000.0
55330 - DESIGN	\$3,020,000.00			
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$1,300.00			
55370 - LEGAL FEES	\$20,000.00	\$6,689.00		\$5,000.0
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$500,000.00			
55400 - APPRAISAL	\$6,500.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$30,200,000.00			
55430 - CONST. CONTRACT ADM.	\$1,208,000.00			
55440 - TESTING	\$20,000.00			
55450 - SURVEY - ASBUILT				
TOTAL AMOUNT	\$35,047,859.00	\$8,748.00	\$0.00	\$75,000.0
	TDD		T	
ENGINEER: R.O.W. ACQUISITION:	TBD N/A	#PLATS: [ 1 ]	ESTIMATED BUDGE	
CONTRACTOR:	IVA	# P.EATO. [ 1 ]	FY 27-28	\$516,111.0
CONSTRUCTION ADM.:	TBD		FY 28-29	\$0.0
INSPECTION:	TBD		FY 29-30	\$0.0
INOI EOTION.	155		FY 30-31	\$0.0
PROJECT DESCRIPTION: This proje	ect is to implement the recommendations of	the French Broad/Carrier		\$0.0
Bridge Preliminary Engineering Re	port. This project will help mitigate wet	weather impacts to the		\$0.0
	peak wet weather flows. Equalizing flow wi			\$0.0
estimated costs shown are planning	g level only, and incorporate a new 8.1MG		1 1 33-34	\$0.0
station and associated piping.			FY 34-35	\$0.0
SPECIAL PROJECT NOTES:	Tank location, project map and compensation			




PROJECT:	Town Branch Int - Phase III	LOCATION:	Asheville	
TYPE:	Interceptor	PIPE RATING:	10	
PROJECT NO.	2017158	TOTAL LF:	3,600	
PROJECT BUDGET:	\$2,710,850.00	PROJECT ORIGIN:	Line Condition, I/I Issues	
	. , . ,		,	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING			T	
5320 - SURVEY - DESIGN	\$28,000.00			
55330 - DESIGN				
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES				
5360 - EASEMENT PLATS	\$8,850.00			
5370 - LEGAL FEES	\$10,000.00			
5380 - ACQUISITION SERVICES				
5390 - COMPENSATION	\$150,000.00			
5400 - APPRAISAL				
5410 - CONDEMNATION				
5420 - CONSTRUCTION	\$2,500,000.00			
5430 - CONST. CONTRACT ADM.				
5440 - TESTING	\$3,000.00			
55450 - SURVEY - ASBUILT	\$10,000.00			
TOTAL AMOUNT	\$2,710,850.00	\$0.00	\$0.00	\$0.0
			·	
NGINEER:	MSD	DP	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	#PLATS: [ 8 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
NSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$28,000.0
PROJECT DESCRIPTION: This project	ct is located in the "South Slope" area of Ash	eville. The project begins	FY 31-32	\$9,000.0
t the intersection of S. French Bro	oad Ave and Ralph St., runs north east cr	ossing Choctaw St. and	FY 32-33	\$160,850.0
AcDowell St., and ending near the ir	I ending near the intersection of Southside Ave. and Coxe Ave. The existing pipes are in ntributing to I/I that surcharges the line during heavy rains.		FY 33-34	\$2,513,000.0
condition contributing to 1/1 that	carcharges the line during neary rains.		FY 34-35	\$0.0

### Capital Improvement Program

Fiscal Years 2026—2035


# General Sewer Rehabilitation Projects









PROJECT:	Adams Street	LOCATION:	Asheville	
ГҮРЕ:	General Sewer Rehab.	PIPE RATING:	12	
PROJECT NO.	2012126	TOTAL LF:	2,630	
PROJECT BUDGET:	\$1,157,800.00	PROJECT ORIGIN:	Work Orders, Line Condi	tion
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		V		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$13,800.00	\$11,800.00		
55330 - DESIGN				
55340 - PERMITS	\$500.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$15,500.00			
55370 - LEGAL FEES	\$18,000.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$78,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,029,000.00			
55430 - CONST. CONTRACT ADM. 55440 - TESTING				
55450 - SURVEY - ASBUILT	\$1,000.00			
TOTAL AMOUNT	\$2,000.00	ii <del></del>	40.00	
TOTAL AMOUNT	\$1,157,800.00	\$11,800.00	\$0.00	\$0.00
ENGINEER:	MSD	SA	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 16 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$16,000.00
			FY 30-31	\$18,000.00
			FY 31-32	\$80,000.0
PROJECT DESCRIPTION: This project	ct is located in downtown Asheville near Sout	th French Broad Ave. and	FY 32-33	\$1,032,000.0
is comprised of 2,630 LF of 8-inch d in poor condition, and runs under sev	luctile iron pipe. The existing line is aging 6- veral houses.	-mon viumed clay pipe, is	FY 33-34	\$0.0
			FY 34-35	\$0.00




PROJECT:	Antique Lane @ Canie Creek	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	14	
PROJECT NO.	2022023	TOTAL LF:	6,039	
PROJECT BUDGET:	\$2,471,000.00	PROJECT ORIGIN:	SSO's, Work Orders, Line	Condition
		Tr.		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		)r		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$50,000.00			\$50,000.0
55330 - DESIGN				
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$30,000.00			
55370 - LEGAL FEES	\$35,000.00			
55380 - ACQUISITION SERVICES 55390 - COMPENSATION	\$124,000.00			
55400 - APPRAISAL	\$59,000.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	#0.450.000.00			
55430 - CONST. CONTRACT ADM.	\$2,150,000.00			
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$20,000.00			
TOTAL AMOUNT	\$2,471,000.00	ii	\$0.00	\$50,000.0
	7,111	,	, , , , , ,	, , , , , , , , , , , , , , , , , , , ,
ENGINEER:	MSD	DP	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	CONSULTANT	# PLATS: [ 31 ]	FY 26-27	\$1,000.0
CONTRACTOR:			FY 27-28	\$213,300.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$34,700.0
INSPECTION:	MSD		FY 29-30	\$2,172,000.0
			FY 30-31	\$0.0
PROJECT DESCRIPTION: This proje	ect is in the Starnes Cove area of west As	heville . The project runs	FY 31-32	\$0.0
along Canie Creek and north to Pis	gah View Road and south to Starnes Cove	Drive through residential	FY 32-33	\$0.0
property. The existing 6-inch and 8-inch root problems, infiltration, and over	nch clay pipes have numerous joint and structerflows.	ctural defects that has led	FY 33-34	\$0.0
in the second of			FY 34-35	\$0.0




PROJECT:	Arlington Street	LOCATION:	Asheville	
	<b>3</b>			
TYPE:	General Sewer Rehab.	PIPE RATING:	15	
PROJECT NO.	2015008	TOTAL LF:	3,230	
PROJECT BUDGET:	\$1,452,000.00	PROJECT ORIGIN:	SSO's, Work Orders, Line	● Condition
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$20,000.00			
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$1,000.00			
55370 - LEGAL FEES	\$2,000.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$13,000.00		+	
55400 - APPRAISAL				
55410 - CONDEMNATION 55420 - CONSTRUCTION				
55430 - CONST. CONTRACT ADM.	\$1,400,000.00			
55440 - TESTING				
55450 - SURVEY - ASBUILT	\$4,000.00			
TOTAL AMOUNT	\$12,000.00 \$1,452,000.00	i <del></del>	0 \$0.00	\$0.0
	\$1,452,000.00	<u>JI \$0.0</u>	<u>0  \$0.00 </u>	\$0.0
ENGINEER:	MSD	DP	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 1 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$20,000.0
			FY 30-31	\$1,000.0
			FY 31-32	\$15,000.0
PROJECT DESCRIPTION: This proje	ct runs along Arlington St. in downtown Ash Mountain Rd. There are numerous structural	eville. The project begin	S FY 32-33	\$1,416,000.0
which contribute to I/I issues.	would not the find the finding out structural	Propietina Mittilli tile illie	FY 33-34	\$0.0
			FY 34-35	\$0.0




PROJECT:	Asheville Rd. @ US Hwy 70	LOCATION:	Swannanoa	
ГҮРЕ:	General Capital Improvements	PIPE RATING:	17	
PROJECT NO.	2023005	TOTAL LF:	5,470	_
PROJECT BUDGET:	\$2,458,210.00	PROJECT ORIGIN:	CSR's, Heavy I&I	
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING		1	T T	
55320 - SURVEY - DESIGN	\$43,760.00			
55330 - DESIGN	\$43,760.00			
55340 - PERMITS	\$15,000.00			
55350 - SPECIAL STUDIES	\$10,500.00			
55360 - EASEMENT PLATS	\$12,750.00			
55370 - LEGAL FEES	\$15,000.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$110,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$2,242,700.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$5,000.00			
55450 - SURVEY - ASBUILT	\$14,000.00			
TOTAL AMOUNT	\$2,458,210.00	\$0.00	\$0.00	\$0.0
ENGINEER:	MSD	ТН	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 13 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$43,760.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$15,000.0
NSPECTION:	MSD		FY 29-30	\$114,900.0
			FY 30-31	\$22,850.0
			FY 31-32	\$2,261,700.0
	oject is located in Swannanoa between I40 a		FY 32-33	\$0.0
and 8" VCP that has heavy I&I and r	oot instrusion. Could be considered as part	of a lining contract.	FY 33-34	\$0.0
			FY 34-35	\$0.0




PROJECT:	Atkins Street	LOCATION:	Arden	
TYPE:	General Sewer Rehab.	PIPE RATING:	19	
PROJECT NO.	2014012	TOTAL LF:	1,833	
PROJECT BUDGET:	\$771,930.00	PROJECT ORIGIN:	SSO's, Work Orders, Line	Condition
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$5,480.00	\$5,480.00		
55330 - DESIGN 55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	40.470.00			
55370 - LEGAL FEES	\$3,450.00			
55380 - ACQUISITION SERVICES	\$4,000.00			
55390 - COMPENSATION	\$45,000.00			
55400 - APPRAISAL	\$40,000.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$710,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$2,000.00			
TOTAL AMOUNT	\$771,930.00	\$5,480.00	\$0.00	\$0.00
ENGINEER:	MSD	BD	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 3 ]	FY 26-27	\$0.00
CONTRACTOR:	MOD		FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$2,600.0
NSPECTION:	MSD		FY 29-30	\$49,850.0
			FY 30-31	\$714,000.0
	roject is located in Arden just north of Lak			\$0.0
1,833 LF of existing 6-inch vitrified existing sewer line is in poor condition	I clay pipe will be replaced with new 8-inc on due to roots, fractures, and sags in the lin	n ductile iron pipe. The le. The line is undersized	FY 32-33	\$0.0
and has flooded houses in the area.	,	/5 445.5/200	FY 34-35	\$0.0




PROJECT:	Avena Rd. @ Flat Creek Rd.	LOCATION:	Black Mountain	
ГҮРЕ:	Pipe Rated Projects	PIPE RATING:	43	
PROJECT NO.	2021009	TOTAL LF:	1,985	
PROJECT BUDGET:	\$840,182.00	PROJECT ORIGIN:	CSR's, I & I	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$13,000.00			
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$6,800.00			
55370 - LEGAL FEES	\$8,000.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$25,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$781,594.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$3,788.00			
TOTAL AMOUNT	\$840,182.00	\$0.00	\$0.00	\$0.00
			i	
ENGINEER:	MSD	TH	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	#PLATS: [7]	FY 26-27	\$13,000.00
CONTRACTOR:			FY 27-28	\$32,950.00
CONSTRUCTION ADM.:	MSD		FY 28-29	\$794,232.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
DDO IECT DESCRIPTION. This was a	et is legated in Plack Mountain on Avera De	and Flat Creak Rd The	FY 31-32	\$0.00
PROJECT DESCRIPTION: This project is located in Black Mountain on Avena Rd and Flat Creek Rd. The existing approximate 1515 linear feet of 4" and 8" VCP lines are full of heavy I&I and defective taps and				\$0.0
	ntail for others too. Line needs to be replace		FY 33-34	\$0.00
			FY 34-35	\$0.00




PROJECT:	Avon Ave. @ Haywood Rd.	LOCATION:	West Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	65	
PROJECT NO.	2021003	TOTAL LF:	218	
PROJECT BUDGET:	\$206,550.00	PROJECT ORIGIN:	Access, Flooded Structure	e, Line Condition
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1	I I	
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN 55330 - DESIGN	\$2,500.00	\$2,500.00		
55340 - PERMITS	#4 000 00		#4 000 CC	
55350 - SPECIAL STUDIES	\$1,000.00		\$1,000.00	
55360 - EASEMENT PLATS	\$5,950.00	\$5,100.00	\$850.00	
55370 - LEGAL FEES	\$8,000.00	\$5,837.00		
55380 - ACQUISITION SERVICES	\$4,000.00	ψο,σστ.σσ	ψ2,100.00	
55390 - COMPENSATION	\$40,000.00	\$12,091.00	\$27,909.00	
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$147,000.00			\$147,000.0
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			\$1,000.0
55450 - SURVEY - ASBUILT	\$1,100.00			\$1,100.0
TOTAL AMOUNT	\$206,550.00	\$25,528.00	\$31,922.00	\$149,100.0
ENGINEER:	GINEER: MSD BD		ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	MSD	#PLATS: [ 6 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
PROJECT DESCRIPTION: This pro	oject is located in West Asheville near Avon	Ave approximately 0.25	FY 31-32	\$0.
mile west of the Haywood Rd. bridge	ge. Approximately 218 LF of existing 6-inch	and 8-inch vitrified clay	FY 32-33	\$0.
pipe will be replaced with new 8-incl	pe will be replaced with new 8-inch ductile iron pipe. The existing sewer line is in poor condition due to ots and cannot be washed or rodded due to lack of access.			\$0.
TOOLS AND CANNOL DE WASHED OF TOUCH	ou due to lack of access.		FY 34-35	\$0.




PROJECT:	Beale Road at Copney Lane	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	40	
PROJECT NO.	2009129	TOTAL LF:	5,430	
PROJECT BUDGET:	\$2,344,375.00	PROJECT ORIGIN:	SSO's, Access, Line Cond	ition
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$24,025.00	\$24,025.00		
55330 - DESIGN				
55340 - PERMITS	\$2,000.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS 55370 - LEGAL FEES	\$20,850.00			\$20,000.00
55370 - LEGAL FEES 55380 - ACQUISITION SERVICES	\$22,500.00			\$19,000.00
55390 - COMPENSATION	\$76,000.00			\$56,000.00
55400 - APPRAISAL	\$140,000.00			\$90,000.00
55410 - CONDEMNATION	\$8,000.00 \$32,000.00			
55420 - CONSTRUCTION	\$2,000,000.00			
55430 - CONST. CONTRACT ADM.	Ψ2,000,000.00			
55440 - TESTING	\$3,000.00			
55450 - SURVEY - ASBUILT	\$16,000.00			
TOTAL AMOUNT	\$2,344,375.00	\$24,025.00	\$0.00	\$185,000.00
ENGINEER:	MSD DP		ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	Consultant	# PLATS: [ 19 ]	FY 26-27	\$116,350.00
CONTRACTOR:			FY 27-28	\$2,019,000.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
ROJECT DESCRIPTION: This project ties into the Lake Julian Ph. 4 project just west of Glen Bridge Road				
and extends northward to Ducker manufacturing sites. The lines are	nd extends northward to Ducker Road and Lower Glen Bridge Road. It serves several major anufacturing sites. The lines are in poor condition with broken segments and leaking joints, hav			\$0.00 \$0.00
experienced SSO's, and are difficult to access for maintenance and repairs.		and loaking joints, riave		
			FY 34-35	\$0.00




PROJECT:	Bear Creek Road	LOCATION:	W. Asheville	
ГҮРЕ:	General Sewer Rehab.	PIPE RATING:	6	
PROJECT NO.	2011117	TOTAL LF:	2,800	
PROJECT BUDGET:	\$1,269,900.00	PROJECT ORIGIN:	Work Orders, Line Condi	tion
PROJECT BUDGET.	\$ 1,203,300.00	PROJECT ORIGIN.	Work Orders, Line Condi	шоп
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		<u> </u>		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$9,400.00	\$7,900.00		
55330 - DESIGN				
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$17,000.00			
55370 - LEGAL FEES	\$19,000.00			
55380 - ACQUISITION SERVICES	\$18,000.00			
55390 - COMPENSATION	\$100,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,100,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$3,500.00			
TOTAL AMOUNT	\$1,269,900.00	\$7,900.00	\$0.00	\$0.00
ENGINEER:	MSD SA		ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 18 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$1,500.00
			FY 31-32	\$16,500.00
ROJECT DESCRIPTION: This project is located in West. Asheville and is comprised of 2,800 LF of 8-inductile iron pipe. The existing line is aging 8-inch vitrified clay pipe. The line has multiple fractures, sag		s.l		
misaligned joints, and root intrusion.	711	, , , , , , , , , , , , , , , , , , , ,	FY 33-34	\$0.00
			FY 34-35	\$1,105,500.00



PROJECT:	Bellevue Road	LOCATION:	S. Asheville	
TYPE:	General Sewer Rehab	PIPE RATING:	15	
PROJECT NO.	2015175	TOTAL LF:	1,100	
PROJECT BUDGET:	\$753,336.00	PROJECT ORIGIN:	Work Orders, Line Condit	ion
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		u-		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$11,450.00	\$11,450.00		
55330 - DESIGN				
55340 - PERMITS	\$10,000.00		\$10,000.00	
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$14,350.00	\$13,500.00		\$850.00
55370 - LEGAL FEES	\$11,000.00			\$11,000.00
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$55,536.00			\$55,536.00
55400 - APPRAISAL	\$4,000.00			\$4,000.00
55410 - CONDEMNATION	\$16,000.00			
55420 - CONSTRUCTION	\$625,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$4,000.00			
TOTAL AMOUNT	\$753,336.00	\$24,950.00	\$10,000.00	\$71,386.00
ENGINEER:	MSD	DP	ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	MSD	#PLATS: [ 9 ]	FY 26-27	\$16,000.00
CONTRACTOR:			FY 27-28	\$631,000.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
DDO IFOT DECODIETION TO	and in Landard in County A. L. 191	and a part of the state of the	FY 31-32	\$0.00
	ect is located in South Asheville along prop /CP and PVC. The existing line is in poor co		\$	
point repairs.	â barran	,	FY 33-34	\$0.0
			FY 34-35	\$0.00




PROJECT:	Bent Tree Rd. @ Old Toll Rd.	LOCATION:	Asheville	
	2011 1100 1101 (@ 010 1011 1101		7.0.107.110	
TYPE:	General Sewer Rehab.	PIPE RATING:	NA	
PROJECT NO.	2024034	TOTAL LF:	0	
PROJECT BUDGET:	\$24,000.00	PROJECT ORIGIN:	Undersized line, poor cond	lition
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN				
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$1,000.00		\$1,000.00	
55370 - LEGAL FEES	\$1,000.00	\$776.00	\$224.00	
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$2,000.00		\$2,000.00	
55400 - APPRAISAL	\$3,500.00		\$3,500.00	
55410 - CONDEMNATION	\$14,000.00		\$5,000.00	\$9,000.00
55420 - CONSTRUCTION				
55430 - CONST. CONTRACT ADM.				
55440 - TESTING				
55450 - SURVEY - ASBUILT	\$2,500.00			\$2,500.00
TOTAL AMOUNT	\$24,000.00	\$776.00	\$11,724.00	\$11,500.00
ENGINEER:	MSD	DP	ESTIMATED BUDGETS - I	
R.O.W. ACQUISITION:	MSD	#PLATS: [ 1 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
			FY 31-32	\$0.00
	ct is located in Asheville in the Town Mounta ial property and ends at Bent Tree Rd. The e		FY 32-33	\$0.00
line is undersized and in poor struct		Shoung T-mon day sewer	FY 33-34	\$0.00
			FY 34-35	\$0.00




PROJECT:	Braddock Way - PRP 20002	LOCATION:	Asheville	
TYPE:	Pipe Rated Projects	PIPE RATING:	22	
PROJECT NO.	2006025	TOTAL LF:	3,199	
PROJECT BUDGET:	\$1,923,853.00	PROJECT ORIGIN:	Pipe Rating Program	
	* ',===,====	price zer erwenn	- ipo itamig i rogiam	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING			<u> </u>	
55320 - SURVEY - DESIGN	\$18,190.00	\$18,190.00		
55330 - DESIGN	\$10,100.00	Ψ10,100.00		
55340 - PERMITS	\$1,000.00		\$1,000.00	
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$22,100.00		\$21,250.00	\$850.00
55370 - LEGAL FEES	\$25,663.00	\$163.00		\$23,000.00
55380 - ACQUISITION SERVICES	\$87,500.00			\$58,500.00
55390 - COMPENSATION	\$78,000.00			\$55,000.00
55400 - APPRAISAL	\$8,000.00			
55410 - CONDEMNATION	\$32,000.00			
55420 - CONSTRUCTION	\$1,635,400.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$3,500.00			
55450 - SURVEY - ASBUILT	\$12,500.00			
TOTAL AMOUNT	\$1,923,853.00	\$18,353.00	\$22,250.00	\$137,350.00
ENGINEER:	MSD	TH	ESTIMATED BUDGE	IS - FY 27 - 35
R.O.W. ACQUISITION:	Consultant	# PLATS: [ 21 ]	FY 26-27	\$78,500.00
CONTRACTOR:			FY 27-28	\$1,667,400.00
CONSTRUCTION ADM.:	MSD		FY 28-29	\$0.00
NSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
DDO IFOT DECODIFIED THE	at will replace line and the boart	Laudatina agrees !	FY 31-32	\$0.00
Park Avenue and Braddock Way su	ct will replace, line, and pipe burst several abdivisions. Problems with these lines inclu	ide leaking joints, broken	FY 32-33	\$0.00
pipes and high inflow and infiltratio	n. In some areas, the existing lines will b	be relocated from private FY 33-34		\$0.0
property to public rights of way for be	etter access and maintenance.		FY 34-35	




Broadway St. at Bordeau Place	LOCATION:	Asheville	
General Sewer Rehab.	PIPE RATING:	22	
2009034	TOTAL LF:	475	
\$259,750.00	PROJECT ORIGIN:	SSO's, Work Orders, Li	ne Condition
ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		<u> </u>	
\$6.250.00	\$6.250.00		
\$0,230.00	φ0,230.00		
\$250,000.00			
\$1,000.00			
\$2,500.00			
\$259,750.00	\$6,250.00	\$0.00	\$0.00
MSD	DP	ESTIMATED BUD	GETS - FY 27 - 35
MSD		FY 26-27	\$0.00
		FY 27-28	\$0.00
MSD		FY 28-29	\$253,500.00
MSD		FY 29-30	\$0.00
		FY 30-31	\$0.00
		FY 31-32	\$0.00
		FY 32-33	\$0.00
		FY 33-34	\$0.00
· ·		FY 34-35	\$0.00
ł	\$259,750.00  ESTIMATED PROJECT COST  \$6,250.00 \$6,250.00 \$250,000.00 \$1,000.00 \$2,500.00 \$259,750.00  MSD  MSD  MSD  MSD  MSD  MSD  MSD  M	\$259,750.00    Solution   PROJECT ORIGIN:   TOTAL EXPENDS THRU 12/31/24	\$259,750.00 PROJECT ORIGIN: SSO's, Work Orders, Li    ESTIMATED PROJECT COST




PROJECT:	Central Ave. @ I-240	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	37	
PROJECT NO.	2014180	TOTAL LF:	1,224	
PROJECT BUDGET:	\$1,020,750.00	PROJECT ORIGIN:	SSO's, Work orders, Line	condition
	FOTIMATED	TOTAL EXPENDS	FOT 000T	DURGET
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING		1	I I	
55320 - SURVEY - DESIGN	#c 000 00		Ø6 000 00	
55330 - DESIGN	\$6,000.00		\$6,000.00	
55340 - PERMITS	\$1,000.00			\$1,000.00
55350 - SPECIAL STUDIES	\$1,000.00			ψ1,000.00
55360 - EASEMENT PLATS	\$1,500.00			\$1,000.00
55370 - LEGAL FEES	\$2,000.00			φ1,000.00
55380 - ACQUISITION SERVICES	. , , , , , , , , , , , , , , , , , , ,			
55390 - COMPENSATION	\$23,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$985,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$1,250.00			
TOTAL AMOUNT	\$1,020,750.00	\$0.00	\$6,000.00	\$2,000.00
ENGINEER:	MSD	SA	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	#PLATS: [ 1 ]	FY 26-27	\$25,500.00
CONTRACTOR:			FY 27-28	\$987,250.00
CONSTRUCTION ADM.:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
			FY 31-32	\$0.00
	project is located in downtown Asheville n			\$0.00
comprised of 990 LF of 12-inch duct with a history of SSO's.	tile iron pipe. The existing line is 6, 10, and	ı∠-ıncn vitrified ciay pipe	FY 33-34	\$0.00
- I			FY 34-35	\$0.00



PROJECT:	Chatham Road	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	19	
PROJECT NO.	2015019	TOTAL LF:	1,330	
PROJECT BUDGET:	\$627,925.00	PROJECT ORIGIN:	Line Condition	
		<u> </u>		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		ı		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$4,800.00	\$4,800.00	0	
55330 - DESIGN				
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$4,500.00			\$3,500.00
55370 - LEGAL FEES	\$5,000.00			\$5,000.00
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION 55400 - APPRAISAL	\$45,000.00			\$45,000.00
55410 - APPRAISAL 55410 - CONDEMNATION	\$4,000.00			
55420 - CONSTRUCTION	\$16,000.00			
55430 - CONST. CONTRACT ADM.	\$543,125.00			
55440 - TESTING	£4,000,00			
55450 - SURVEY - ASBUILT	\$1,000.00 \$3,500.00			
TOTAL AMOUNT	\$627,925.00	ĺ	0 \$0.00	\$53,500.00
	Ψ021,323.00	η <del>ψ4,000.01</del>	φ	Ψ33,300.00
ENGINEER:	MSD	SA	ESTIMATED BUDGE	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	#PLATS: [ 4 ]	FY 26-27	\$16,000.00
CONTRACTOR:			FY 27-28	\$553,625.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
			FY 31-32	\$0.00
PROJECT DESCRIPTION: This pro	ject is located in North Asheville near W actile iron pipe. The existing line is 6-inch v	T. Weaver Blvd. and is	FY 32-33	\$0.00
condition with heavy root intrusion.	ionic non pipe. The existing line is 0-IIICH	viamed clay pipe iii poo	FY 33-34	\$0.00
			FY 34-35	\$0.00




PROJECT:	Chester Pl. @ Cranford Rd.	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	7	
PROJECT NO.	2019026	TOTAL LF:	1,025	
PROJECT BUDGET:	\$426,100.00	PROJECT ORIGIN:	Work Orders, Line Condit	ion
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$15,000.00			
55330 - DESIGN 55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	240,000,00			
55370 - LEGAL FEES	\$13,600.00			
55380 - ACQUISITION SERVICES	\$16,000.00			
55390 - COMPENSATION	\$92,000.00			
55400 - APPRAISAL	\$32,000.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$285,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$3,500.00			
TOTAL AMOUNT	\$426,100.00	\$0.00	\$0.00	\$0.00
			1	
ENGINEER:	MSD	TH	ESTIMATED BUDGE	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 14 ]	FY 26-27	\$0.00
CONTRACTOR:	MSD		FY 27-28	\$0.00
CONSTRUCTION ADM.:	MSD		FY 28-29 FY 29-30	\$0.00
NSFECTION.	INIOU		FY 30-31	\$0.00
			FY 31-32	\$0.0
PROJECT DESCRIPTION: This project	t is located in West Asheville running along the	e rear of properties fronting	FY 32-33	\$90,900.0
Chester Place, Cranford Rd. and Wend	dover Rd. It consists of replacing approximately is in structurally poor condition with heavy root int	1050 LF 6-inch and 8-inch	FY 33-34	\$45,700.0
VOI WILL O-ILION DIL . THE EXISTING VOP	is in structurally poor confution with neary foot lift	u u o i U I I.	FY 34-35	\$0.00 \$289,500.00




PROJECT:	Covewood Trail @ Chunns Cove Rd.	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	17	
PROJECT NO.	2021005	TOTAL LF:	1,120	
PROJECT BUDGET:	\$455,500.00	PROJECT ORIGIN:	Access, Line Condition, U	ndersized
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$8,500.00			
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$10,000.00			
55370 - LEGAL FEES	\$12,000.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$21,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$400,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING				
55450 - SURVEY - ASBUILT	\$4,000.00	ii <del></del>		
TOTAL AMOUNT	\$455,500.00	\$0.00	0  \$0.00	\$0.0
ENGINEER:	MSD	DP	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 10 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$8,500.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$9,150.0
NSPECTION:	MSD		FY 29-30	\$33,850.0
			FY 30-31	\$404,000.0
			FY 31-32	\$0.0
PROJECT DESCRIPTION: This proje	ect will replace the existing 6-inch sewer ma	in from Chunns Cove Ro	FY 32-33	\$0.0
	Covewood Rd. The line is old vitrified clay pof the lines are hard to access which make re		FY 33-34	\$0.0
		•	FY 34-35	\$0.0




PROJECT:	Cub Road	LOCATION:	Asheville	
PROJECT.	Cub Road	LOCATION.	Asheville	
TYPE:	General Sewer Rehab	PIPE RATING:	15	
PROJECT NO.	2018027	TOTAL LF:	1,204	
PROJECT BUDGET:	\$455,300.00	PROJECT ORIGIN:	CSR's, MH Overflow, Wor	k Orders
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$9,600.00			
55330 - DESIGN				
55340 - PERMITS	\$500.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS 55370 - LEGAL FEES	\$11,200.00			
55380 - ACQUISITION SERVICES	\$14,500.00			
55390 - COMPENSATION	055,000,00			
55400 - APPRAISAL	\$55,000.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$360,000.00			
55430 - CONST. CONTRACT ADM.	\$550,550.00			
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$3,500.00			
TOTAL AMOUNT	\$455,300.00	\$0.00	\$0.00	\$0.00
ENGINEER:	MSD	тн	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 12 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$10,100.00
INSPECTION:	MSD		FY 29-30	\$78,200.00
			FY 30-31	\$2,500.00
PROJECT DESCRIPTION: This proje	ect is located in West Asheville running alo	ng the rear of properties	FY 31-32	\$364,500.00
fronting Cub Rd. This system consist	ts of approximately 1,204 LF of 8-inch VCP t gs, has heavy root intrusion, deteriorating ma	o be replaced with 8-inch	FY 32-33	\$0.00
connections.	gs, nas neavy 100t initiusion, detenorating ma	amores, and bad service		\$0.00
			FY 34-35	\$0.00




PROJECT:	Dover St. @ Merrimon Ave.	LOCATION:	Asheville	
TYPE:	General Sewer Rehab	PIPE RATING:	29	
ITFE.	General Sewer Reliab	PIPE RATING.	29	
PROJECT NO.	2023006	TOTAL LF:	223	
PROJECT BUDGET:	\$118,600.00	PROJECT ORIGIN:	Work orders in the past	
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING		<u> </u>		
55320 - SURVEY - DESIGN	\$1,900.00			
55330 - DESIGN	φ1,900.00			
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$2,500.00			
55370 - LEGAL FEES	\$2,500.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$10,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$100,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$700.00			
TOTAL AMOUNT	\$118,600.00	\$0.00	\$0.00	\$0.0
ENGINEER:	MSD	TH	ESTIMATED BUDG	SETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 2 ]	FY 26-27	\$1,900.0
CONTRACTOR:			FY 27-28	\$15,000.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.
INSPECTION:	MSD		FY 29-30	\$101,700.
			FY 30-31	\$0.
			FY 31-32	\$0.
	ect is located in Asheville across Merrimon A with structural defects. If line is being replaced			\$0.
	nents and place in the road with a more desira		FY 33-34	\$0.
			FY 34-35	\$0.




PROJECT:	Druid Drive	LOCATION:	W. Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	10	
PROJECT NO.	2020006	TOTAL LF:	500	
PROJECT BUDGET:	\$204,000.00	PROJECT ORIGIN:	Work Orders, Line Condi	tion
		i -		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$4,000.00			
55330 - DESIGN	\$4,000.00			
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES	ψ1,000.00			
55360 - EASEMENT PLATS	\$8,000.00			
55370 - LEGAL FEES	\$9,000.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$30,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$150,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$1,000.00			
TOTAL AMOUNT	\$204,000.00	\$0.00	\$0.00	\$0.00
ENGINEER:	MSD	SA	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 8 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM.:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
			FY 31-32	\$20,000.0
	pject is located in West Asheville and is comp		FY 32-33	\$32,000.0
ductile iron pipe. The existing line is bends that cannot pass a CCTV cam	s aging 6 and 8-inch vitrified clay pipe, with r nera, and heavy root intrusion.	numple structural delects,	FY 33-34	\$152,000.0
			FY 34-35	\$0.0




PROJECT:	East Chestnut Ave. @ Five Points	LOCATION:	N. Asheville	
	<u> </u>			
TYPE:	General Sewer Rehab.	PIPE RATING:	29	
PROJECT NO.	2015192	TOTAL LF:	5,225	
PROJECT BUDGET:	\$2,097,121.00	PROJECT ORIGIN:	MH Overflows, Line Cond	ition
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$21,821.00	\$19,321.00		\$2,500.0
55330 - DESIGN				
55340 - PERMITS	\$1,000.00			\$1,000.0
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$20,550.00			
55370 - LEGAL FEES	\$25,000.00			
55380 - ACQUISITION SERVICES	\$92,000.00			
55390 - COMPENSATION 55400 - APPRAISAL	\$100,000.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	#4 000 750 00			
55430 - CONST. CONTRACT ADM.	\$1,828,750.00			
55440 - TESTING	\$2,000,00			
55450 - SURVEY - ASBUILT	\$3,000.00 \$5,000.00			
TOTAL AMOUNT	\$2,097,121.00	i <del></del>	\$0.00	\$3,500.0
	, , , , , , , , , , , , , , , , , , , ,	<u>, , , , , , , , , , , , , , , , , , , </u>	72.22	**,****
ENGINEER:	MSD	SA	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	Consultant	# PLATS: [ 23 ]	FY 26-27	\$92,550.0
CONTRACTOR:			FY 27-28	\$145,000.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$1,836,750.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
			FY 31-32	\$0.0
<b>PROJECT DESCRIPTION:</b> This proje ductile iron pipe. The existing line in the interior of the project of the pr	ct is located in N. Asheville and is comprise s aging 6, 8, and 10-inch VCP in poor shap	ed of 5,225 LF of 8-inch be with multiple structural	FY 32-33	\$0.
defects per segment.	5 5 1, 1, 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	,	FY 33-34	\$0.
			FY 34-35	\$0.0




		1		
PROJECT:	Edgewood Rd. S @ Sweeten Crk Rd.	LOCATION:	Asheville	
TVDF.	Dina Datad Dynicata	PIPE RATING:	10	
TYPE:	Pipe Rated Projects	PIPE RATING:	10	
PROJECT NO.	2021007	TOTAL LF:	500	
PROJECT BUDGET:	\$186,300.00	PROJECT ORIGIN:	CSR's	
		<u> </u>		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING		1	T I	
55320 - SURVEY - DESIGN	#2.000.00			
55330 - DESIGN	\$3,000.00			
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES	\$1,000.00			
55360 - EASEMENT PLATS	\$2,550.00			
55370 - LEGAL FEES	\$2,500.00			
55380 - ACQUISITION SERVICES	Ψ2,000.00			
55390 - COMPENSATION	\$24,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$150,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$1,250.00			
TOTAL AMOUNT	\$186,300.00	\$0.00	\$0.00	\$0.00
			<u> </u>	
ENGINEER:	MSD	ТН	ESTIMATED BUDG	GETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	#PLATS: [2 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM.:	MSD		FY 28-29	\$4,000.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31 FY 31-32	\$29,050.0
PROJECT DESCRIPTION: This proie	ct is located in Asheville near the intersectio	n of Edgewood Rd S and		\$0.0
Sweeten Creek. The existing VCP	line has a MSD MH located in the baseme	nt of homeowners house	FY 32-33 FY 33-34	\$153,250.0
and needs to be re-routed to avoid a	tuture disaster.		FY 34-35	\$0.0
<u> </u>			1 1 34-33	\$0.00




PROJECT:	Edwards Ave. @ US 70 Hwy.	LOCATION:	Swannanoa	
TYPE:	General Sewer Rehab.	PIPE RATING:	29	
DDO JEST NO	0004004		0.400	
PROJECT NO.	2021004	TOTAL LF:	2,400	
PROJECT BUDGET:	\$963,750.00	PROJECT ORIGIN:	Line Condition, Flooded	Structure
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$11,000.00	\$0.00	\$11,000.00	
55330 - DESIGN	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	, , , , ,	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$7,650.00			
55370 - LEGAL FEES	\$9,500.00			
55380 - ACQUISITION SERVICES	71,000.00			
55390 - COMPENSATION	\$30,000.00			
55400 - APPRAISAL	,			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$900,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$3,600.00			
TOTAL AMOUNT	\$963,750.00	\$0.00	\$11,000.00	\$0.0
ENGINEER:	MSD	BD	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 8 ]	FY 26-27	\$6,800.0
CONTRACTOR:			FY 27-28	\$40,350.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$905,600.0
NSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
PROJECT DESCRIPTION: This pr	oject is located in Swannanoa, approximat	ely 0.5 mile east of the	FY 31-32	\$0.0
Patton Cove Rd exit (I-40 exit 59).  Ave and Young St Approximately	The project includes pipe replacement on 2,400 LF of existing 6-inch and 8-inch v	Edwards Ave, Richmond vitrified clay pine will be	FY 32-33	\$0.0
eplaced with 8-inch ductile iron pipe	. This line was constructed in the 1920s and			\$0.0
defects which contributed to one floo	ded structure.		FY 34-35	\$0.0



PDO ISOT.	File Book Drive DDD 25004	L OCATION:	Mondin	
PROJECT:	Elk Park Drive - PRP 35001	LOCATION:	Woodfin	
TYPE:	Pipe Rated Projects	PIPE RATING:	8	
	1 190 1			
PROJECT NO.	2006028	TOTAL LF:	2,242	
PROJECT BUDGET:	\$767,046.00	PROJECT ORIGIN:	Pipe Rating Program	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING		11	T	
55320 - SURVEY - DESIGN	\$40,050,00	\$10.050.0C	+	
55330 - DESIGN	\$10,050.00	\$10,050.00	+	
55340 - PERMITS	\$200.00	\$200.00		
55350 - SPECIAL STUDIES	\$200.00	\$200.00	+	
55360 - EASEMENT PLATS	\$9,290.00	\$9,290.00	,	
55370 - LEGAL FEES	\$9,290.00	\$9,290.00		
55380 - ACQUISITION SERVICES	*:-,:	<b>* · ,</b> · · · · ·	†	
55390 - COMPENSATION	\$18,320.00	\$18,320.00	1	
55400 - APPRAISAL	-			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$710,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$5,000.00			
TOTAL AMOUNT	\$767,046.00	\$50,046.00	\$0.00	\$0.0
ENGINEER:	MSD			GETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 17 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM.:	MSD		FY 28-29	\$0.
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
This project		TO 10 LE - 40 inch duptile	FY 31-32	\$0.
	ct is located in Woodfin and is comprised of 2 vitrified clay pipe and PVC with numerous sa		1 1 32-33	\$0.
	will be replaced during construction of the ne		FY 33-34	\$0.
		•	FY 34-35	\$717,000.




PROJECT:	Elkwood Ave. @ Norman Austin Dr.	LOCATION:	Woodfin	
ГҮРЕ:	General Sewer Rehab.	PIPE RATING:	22	
PROJECT NO.	2014008	TOTAL LF:	600	
PROJECT BUDGET:	\$266,350.00	PROJECT ORIGIN:	SSO's, Access, Line Cond	lition
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		)(		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$3,500.00			
55330 - DESIGN				
55340 - PERMITS 55350 - SPECIAL STUDIES				
55360 - SPECIAL STUDIES 55360 - EASEMENT PLATS				
55370 - LEGAL FEES	\$2,850.00			
55380 - ACQUISITION SERVICES	\$3,000.00			
55390 - COMPENSATION	£4,000,00			
55400 - APPRAISAL	\$4,000.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$250,000.00			
55430 - CONST. CONTRACT ADM.	\$250,500.00			
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$2,000.00			
TOTAL AMOUNT	\$266,350.00	\$0.00	\$0.00	\$0.0
			·	
ENGINEER:	MSD	DP	ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 2 ]	FY 26-27	\$3,500.0
CONTRACTOR:			FY 27-28	\$2,000.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$7,850.0
NSPECTION:	MSD		FY 29-30	\$253,000.0
			FY 30-31	\$0.0
PROJECT DESCRIPTION: This project runs through properties along Elkwood Ave., starting at Norman Austin Drive. The existing pipe is 4-inch and 6-inch, is undersized and has misaligned joints. There is a manhole that is located under a property owner's porch. The proposed 8-inch ductile iron pipe will run				
			a FY 32-33	
namole that is located under a property owner's porch. The proposed 6-inch ductile from pipe will mainly on Elkwood Ave. to move the system into the road for easier maintenance.			FY 33-34 FY 34-35	\$0.0




PROJECT:	Fairmont Road	LOCATION:	N. Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	4	
PROJECT NO.	2015017	TOTAL LF:	3,900	
PROJECT BUDGET:	\$1,715,850.00	PROJECT ORIGIN:	SSO's, Access, Line Cond	dition
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$25,000.00			
55330 - DESIGN				
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$10,850.00			
55370 - LEGAL FEES	\$13,000.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$150,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,500,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$4,000.00			
55450 - SURVEY - ASBUILT	\$12,000.00			
TOTAL AMOUNT	\$1,715,850.00	\$0.00	\$0.00	\$0.00
			Ü.	
ENGINEER:	MSD DP		ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 11 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$25,000.00
			FY 31-32	\$0.00
PROJECT DESCRIPTION: This project will run alo	ect is located in North Asheville approximing roads and properties from Glendale Rd. to	ately 0.25 miles east o o Sunset Dr.  The 6-inch	FY 32-33	\$10,000.0
	have caused manhole overflows and SSOs.		FY 33-34	\$164,850.0
			FY 34-35	\$1,516,000.00




PROJECT:	Forestdale Drive	LOCATION:	S. Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	14	
PROJECT NO.	2014002	TOTAL LF:	2,900	
PROJECT BUDGET:	\$1,456,050.00	PROJECT ORIGIN:	SSO's, Work Orders, Line	Condition
		1	Ī	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1	I I	
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN 55330 - DESIGN	\$25,500.00	\$25,500.00		
55340 - PERMITS 55350 - SPECIAL STUDIES	\$500.00			
55350 - SPECIAL STUDIES 55360 - EASEMENT PLATS				
55370 - LEGAL FEES	\$32,550.00			
55380 - ACQUISITION SERVICES	\$32,500.00			
55390 - COMPENSATION	\$103,000.00			
55400 - APPRAISAL	\$100,000.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,250,000.00			
55430 - CONST. CONTRACT ADM.	. , ,			
55440 - TESTING	\$3,000.00			
55450 - SURVEY - ASBUILT	\$9,000.00			
TOTAL AMOUNT	\$1,456,050.00	\$25,500.00	\$0.00	\$0.0
ENGINEER:	MSD	DP	ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 30 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$500.0
NSPECTION:	MSD		FY 29-30	\$154,000.0
			FY 30-31	\$14,050.
PROJECT DESCRIPTION: This project begins at Cornell St. and ends at Caribou Rd. The system runs				
along side roads and properties pa	arallel to Hendersonville Rd. System Servic le SSO's. The existing pipes will be replace	ces crews have reported ed with 8-inch ductile iron	FY 32-33	\$0.
pipe.	c		FY 33-34 FY 34-35	\$0. \$0.



PROJECT:	Forest Hill Dr. @ Warwick Rd.	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	10	
PROJECT NO.	2014020	TOTAL LF:	3,400	
PROJECT BUDGET:	\$1,481,000.00	PROJECT ORIGIN:	SSO's, Work Orders, Line	Condition
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$24,000.00			
55330 - DESIGN				
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,450,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$4,000.00			
TOTAL AMOUNT	\$1,481,000.00	\$0.00	\$0.00	\$0.00
ENGINEER:	MSD	SA	ESTIMATED BUDGE	TS - FV 27 - 35
R.O.W. ACQUISITION:	N/A	# PLATS: [ 0 ]	FY 26-27	
CONTRACTOR:			FY 27-28	\$0.00 \$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
				\$24,000.00
	ROJECT DESCRIPTION: This project is in Asheville in the Kenilworth neighborhood and consists on 400 LF of 8-inch ductile iron pipe. The current pipe is undersized 6-inch clay in poor condition, wit			\$1,000.00
roots and fractures.		, F-1: 13:13:13:13 Will	FY 33-34	\$1,456,000.00
			FY 34-35	\$0.00




PROJECT:	Harmony Lane	LOCATION:	Asheville	
ГҮРЕ:	General Sewer Rehab.	PIPE RATING:	28	
PROJECT NO.	2016103	TOTAL LF:	670	
PROJECT BUDGET:	\$308,500.00	PROJECT ORIGIN:	Undersized, Maintenance	Issues
		II.		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$5,000.00			
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES 55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	#200 000 00			
55430 - CONST. CONTRACT ADM.	\$300,000.00			
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$2,500.00			
TOTAL AMOUNT	\$308,500.00	\$0.00	\$0.00	\$0.00
	***************************************	,, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	, , , , , , , , , , , , , , , , , , , ,	****
ENGINEER:	MSD	MSD DP		ETS - FY 27 - 35
R.O.W. ACQUISITION:		# PLATS: [ 0 ]	FY 26-27	\$5,000.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$303,500.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
			FY 31-32	
PROJECT DESCRIPTION: This project system has two parallel lines that co	ect is along Harmony Lane in Asheville's C ollect on both side of the street. Problems w	Dakley area. The existing rith the system consist of	9 FY 32-33	
system has two parallel lines that collect on both side of the street. Problems with the system to			FY 33-34	\$0.00
			FY 34-35	\$0.00



PROJECT:	Hazel Mill Rd. @ Richland St.	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	41	
PROJECT NO.	2014016	TOTAL LF:	3,858	
PROJECT BUDGET:	\$2,528,050.00	PROJECT ORIGIN:	SSO's, Work Orders, Line	Condition
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		10		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$26,350.00	\$26,350.00		
55330 - DESIGN				
55340 - PERMITS	\$1,000.00		\$1,000.00	
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$16,700.00	\$8,260.00	\$6,740.00	\$1,700.00
55370 - LEGAL FEES	\$31,000.00		\$28,000.00	\$3,000.00
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION 55400 - APPRAISAL	\$156,000.00			\$100,000.00
55410 - CONDEMNATION	\$12,000.00			\$4,000.00
55420 - CONSTRUCTION	\$48,000.00			\$16,000.00
55430 - CONST. CONTRACT ADM.	\$2,225,000.00			
55440 - TESTING	\$2,000,00			
55450 - SURVEY - ASBUILT	\$3,000.00 \$9,000.00			
TOTAL AMOUNT	\$2,528,050.00	<u> </u>	\$35,740.00	\$124,700.00
	<b></b>	<u>,                                    </u>	, <del>, , , , , , , , , , , , , , , , , , </del>	¥ 1= 1,1 0 4 10
ENGINEER:	MSD	SA	ESTIMATED BUDGET	rs - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 28 ]	FY 26-27	\$2,333,000.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
PROJECT DESCRIPTION: This is	project is located in West Asheville, near	the Bowen Bridge, and	FY 31-32	\$0.00
consists of 3,907 LF of 8-inch ductile	iron pipe. The current pipe is 6-inch and 8-i	nch clay and PVC. Lines	FY 32-33	\$0.00
are undersized and in poor condition	with multiple pipe sags, cracks, and fracture	S.	FY 33-34	\$0.00
I			FY 34-35	\$0.00




PROJECT:	Hemphill Rd. @ Charlotte Hwy.	LOCATION:	Asheville	
TYPE:	Pipe Rated Projects	PIPE RATING:	7	
PROJECT NO.	2021006	TOTAL LF:	2550	
PROJECT BUDGET:	\$887,725.00	PROJECT ORIGIN:	CSR's	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$15,300.00			
55330 - DESIGN				
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$6,800.00			
55370 - LEGAL FEES	\$8,500.00			
55380 - ACQUISITION SERVICES 55390 - COMPENSATION				
55400 - APPRAISAL	\$19,000.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	фоор 750 oo			
55430 - CONST. CONTRACT ADM.	\$828,750.00			
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$6,375.00			
TOTAL AMOUNT	\$887,725.00	\$0.00	\$0.00	\$0.00
		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	, , , , , , , , , , , , , , , , , , , ,	,,,,,,
ENGINEER:	MSD	тн	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [7 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM.:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.0
			FY 31-32	\$15,300.0
PROJECT DESCRIPTION: This proje	ect is located in Asheville on Hemphill Rd o	ff of Charlotte Hwy. The	FY 32-33	\$33,450.0
existing 8" VCP of approximately 25	50 linear feet has heavy I&I throughout the ru	n and needs to be lined.	FY 33-34	\$1,850.0
			FY 34-35	\$837,125.00




PROJECT:	Herron Avenue	LOCATION:	W. Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	9	
		1		
PROJECT NO.	2014186	TOTAL LF:	2060	
PROJECT BUDGET:	\$908,950.00	PROJECT ORIGIN:	Work Orders, Line Condit	lion
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$14,200.00	\$1,700.00		
55330 - DESIGN				
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$2,000.00			
55370 - LEGAL FEES	\$2,500.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$10,500.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$875,500.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$2,250.00			
TOTAL AMOUNT	\$908,950.00	\$1,700.00	\$0.00	\$0.00
ENGINEER:	MSD	SA	ESTIMATED BUDGE	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 2 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$13,000.0
PPO JECT DESCRIPTION: This proje	ect is located in West Asheville near the inte	ersection of Sand Hill Rd	FY 31-32	\$12,500.0
and Haywood Rd. and is comprised	d of 2,060 LF of 8-inch ductile iron pipe. T	he existing line is 6-inch	FY 32-33	\$3,000.0
vitrified clay pipe in poor condition, v	with multiple pipe defects that cannot be ade	equately repaired by point	FY 33-34	\$878,750.0
repairs.			FY 34-35	\$0.0




PROJECT:	Hill Street @ Cross Place	LOCATION:	Asheville	
FROJECT.	TIII Street W C1033 1 lace	LOGATION.	Ashevine	
TYPE:	General Sewer Rehab.	PIPE RATING:	42	
		1		
PROJECT NO.	2016249	TOTAL LF:	641	
		<u> </u>		
PROJECT BUDGET:	\$299,355.00	PROJECT ORIGIN:	Work Orders, Line Location	on and Condition
	ESTIMATED	TOTAL EXPENDS	EST. COST	BUDGET
DESCRIPTION	PROJECT COST	THRU 12/31/24	JAN - JUNE 2025	FY 25-26
	1	Tr.	,	
55310 - PRELIM. ENGINEERING		<u> </u>		
55320 - SURVEY - DESIGN	\$3,875.00	0 \$1,525.00	1	\$2,350.00
55330 - DESIGN				
55340 - PERMITS	\$500.00	<u> </u>		
55350 - SPECIAL STUDIES		<u> </u>		
55360 - EASEMENT PLATS	\$3,400.00	<u> </u>		
55370 - LEGAL FEES	\$4,500.00	<u> </u>		
55380 - ACQUISITION SERVICES			<u> </u>	
55390 - COMPENSATION	\$22,000.00	<u> </u>	<u> </u>	
55400 - APPRAISAL	\$4,000.00	<u> </u>	<u> </u>	
55410 - CONDEMNATION	\$16,000.00	<u> </u>	<u> </u>	
55420 - CONSTRUCTION	\$243,580.00	<u> </u>	<u> </u>	
55430 - CONST. CONTRACT ADM.			<u> </u>	
55440 - TESTING	\$500.00	o <u> </u>		
55450 - SURVEY - ASBUILT	\$1,000.00	<u>ə</u>	<u> </u>	
TOTAL AMOUNT	\$299,355.00	0 \$1,525.00	\$0.00	\$2,350.00
ENGINEER:	MSD	TH	ESTIMATED BUDGE	FTS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 3 ]	FY 26-27	\$29,550.00
CONTRACTOR:	TBD		FY 27-28	\$29,550.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$265,930.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
		51 1 11 11 10 10 10	FY 31-32	\$0.0
	ect runs along Hill St. to the intersection of C eplacing approximately 641 LF of existing 6-i		FY 32-33	\$0.0
The line has numerous structural iss	sues, experienced frequent stoppages, and fl			\$0.0
years.				——————————————————————————————————————




PROJECT:	Howland Rd. @ Sunset Trail	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	51	
PROJECT NO.	2012134	TOTAL LF:	994	
PROJECT BUDGET:	\$494,350.00	PROJECT ORIGIN:	SSO's, Work Orders, Line O	Condition
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$7,500.00	\$4,600.00	\$2,900.00	
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$5,850.00		\$5,000.00	\$850.0
55370 - LEGAL FEES	\$7,000.00			\$7,000.0
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION 55400 - APPRAISAL	\$50,000.00			\$50,000.0
55410 - APPRAISAL 55410 - CONDEMNATION	\$4,000.00			\$4,000.0
55420 - CONSTRUCTION	\$16,000.00			\$16,000.0
55430 - CONST. CONTRACT ADM.	\$400,000.00			
55440 - TESTING	£4.000.00			
55450 - SURVEY - ASBUILT	\$1,000.00 \$3,000.00			
TOTAL AMOUNT	\$494,350.00	i	\$7,900.00	\$77,850.0
	ψ+3+,330.00	η ψ4,500.00	ψ1,300.00	ψ11,000.0
ENGINEER:	MSD	DP	ESTIMATED BUDGET	S - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 5 ]	FY 26-27	\$404,000.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
			FY 31-32	\$0.0
PROJECT DESCRIPTION: This projection from the project of 371 Sunset Dr. System Ser	ect will replace an existing 8-inch main from vices recently completed another portion of t	5 Howland Rd. up to the his system due to SSO's	FY 32-33	\$0.
and line condition.		2,0.0 240 10 0000	FY 33-34	\$0.
			FY 34-35	\$0.




PROJECT:	Innsbrook Rd. @ GPI	LOCATION:	North Asheville	
	missicon na. @ or r	200ATION.	North Ashevine	
TYPE:	General Sewer Rehab.	PIPE RATING:	28	
PROJECT NO.	2023256	TOTAL LF:	5,730	
PROJECT BUDGET:	\$2,492,875.00	PROJECT ORIGIN:	SSO's, Work Orders, Line	Condition
		u-		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		ĭ		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$40,100.00		\$40,100.00	
55330 - DESIGN				
55340 - PERMITS	\$1,500.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS 55370 - LEGAL FEES	\$31,700.00			
55370 - LEGAL FEES 55380 - ACQUISITION SERVICES	\$40,000.00			
55390 - COMPENSATION	\$144,000.00			
55400 - APPRAISAL	\$290,000.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	¢1 022 975 00			
55430 - CONST. CONTRACT ADM.	\$1,933,875.00			
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$9,700.00			
TOTAL AMOUNT	\$2,492,875.00	ii <del></del>	\$40,100.00	\$0.00
ENGINEER:	MSD	BD	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	Consultant	# PLATS: [ 35 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$97,000.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$306,200.00
INSPECTION:	MSD		FY 29-30	\$2,049,575.00
			FY 30-31	\$0.00
DDO IECT DESCRIPTION: This	oignt in located in North Ashavilla mass been	phrook Dr and the Crew	FY 31-32	\$0.0
Park Inn. 5,730 feet of 8", 6", and 4"	oject is located in North Asheville near Inns 'VCP line will be replaced with ductile iron.	Sprook or and the Grove The line has experienced	d	\$0.0
	ot issues, structural defects, and I&I.	·	FY 33-34	\$0.0
			FY 34-35	\$0.00




PROJECT:	Johnston Blvd. @ Providence Rd.	LOCATION:	W. Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	11	
PROJECT NO.	2014013	TOTAL LF:	2,086	
PROJECT BUDGET:	\$918,650.00	PROJECT ORIGIN:	SSO's, Access, Line Cond	ition
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$8,150.00	\$8,150.00		
55330 - DESIGN				
55340 - PERMITS	\$6,000.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$15,000.00			
55370 - LEGAL FEES	\$16,500.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION 55400 - APPRAISAL	\$66,000.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	***************************************			
55430 - CONST. CONTRACT ADM.	\$800,000.00			
55440 - TESTING	\$1,000,00			
55450 - SURVEY - ASBUILT	\$1,000.00 \$6,000.00			
TOTAL AMOUNT	\$918,650.00	i <del></del>	\$0.00	\$0.00
	ψ3 10,000.00	<u>n</u>	<del>  \$0.00</del>	ψο.στ
ENGINEER:	MSD	DP	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 14 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$13,300.0
PROJECT DESCRIPTION: This pr	oject is located in West Asheville, approx	. 0.6 miles west of New	FY 31-32	\$90,200.0
Leicester Hwy. The project consists	of replacing 2,000 LF of existing 6-inch vit	trified clay and PVC pipe	FY 32-33	\$807,000.0
with new 8-inch ductile iron pipe. The structural condition.	ne existing line contains many offset joints a	and bends, and is in poor	FY 33-34	\$0.0
			FY 34-35	\$0.0




PROJECT:	Jonestown Road @ Riverside Drive	LOCATION:	Woodfin	
TYPE:	General Sewer Rehab.	PIPE RATING:	52	
PROJECT NO.	2018028	TOTAL LF:	1,992	
PROJECT BUDGET:	\$794,500.00	PROJECT ORIGIN:	CSR's, Work Orders, I & I	issues
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		Transfer of the second		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$13,000.00	\$11,600.00	\$1,400.00	
55330 - DESIGN				
55340 - PERMITS	\$1,000.00		\$1,000.00	
55350 - SPECIAL STUDIES 55360 - EASEMENT PLATS				
55370 - EASEMENT PLATS	\$8,000.00			
55380 - ACQUISITION SERVICES	\$11,000.00	\$8,602.00	\$2,398.00	
55390 - COMPENSATION	#20,000,00	<b>\$04.700.00</b>	#0.007.00	
55400 - APPRAISAL	\$30,000.00	\$21,733.00	\$8,267.00	
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$725,000.00			\$725,000.0
55430 - CONST. CONTRACT ADM.	\$725,000.00			Ψ123,000.0
55440 - TESTING	\$1,500.00			
55450 - SURVEY - ASBUILT	\$5,000.00			
TOTAL AMOUNT	\$794,500.00	\$49,935.00	\$13,065.00	\$725,000.0
ENGINEER:	MSD	тн	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 10 ]	FY 26-27	\$6,500.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
PROJECT DESCRIPTION: This proje	ect is located upstream from MSD's WWTI	P along Riverside Dr. on		\$0.
Jonestown Rd. It consists of approx	ximately 1,992 LF of existing 6-inch VCP to d pip bursting. This system is full of structura	be replaced with 8-inch	FY 32-33	\$0.
issues, and deteriorating manholes.	a pip bursung. Triis system is iun oi structura	ii uciecis, iias lieavy I & I	FY 33-34	\$0.
			FY 34-35	\$0.0



PROJECT:	Kimberly Ave. @ Sedley Avenue	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	51	
PROJECT NO.	2018029	TOTAL LF:	2,947	
PROJECT BUDGET:	\$1,148,622.00	PROJECT ORIGIN:	CSR's, Work Orders, MH O	verflows
		<u>.                                    </u>	1	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$25,175.00	\$25,175.00		
55330 - DESIGN				
55340 - PERMITS	\$1,000.00		\$1,000.00	
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$11,350.00			
55370 - LEGAL FEES	\$15,176.00	\$14,676.00		\$500.0
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION 55400 - APPRAISAL	\$78,921.00	·	\$74,532.00	***
55410 - CONDEMNATION	\$4,000.00			\$4,000.0
55420 - CONSTRUCTION	\$16,000.00			\$16,000.0
55430 - CONST. CONTRACT ADM.	\$985,000.00			\$985,000.0
55440 - TESTING	\$2,000.00			\$2,000.0
55450 - SURVEY - ASBUILT	\$10,000.00			\$10,000.0
TOTAL AMOUNT	\$1,148,622.00	ì	\$77,282.00	\$1,017,500.0
ENGINEER:	MSD	тн	ESTIMATED BUDGET	S - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 11 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
PROJECT DESCRIPTION: This proje	ect is located in N. Asheville along Kimberly	Ave. The existing 6-inch	FY 31-32	\$0.0
VCP will be replaced with 2.947	LF new 8" pipe (predomitely 8-inch HDP	E through pipe bursting	FY 32-33	\$0.0
roots present throughout, mis-aligned	DIP and PVC). This 6-inch VCP line is in d joints, and problematic spur lines.	poor structural condition,		\$0.0
1	•		FY 34-35	\$0.0




PROJECT:	Lakeview @ Glen Falls Rd.	LOCATION:	N. Asheville	
ГҮРЕ:	General Sewer Rehab.	PIPE RATING:	39	
PROJECT NO.	2014007	TOTAL LF:	3,070	
	0.4 = 0.4 0.00 0.0		W 101 1: 0 III	
PROJECT BUDGET:	\$1,721,200.00	PROJECT ORIGIN:	Work Orders, Line Condit	ion, Access
		TOTAL EXPENDS		DUDGET
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$26,000.00	\$6,000.00		
55330 - DESIGN				
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES 55360 - EASEMENT PLATS				
55370 - LEGAL FEES	\$25,700.00			
55380 - ACQUISITION SERVICES	\$31,500.00			
55390 - COMPENSATION	\$112,000.00			
55400 - APPRAISAL	\$262,000.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,250,000.00			
55430 - CONST. CONTRACT ADM.	\$1,230,000.00			
55440 - TESTING	\$3,000.00			
55450 - SURVEY - ASBUILT	\$10,000.00			
FOTAL AMOUNT	\$1,721,200.00	\$6,000.00	\$0.00	\$0.0
ENGINEER:	MSD	DP	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	CONSULTANT	# PLATS: [ 28 ]	FY 26-27	\$261,500.0
CONTRACTOR:			FY 27-28	\$190,700.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$1,263,000.0
NSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
PROJECT DESCRIPTION: This proje	ect is just south of Beaver Lake on Lakeview	Rd., Glen Falls Rd., and	FY 31-32	\$0.
hrough properties on Glen Falls Ro	d. The existing 6-inch clay pipe will be replacenced numerous problems with this line. Appr	ed with 8-inch ductile iron	FY 32-33	\$0.
_akewview Rd was removed from th	inced numerous problems with this line. Appr his project and will be constructed by In-House	e crew.	FY 33-34 FY 34-35	\$0.




PROJECT:	Lakewood Drive @ Dudley Ave.	LOCATION:	Asheville	
ГҮРЕ:	General Sewer Rehab.	PIPE RATING:	7	
PROJECT NO.	2015016	TOTAL LF:	280	
DO IFOT BURGET	\$400.050.00		0001- 4 1: 0	***
PROJECT BUDGET:	\$122,050.00	PROJECT ORIGIN:	SSO's, Access, Line Cond	ition
	ESTIMATED	TOTAL EXPENDS	EST. COST	BUDGET
DESCRIPTION	PROJECT COST	THRU 12/31/24	JAN - JUNE 2025	FY 25-26
5310 - PRELIM. ENGINEERING				
5320 - SURVEY - DESIGN	\$2,000.00			
55330 - DESIGN	ΨΣ,000.00			
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$3,450.00			
55370 - LEGAL FEES	\$3,500.00			
55380 - ACQUISITION SERVICES	,			
55390 - COMPENSATION	\$20,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$91,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$1,100.00			
TOTAL AMOUNT	\$122,050.00	\$0.00	\$0.00	\$0.0
			1	
NGINEER:	MSD	BD	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 3 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
NSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
PROJECT DESCRIPTION: This proj	ect is located on Lakewood Dr. in the Ke	nilworth neiahborhood o	FY 31-32	\$2,000.0
Asheville. It consists of replacing	approx. 280 LF of existing 8-inch VCP wi	th new 8-inch DIP. The	FY 32-33	\$2,600.0
existing line runs adjacent to a hous ntrusion.	e foundation and is difficult to maintain. This	s line has a history of roof	FY 33-34	\$24,350.0
TIL GOLOTI.			FY 34-35	\$93,100.0




PROJECT:	Lincoln Avenue	LOCATION:	Asheville	
	Elligoni, trongo		Adiovino	
TYPE:	General Sewer Rehab.	PIPE RATING:	4	
PROJECT NO.	2013103	TOTAL LF:	1,415	
PROJECT BUDGET:	\$609,570.00	PROJECT ORIGIN:	Work Orders, Line Condi	tion, Access
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$2,870.00	\$2,870.00		
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$601,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$4,000.00			
55450 - SURVEY - ASBUILT	\$1,700.00			
TOTAL AMOUNT	\$609,570.00	\$2,870.00	\$0.00	\$0.00
			1	
ENGINEER:	MSD	BD	ESTIMATED BUDGI	ETS - FY 27 - 35
R.O.W. ACQUISITION:	N/A	#PLATS: [ 0 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
DDO IFOT DECODIDATION. This is	and the least of the Oalders are included and	-1 i	FY 31-32	\$0.0
	roject is located in the Oakley neighborhoo lacing approximately 1,415 LF of existing 6-ir			\$0.0
	line is in very poor structural condition.	, , ,	FY 33-34	\$0.0
			FY 34-35	\$606,700.00




PROJECT:	Lining Contract #10	LOCATION:	Various	
TYPE:	General Sewer Rehab.	PIPE RATING:	NA	
PROJECT NO.	2024035	TOTAL LF:	12,015	
PROJECT BUDGET:	\$3,604,500.00	PROJECT ORIGIN:	Access, Line Condition	
	ESTIMATED	TOTAL EXPENDS	EST. COST	BUDGET
DESCRIPTION	PROJECT COST	THRU 12/31/24	JAN - JUNE 2025	FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN				
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$3,604,500.00			
55430 - CONST. CONTRACT ADM.	φ3,004,300.00			
55440 - TESTING				
55450 - SURVEY - ASBUILT				
TOTAL AMOUNT	\$2 CO4 FOO OO		£0.00	£0.00
	\$3,604,500.00	\$0.00	\$0.00	\$0.00
ENGINEER:	MSD	TH	ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]	FY 26-27	\$3,604,500.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
			FY 31-32	\$0.00
PROJECT DESCRIPTION: Various li	ining locatoins throughout MSD sewer o	district totaling to 12 015	FY 32-33	\$0.00
linear feet	g locatorio arroagnoat Mob 3eWel C	action totaling to 12,010	FY 33-34	\$0.00
			FY 34-35	\$0.00
SPECIAL PROJECT NOTES:			<u>  </u>	φυ.υυ




PROJECT:	Logan Avenue	LOCATION:	W. Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	48	
PROJECT NO.	2017256	TOTAL LF:	1,623	
PROJECT BUDGET:	\$962,137.00	PROJECT ORIGIN:	Work Orders, Line Conditi	on
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		10		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$13,500.00	\$11,500.00	\$2,000.00	
55330 - DESIGN				
55340 - PERMITS	\$1,000.00		\$1,000.00	
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$12,800.00	\$10,400.00	\$1,300.00	\$1,100.00
55370 - LEGAL FEES	\$16,000.00		\$13,000.00	\$3,000.00
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$83,337.00		\$20,000.00	\$63,337.00
55400 - APPRAISAL	\$8,000.00			\$8,000.00
55410 - CONDEMNATION	\$32,000.00			\$12,000.00
55420 - CONSTRUCTION	\$791,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$3,500.00			
TOTAL AMOUNT	\$962,137.00	\$21,900.00	\$37,300.00	\$87,437.00
ENGINEER:		MSD SA		TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 13 ]	FY 26-27	\$815,500.00
CONTRACTOR:	MCD		FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
			FY 31-32	\$0.00
PROJECT DESCRIPTION: This project is located in West Asheville near Craven St. and co 2,150 LF of 8-inch DIP. The existing clay pipe is undersized and has a large number of pipe defe		ven St. and consists of the of pine defects		\$0.00
2,100 Er of o mon bir . The existing	ora, pipe is andorsized and has a raige hum	iso, or pipe defects.	FY 33-34	\$0.00
<u>i</u>			FY 34-35	\$0.00




ROJECT:	Louisiana Avenue	LOCATION:	W. Asheville	
YPE:	General Sewer Rehab	PIPE RATING:	12	
PROJECT NO.	2015174	TOTAL LF:	2,150	
PROJECT BUDGET:	\$1,023,500.00	PROJECT ORIGIN:	Undersized, Line Condition	on
DESCRIPTION	ESTIMATED	TOTAL EXPENDS	EST. COST	BUDGET
DESCRIPTION	PROJECT COST	THRU 12/31/24	JAN - JUNE 2025	FY 25-26
5310 - PRELIM. ENGINEERING				
5320 - SURVEY - DESIGN	\$15,000.00			
5330 - DESIGN				
5340 - PERMITS				
5350 - SPECIAL STUDIES				
5360 - EASEMENT PLATS				
5370 - LEGAL FEES				
5380 - ACQUISITION SERVICES				
5390 - COMPENSATION				
5400 - APPRAISAL				
5410 - CONDEMNATION				
5420 - CONSTRUCTION	\$1,000,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,500.00			
5450 - SURVEY - ASBUILT	\$6,000.00			
OTAL AMOUNT	\$1,023,500.00	\$0.00	\$0.00	\$0.
			ii-	
NGINEER:	MSD	DP	ESTIMATED BUDGETS - FY 27 -	
R.O.W. ACQUISITION:		# PLATS: [ 0 ]	FY 26-27	\$0.
CONTRACTOR:			FY 27-28	\$0.
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.
NSPECTION:	MSD		FY 29-30	\$0.
			FY 30-31	\$15,000
			FY 31-32	\$0.
ROJECT DESCRIPTION: This project is located in West Asheville along Louisiana Avenue. The project is replace 2,150 LF of 6-inch VCP. The existing lines are undersized, in bad condition, and have to		ana Avenue. The project condition, and have too	FY 32-33 \$1,008,	
nany point repairs.	<u> </u>	, 3	FY 33-34	\$0
			FY 34-35	\$0.




PROJECT:	Lower Glendale Ave.	LOCATION:	E. Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	23	
PROJECT NO.	2012083	TOTAL LF:	2,716	
PROJECT BUDGET:	\$1,449,700.00	PROJECT ORIGIN:	SSO's, Work Orders, Li	ne Condition
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55240 DDELIM ENGINEEDING				
55310 - PRELIM. ENGINEERING 55320 - SURVEY - DESIGN				
55330 - DESIGN	\$6,650.00	\$6,650.00		
55340 - PERMITS	040,000,00			
55350 - SPECIAL STUDIES	\$10,000.00			
55360 - EASEMENT PLATS	\$7,650.00			
55370 - LEGAL FEES	\$10,000.00			
55380 - ACQUISITION SERVICES	\$10,000.00			
55390 - COMPENSATION	\$37,000.00			
55400 - APPRAISAL	,			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,370,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$4,000.00			
55450 - SURVEY - ASBUILT	\$4,400.00			
TOTAL AMOUNT	\$1,449,700.00	\$6,650.00	\$0.00	\$0.00
	HOD		T	
ENGINEER:		MSD BD		GETS - FY 27 - 35
R.O.W. ACQUISITION:  CONTRACTOR:	MSD	# PLATS: [ 8 ]	FY 26-27 FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$16,800.00
INSPECTION:	MSD		FY 29-30	\$0.00
INSPECTION.	MOD		FY 30-31	\$47,850.00
			FY 31-32	\$1,378,400.00
PROJECT DESCRIPTION: This project is located in S.E. Asheville near the Oakley neighborhood. It		FY 32-33 \$0.00		
consists of replacing approximately 2	onsists of replacing approximately 2,716 LF of existing 10-inch and 12-inch vitrified clay pipe alo illendale Ave. The existing line is subject to inflow and infiltration, is in poor condition, and undersized.		g	
Gleridale Ave. The existing line is subj	ect to initiow and intilitration, is in poor condi	ulon, and undersized.	FY 34-35	\$0.00
SPECIAL PROJECT NOTES: Portions of this project overlap with the South Swannanoa Wet Weather project #4 identifie			<u> </u>	\$0.00
	· · ·			



PROJECT:	Manetta Rd. @ Johnson Dr.	LOCATION:	N. Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	24	
PROJECT NO.	2014022	TOTAL LF:	5,340	
PROJECT BUDGET:	\$2,898,787.00	PROJECT ORIGIN:	SSO's, Work Orders, Line	Condition
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING			l I	
55320 - SURVEY - DESIGN	¢50,300,00	\$35,600,000	¢14.700.00	
55330 - DESIGN	\$50,300.00	\$35,600.00	\$14,700.00	
55340 - PERMITS	\$1,000,00		¢1 000 00	
55350 - SPECIAL STUDIES	\$1,000.00	4	\$1,000.00	
55360 - EASEMENT PLATS	\$17,850.00			\$16,150.0
55370 - LEGAL FEES	\$17,850.00			\$10,130.
55380 - ACQUISITION SERVICES	\$76,000.00			\$25,000.
55390 - COMPENSATION	\$226,000.00			\$80,000.0
55400 - APPRAISAL	\$8,000.00			Ψ00,000.
55410 - CONDEMNATION	\$32,000.00			
55420 - CONSTRUCTION	\$2,448,137.00			
55430 - CONST. CONTRACT ADM.	<del></del>	ψο 12,101100		
55440 - TESTING	\$2,500.00	\$1,157.00		
55450 - SURVEY - ASBUILT	\$15,000.00			
TOTAL AMOUNT	\$2,898,787.00	\$348,894.00	\$15,700.00	\$141,150.0
		•		
ENGINEER:	MSD TH		ESTIMATED BUDGETS - FY 27 - 3	
R.O.W. ACQUISITION:	Consultant	# PLATS: [ 19 ]	FY 26-27	\$224,700.0
CONTRACTOR:			FY 27-28	\$2,168,343.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
NSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
PROJECT DESCRIPTION: This General Sewer Rehabilitation project is located in North Ashavilla poo		FY 31-32	\$0.0	
<b>PROJECT DESCRIPTION:</b> This General Sewer Rehabilitation project is located in North Asheville near Merrimon Ave and consists of 6500 LF of 8" DIP/HDPE. The existing clay pipe is undersized and has multiple SSO's, voids, fractures, and root intrusions. Portions of Other Rd were constructed in FY 22 in a section with a CSA reviews, and root intrusions.			S FY 32-33	
			PY 33-34	
conjunction with a CoA paving project. The project has approximately 5340 LF remaining.		maining.	FY 34-35	




PROJECT:	Maplewood Rd. @ Griffing Circle	LOCATION:	N. Asheville	
	g energ			
TYPE:	General Sewer Rehab.	PIPE RATING:	51	
PROJECT NO.	2025000	TOTAL LF:	1,850	
PROJECT BUDGET:	\$884,500.00	PROJECT ORIGIN:	Work Orders, Line Conditi	on
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
FERMA PRELIM ENGINEERING		N		
55310 - PRELIM. ENGINEERING 55320 - SURVEY - DESIGN		-		
55320 - SURVEY - DESIGN 55330 - DESIGN	\$15,000.00			\$15,000.0
55330 - DESIGN 55340 - PERMITS				
55350 - SPECIAL STUDIES	\$1,000.00			
55350 - SPECIAL STODIES 55360 - EASEMENT PLATS				
55370 - LEGAL FEES	\$15,000.00			
55380 - ACQUISITION SERVICES	\$18,500.00			
55390 - COMPENSATION	\$175,000.00			
55400 - APPRAISAL	\$8,000.00			
55410 - CONDEMNATION	\$32,000.00			
55420 - CONSTRUCTION	\$615,000.00			
55430 - CONST. CONTRACT ADM.	Ψ010,000.00			
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$4,000.00			
TOTAL AMOUNT	\$884,500.00	ĺ	\$0.00	\$15,000.0
ENGINEER:	MSD	MSD SA		TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 16 ]	FY 26-27	\$91,600.0
CONTRACTOR:			FY 27-28	\$777,900.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
			FY 31-32	\$0.0
PROJECT DESCRIPTION: This project is located in North Asheville, along Maplewood Rd and Griffing Cir The existing line is 6" and 8" vitrified clay pipe, with many structural defects, requiring extensive				\$0.
	rified clay pipe, with many structural defi ed with approximately 1,850 LF of 8" DIP.	ecis, requiring extensive	FY 33-34	\$0.0
			FY 34-35	




PROJECT:	McDowell St. @ Lily Carmichael Dr.	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	21	
PROJECT NO.	2021011	TOTAL LF:	1,660	
PROJECT BUDGET:	\$721,500.00	PROJECT ORIGIN:	Work Orders, Line Condit	ion
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING		<u> </u>	T	
55320 - SURVEY - DESIGN	\$11,000.00			
55330 - DESIGN	\$11,000.00			
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES	Ψ1,000.00			
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$705,500.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$3,000.00			
TOTAL AMOUNT	\$721,500.00	\$0.00	\$0.00	\$0.0
			<u> </u>	
ENGINEER:	MSD	SA	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:		# PLATS: [ 0 ]	FY 26-27	\$11,000.0
CONTRACTOR:	MOD		FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$1,000.0
NSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$709,500.
PROJECT DESCRIPTION: This proje	ect is located in downtown Asheville, along l	McDowell St near Mission	FY 31-32	\$0.
Hospital's main campus. The existir	ng line is 6 and 8-inch vitrified clay pipe, witl	n many structural defects	,	\$0.
requiring extensive maintenance. Th	nis line will be replaced with approximately 1,	660 LF of 8-inch DIP.	FY 33-34	\$0.
			FY 34-35	\$0.0




PROJECT:	McDowell St. @ Myrtle St.	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	19	
PROJECT NO.	2019257	TOTAL LF:	465	
PROJECT BUDGET:	\$308,850.00	PROJECT ORIGIN:	Access, Line Condition	
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$3,500.00			
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$4,850.00			
55370 - LEGAL FEES	\$5,000.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$93,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$200,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING				
55450 - SURVEY - ASBUILT	\$2,500.00	ii <del></del>		
TOTAL AMOUNT	\$308,850.00	\$0.00	0 \$0.00	\$0.0
ENGINEER:	MSD	DP	ESTIMATED BUDGE	 ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	#PLATS: [ 4 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$3,500.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$4,000.0
NSPECTION:	MSD		FY 29-30	\$98,850.0
			FY 30-31	\$202,500.0
			FY 31-32	\$0.0
PROJECT DESCRIPTION: This project	ct consists of a spur line that runs through p	roperties along McDowel	FY 32-33	\$0.0
	St. The existing clay line runs under a building poor condition of this system is creating I&I i		FY 33-34	\$0.0
-			FY 34-35	\$0.0




PROJECT:	Meadow Road @ Train Yard	LOCATION:	Asheville	
	<del>-</del>			
TYPE:	General Sewer Rehab.	PIPE RATING:	6	
1				
PROJECT NO.	2015207	TOTAL LF:	2,001	
PROJECT BUDGET:	\$2,271,350.00	PROJECT ORIGIN:	Line Condition, Undersiz	ed
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$7,000.00	\$7,000.00		
55330 - DESIGN				
55340 - PERMITS	\$22,500.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$3,850.00			
55370 - LEGAL FEES	\$32,000.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$40,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$2,157,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$3,000.00			
55450 - SURVEY - ASBUILT	\$6,000.00			
TOTAL AMOUNT	\$2,271,350.00	\$7,000.00	\$0.00	\$0.00
ENGINEER:	MSD	BD	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	#PLATS: [ 3 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
		B	FY 31-32	\$0.00
and AB Tech College. It consists of	ct is located in Asheville on Meadow Rd. bet replacing 2,001 LF of existing 6-inch VCP v	ween the Biltmore Estate with new 8-inch DIP. The	FY 32-33	\$3,000.00
	ndersized, and runs underneath various struc		FY 33-34	\$95,350.0
			FY 34-35	\$2,166,000.00




PROJECT:	Merrimon Ave. @ Clearview Terrace	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	6	
PROJECT NO.	2007012	TOTAL LF:	500	
PROJECT BUDGET:	\$313,950.00	PROJECT ORIGIN:	SSO's, Access, Line Cond	ition
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		*		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$5,700.00	\$3,200.00		
55330 - DESIGN				
55340 - PERMITS	\$750.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$4,500.00	\$1,390.00		
55370 - LEGAL FEES	\$11,000.00	\$1,454.00		
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$57,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$233,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$1,000.00			
TOTAL AMOUNT	\$313,950.00	\$6,044.00	\$0.00	\$0.00
			i	
ENGINEER:	MSD	ТН	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 4 ]	FY 26-27	\$0.00
CONTRACTOR:	MOD		FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.0
PPO IECT DESCRIPTION. This proje	ct is located along Merrimon Avenue, in the a	area of Clearview Terrocc	FY 31-32	\$68,360.0
and Farrwood Avenue. The existing	g line is an old 4-inch main that is in very p	poor condition and will be		\$4,546.0
replaced with approximately 500LF of	of 8-inch DIP.		FY 33-34	\$0.0
			FY 34-35	\$235,000.00




PROJECT:	Merrimon Ave. @ Coleman Ave.	LOCATION:	N. Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	6	
PROJECT NO.	2014009	TOTAL LF:	2,800	
PROJECT BUDGET:	\$1,282,000.00	PROJECT ORIGIN:	Work Orders, Line Condit	ion
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$20,000.00			
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,250,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$4,000.00			
55450 - SURVEY - ASBUILT	\$8,000.00			
TOTAL AMOUNT	\$1,282,000.00	\$0.00	\$0.00	\$0.00
			TI-	
ENGINEER:	MSD	DP	ESTIMATED BUDGI	ETS - FY 27 - 35
R.O.W. ACQUISITION:	N/A	# PLATS: [ 0 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.0
			FY 31-32	\$0.0
PROJECT DESCRIPTION: This projection is old and has numerous defection.	ct is on Merrimon Ave., Coleman Ave., and A	Austin Ave. Existing cla ustin, and the 8-inch cla	vII	\$20,000.0
pipe on Merrimon will all be replaced		,	FY 33-34	\$0.0
			FY 34-35	\$1,262,000.00




PROJECT:	Mitchell Avenue	LOCATION:	W. Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	8	
PROJECT NO.	2014185	TOTAL LF:	3,360	
PROJECT BUDGET:	\$1,518,750.00	PROJECT ORIGIN:	Work Orders, Line Cond	ition
		II.		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$24,000.00			
55330 - DESIGN				
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS 55370 - LEGAL FEES	\$9,000.00			
55370 - LEGAL FEES 55380 - ACQUISITION SERVICES	\$9,000.00			
55390 - ACQUISITION SERVICES  55390 - COMPENSATION				
55400 - APPRAISAL	\$70,000.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$4.400.000.00			
55430 - CONST. CONTRACT ADM.	\$1,400,000.00			
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$3,750.00			
TOTAL AMOUNT	\$1,518,750.00	ii	00 \$0.00	\$0.0
	**,************************************		<u> </u>	,,,,,
ENGINEER:	MSD	SA	ESTIMATED BUDG	GETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 8 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$24,000.
DDO IFOT DECORISTION TO		A I	FY 31-32	\$9,500.
PROJECT DESCRIPTION: This pr Rd. and is comprised of 3,360 LF of	oject is located in West Asheville between Pa 8-inch ductile iron pipe. The existing line is 6	atton Ave. and Haywo B-inch vitrified clay pipe	PY 32-33 in	\$79,500.
	fects that cannot be adequately repaired by p		FY 33-34	\$1,405,750.
			FY 34-35	\$0.0



PROJECT:	Montford Ave. @ Montford Park	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	59	
PROJECT NO.	2017144	TOTAL LF:	1,129	
PROJECT BUDGET:	\$754,739.00	PROJECT ORIGIN:	Sags, Structural Defects, S	oil Pipe
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$7,325.00	\$7,325.00		
55330 - DESIGN				
55340 - PERMITS	\$1,000.00		\$1,000.00	
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$9,400.00	\$8,850.00	\$550.00	
55370 - LEGAL FEES	\$14,000.00	\$9,213.00	\$3,787.00	\$1,000.00
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$89,514.00	\$2,405.00	\$57,049.00	\$30,060.00
55400 - APPRAISAL	\$7,000.00			\$7,000.00
55410 - CONDEMNATION	\$32,000.00		\$5,000.00	\$27,000.00
55420 - CONSTRUCTION	\$590,000.00			\$590,000.00
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,000.00			\$2,000.00
55450 - SURVEY - ASBUILT	\$2,500.00			\$2,500.00
TOTAL AMOUNT	\$754,739.00	\$27,793.00	\$67,386.00	\$659,560.00
ENGINEER:	MSD	BD # DI 470	ESTIMATED BUDGET	S - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 11 ]	FY 26-27	\$0.00
CONTRACTOR:  CONSTRUCTION ADM:	MSD		FY 27-28 FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
INSPECTION.	INIOD			\$0.00
			FY 30-31 FY 31-32	\$0.00
PROJECT DESCRIPTION: This	project is located just south of Montford	d Park and includes the		\$0.00
replacement of approximately 1,129	LF of existing 8-inch VCP with new 8-inch D	IP. The existing pipe has		\$0.0
sags, multiple structural defects, and	areas where the pipe is almost non-existent		FY 33-34	\$0.00
			FY 34-35	\$0.00




PROJECT:	New Haw Creek @ Cisco Rd.	LOCATION:	Asheville	
			7.00	
TYPE:	General Sewer Rehab.	PIPE RATING:	54	
PROJECT NO.	2025002	TOTAL LF:	700	
PROJECT BUDGET:	\$316,200.00	PROJECT ORIGIN:	SSO's, Line Condition	
		<u> </u>	1	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING			+	
55320 - SURVEY - DESIGN 55330 - DESIGN	\$4,900.00			\$4,900.00
55330 - DESIGN 55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$6,800.00			\$5,800.00
55370 - LEGAL FEES	\$8,000.00			φ3,800.00
55380 - ACQUISITION SERVICES	\$6,000.00			
55390 - COMPENSATION	\$42,000.00			
55400 - APPRAISAL	\$4,000.00			
55410 - CONDEMNATION	\$16,000.00			
55420 - CONSTRUCTION	\$232,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$500.00			
55450 - SURVEY - ASBUILT	\$2,000.00			
TOTAL AMOUNT	\$316,200.00	\$0.0	0 \$0.00	\$10,700.00
ENCINEED.	MSD	DD.	FOTIMATED BLIDG	FTC FV 27 25
ENGINEER: R.O.W. ACQUISITION:	MSD	# PLATS: [ 7 ]	FY 26-27	
CONTRACTOR:	MOD	#1EA10. [ 7 ]	FY 27-28	\$71,000.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$234,500.00 \$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
			FY 31-32	\$0.00
PROJECT DESCRIPTION: This p	roject is located in the Haw Creek Area.	The project consists of	FY 32-33	\$0.00
	6-inch vitrified clay pipe with 8-inch ductile in aced overflows. One line runs under a house.		FY 33-34	\$0.00
			FY 34-35	\$0.00




#### **BUDGET DATA SHEET - FY 2025 - 2026** PROJECT: New Haw Creek Rd. @ Dogwood Grove LOCATION: E. Asheville TYPE: General Sewer Rehab. PIPE RATING: 8 PROJECT NO. 2014021 TOTAL LF: 3,000 PROJECT BUDGET: \$982,775.00 PROJECT ORIGIN: SSO's, Work Orders, Line Condition TOTAL EXPENDS EST. COST BUDGET **ESTIMATED** DESCRIPTION PROJECT COST THRU 12/31/24 **JAN - JUNE 2025** FY 25-26 55310 - PRELIM. ENGINEERING 55320 - SURVEY - DESIGN \$8,525.00 \$4,925.00 \$3,600.00 55330 - DESIGN 55340 - PERMITS \$1,000.00 55350 - SPECIAL STUDIES 55360 - EASEMENT PLATS \$14,750.00 55370 - LEGAL FEES \$18,000.00 55380 - ACQUISITION SERVICES 55390 - COMPENSATION \$36,000.00 55400 - APPRAISAL 55410 - CONDEMNATION 55420 - CONSTRUCTION \$900,000.00 55430 - CONST. CONTRACT ADM. 55440 - TESTING \$1,000.00 55450 - SURVEY - ASBUILT \$3,500.00 TOTAL AMOUNT \$982,775.00 \$4,925.00 \$3,600.00 \$0.00 ENGINEER: MSD **ESTIMATED BUDGETS - FY 27 - 35** R.O.W. ACQUISITION: MSD # PLATS: [ 15 ] FY 26-27 \$0.00 CONTRACTOR: FY 27-28 \$0.00 CONSTRUCTION ADM: MSD FY 28-29 \$46,000.00 INSPECTION: MSD FY 29-30 \$20,750.00 FY 30-31 \$3,000.00 FY 31-32 \$0.00 PROJECT DESCRIPTION: This project is in East Asheville near Haw Creek Rd., and consists of 3,000 LF or 8-inch ductile iron pipe. Existing 4-inch and 6-inch clay pipe is undersized, with fractures, root intrusion, and FY 32-33 \$0.00 misaligned joints. Existing 8-inch ductile iron pipe has corrosion issues. Existing manholes are in poor \$904,500.00 condition. FY 34-35 \$0.00


SPECIAL PROJECT NOTES:




PROJECT:	New Stock Road	LOCATION:	Weaverville	
TYPE:	General Sewer Rehab.	PIPE RATING:	23	
PROJECT NO.	2015011	TOTAL LF:	9,020	
PROJECT BUDGET:	\$5,520,900.00	PROJECT ORIGIN:	SSO's, Undersized Pipe	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$36,000.00	\$17,750.00	\$18,250.00	
55330 - DESIGN				
55340 - PERMITS	\$2,000.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$40,400.00			
55370 - LEGAL FEES	\$46,500.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION 55400 - APPRAISAL	\$46,000.00			
55410 - APPRAISAL 55410 - CONDEMNATION	\$16,000.00			
55420 - CONSTRUCTION	\$44,000.00			
55430 - CONST. CONTRACT ADM.	\$5,250,000.00			
55440 - TESTING	\$40,000,00			
55450 - SURVEY - ASBUILT	\$10,000.00 \$30,000.00			
TOTAL AMOUNT	\$5,520,900.00	ii	\$18,250.00	\$0.0
	\$5,020,000.00	,	<b>\$10,200.00</b>	Ψ0.0
ENGINEER:	MSD	DP	ESTIMATED BUDG	GETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 44 ]	FY 26-27	\$97,000.0
CONTRACTOR:			FY 27-28	\$97,900.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$5,290,000.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
			FY 31-32	\$0.0
PROJECT DESCRIPTION: This project New Stock Rd., runs under I-26. ar	ct runs along New Stock Rd. The project be nd ends at Weaverville Rd. The existing 8-i	gıns at Nichols Hill Dr. & nch lines have structural	FY 32-33	\$0.0
issues which have led to root intrusion			FY 33-34	\$0.0
			FY 34-35	\$0.0




PROJECT:	North Market Street	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	6	
PROJECT NO.	2014019	TOTAL LF:	1,064	
PROJECT BUDGET:	\$443,300.00	PROJECT ORIGIN:	Work Orders, Line Condi	tion
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$5,300.00	\$3,875.00		
55330 - DESIGN				
55340 - PERMITS	\$500.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$435,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$1,500.00			
TOTAL AMOUNT	\$443,300.00	\$3,875.00	\$0.00	\$0.00
ENGINEER:	MSD	SA	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:		# PLATS: [ 0 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
PROJECT DESCRIPTION: This pro	oject is located in downtown Asheville and c	onsists of 1.064 LF of 8-	FY 31-32	\$1,425.00
inch ductile iron pipe. The existing	6-inch clay line is undersized, has multiple s		FY 32-33	\$500.00
caused flooded structures.			FY 33-34	\$0.0
			FY 34-35	\$437,500.00



PROJECT:	North Street @ Broadway Street	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	12	
··· <del>-</del>			·-	
PROJECT NO.	2018030	TOTAL LF:	1,067	
PROJECT BUDGET:	\$459,500.00	PROJECT ORIGIN:	Work Orders, Line Condit	ion
		<u> </u>	<u> </u>	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$12,500.00			
55330 - DESIGN				
55340 - PERMITS 55350 - SPECIAL STUDIES	\$500.00			
55350 - SPECIAL STUDIES 55360 - EASEMENT PLATS				
55370 - LEGAL FEES	\$10,000.00			
55380 - ACQUISITION SERVICES	\$9,500.00			
55390 - COMPENSATION	\$23,000.00			
55400 - APPRAISAL	\$23,000.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$400,000.00			-
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$3,000.00			
TOTAL AMOUNT	\$459,500.00	\$0.00	\$0.00	\$0.00
			ıı	
ENGINEER:	MSD	TH	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 8 ]	FY 26-27	\$0.00
CONTRACTOR:  CONSTRUCTION ADM:	MSD		FY 27-28 FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$13,000.00
INOI EOTION.	Med		FY 30-31	\$0.00 \$42,500.00
			FY 31-32	· · ·
	neral Sewer Rehabilitation project in North A Broadway St. Currently this public system		1	\$0.00 \$404,000.00
consists of approximately 1,067 LF of	of existing 6-inch VCP to be replaced with 8-in	nch DIP. This 6-inch VCF		\$404,000.00
system is full of structural defects, ha	as heavy root intrusion, and many point repai	rs.	FY 34-35	\$0.00




PROJECT:	Oakland Drive @ Church Street	LOCATION:	Black Mountain	
-ROJECT.	Oakland Brive & Church Street	ECCATION.	Diack Mountain	
ГҮРЕ:	General Sewer Rehab	PIPE RATING:	9	
PROJECT NO.	2015177	TOTAL LF:	575	
PROJECT BUDGET:	\$241,500.00	PROJECT ORIGIN:	Access, Line Condition	
		T		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		-u		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$5,000.00			
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$4,500.00			
55370 - LEGAL FEES	\$5,500.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$24,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$200,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$1,500.00			
TOTAL AMOUNT	\$241,500.00	\$0.00	0 \$0.00	\$0.00
ENGINEER:	MSD	DP	ESTIMATED BUDG	GETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 4 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
NSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$5,000.0
			FY 31-32	\$3,650.0
PROJECT DESCRIPTION: This proj	ect is located in Black Mountain running thro	ough properties from Pine	FY 32-33	\$30,350.0
St to Oakland Dr. The project will re are in poor condition and have too i	eplace 575 LF of 4-inch Orangeburg and 6-inc many point repairs.	ch VCP. The existing lines	FY 33-34	\$202,500.0
poor containon and have too i			FY 34-35	\$0.0



PROJECT:	Oakwood Street	LOCATION:	W. Asheville	
ricolo I.	Oakwood Street	LOCATION.	W. Asheville	
ГҮРЕ:	General Sewer Rehab.	PIPE RATING:	9	
PROJECT NO.	2014155	TOTAL LF:	976	
PROJECT BUDGET:	\$445,350.00	PROJECT ORIGIN:	Work Orders, Line Conditi	on
		l		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING			T	
55320 - SURVEY - DESIGN	\$7,000.00			
55330 - DESIGN	. , , , , , , , , , , , , , , , , , , ,			
55340 - PERMITS				
55350 - SPECIAL STUDIES				
5360 - EASEMENT PLATS	\$3,450.00			
5370 - LEGAL FEES	\$3,500.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$37,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$391,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$1,400.00			
TOTAL AMOUNT	\$445,350.00	\$0.00	\$0.00	\$0.0
			<u> </u>	
ENGINEER:	MSD	SD BD		TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 3 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
NSPECTION:	MSD		FY 29-30	\$7,000.0
			FY 30-31	\$2,600.0
PROJECT DESCRIPTION: This or	oject is located in West Asheville on Oakwo	od St., approximatelv 0.6	FY 31-32	\$0.0
PROJECT DESCRIPTION: This project is located in West Asheville on Oakwood St., approximately 0.6 nile east of the the Patton Ave./Haywood Rd. intersection. Approximately 976 LF of existing 6-inch VCF			P FY 32-33 \$41,3	
and Orangeburg pipe will be replace undersized for the neighborhood it se	pipe will be replaced with 8-inch DIP. The existing line has structural problems and is			\$394,400.0
and an area in the merginbornood it se			FY 34-35	\$0.0



PROJECT:	Old Toll Rd. @ Blue Briar Rd.	LOCATION:	Asheville	
PROJECT.	Old Toll Rd. @ Blue Briar Rd.	LOCATION.	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	14	
PROJECT NO.	2018032	TOTAL LF:	185	
PROJECT BUDGET:	\$81,000.00	PROJECT ORIGIN:	CSR's, Work Orders	
		<u>'</u>		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING			T	
55320 - SURVEY - DESIGN	\$3,000.00			
55330 - DESIGN				
55340 - PERMITS	\$500.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$1,500.00			
55370 - LEGAL FEES	\$1,500.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$7,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$65,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$1,500.00			
TOTAL AMOUNT	\$81,000.00	\$0.00	\$0.00	\$0.0
ENGINEER:	MSD	TH		TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 1 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
NSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$3,500.0
PROJECT DESCRIPTION: This G	eneral Sewer Rehabilitation project is lo	cated in North Asheville	FY 31-32	\$10,000.0
stretching between Blue Briar Rd. and Old Toll Rd. Currently this public system planned for rehabilitation			FY 32-33	\$67,500.0
consists of approximately 185 LF of	of approximately 185 LF of existing 6-inch VCP to be replaced with 8-inch DIP. This 6-inch VCF full of structural defects and bends that prevent proper maintenance.			\$0.0
2,5to to fail of structural delects all	a sonas that provent proper maintenance.		FY 34-35	\$0.0



PROJECT:	Old Turnpike Rd. @ Azalea	LOCATION:	Arden	
TYPE:	Pipe Rated Projects	PIPE RATING:	35	
PROJECT NO.	2023255	TOTAL LF:	1,168	
PROJECT BUDGET:	\$497,900.00	PROJECT ORIGIN:	Pipe Rating Program	
	<del></del>		- ipo itamig i rogiam	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING		1	T T	
55320 - SURVEY - DESIGN	¢40,000,00		¢40,000,00	
55330 - DESIGN	\$10,000.00		\$10,000.00	
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES	ψ1,000.00			
55360 - EASEMENT PLATS	\$11,900.00			\$11,050.00
55370 - LEGAL FEES	\$16,000.00			\$15,000.00
55380 - ACQUISITION SERVICES				, ,
55390 - COMPENSATION	\$60,000.00			\$40,000.00
55400 - APPRAISAL	\$8,000.00			
55410 - CONDEMNATION	\$32,000.00			
55420 - CONSTRUCTION	\$355,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$3,000.00			
TOTAL AMOUNT	\$497,900.00	\$0.00	\$10,000.00	\$66,050.00
ENGINEER:	MSD TH		ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 13 ]	FY 26-27	\$46,850.00
CONTRACTOR:			FY 27-28	\$375,000.00
CONSTRUCTION ADM.:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
			FY 31-32	\$0.00
	ect is located in Arden off of Sweten Cr elocating the line a minimum of 10' from top			\$0.0
	/I, and crosses the creek multiple times with		FY 33-34	\$0.0
			FY 34-35	\$0.00



PROJECT:	Parkwood Avenue	LOCATION:	Woodfin	
TYPE:	General Sewer Rehab.	PIPE RATING:	31	
PROJECT NO.	2021286	TOTAL LF:	1,165	
PROJECT BUDGET:	\$453,685.00	PROJECT ORIGIN:	Work Orders, Excessive	Infiltration
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		<u> </u>	1 1	
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$10,485.00			
55330 - DESIGN				
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$10,200.00			
55370 - LEGAL FEES	\$12,500.00			
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$65,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION 55420 - CONSTRUCTION				
55430 - CONST. CONTRACT ADM.	\$349,500.00			
55440 - TESTING	40.000.00			
55450 - SURVEY - ASBUILT	\$2,000.00			
TOTAL AMOUNT	\$3,000.00 \$453,685.00	ii <del></del>	\$0.00	\$0.0
	ψ <del></del>	<u>JI                                    </u>	ψυ.υυ	Ψ0.0
ENGINEER:	MSD	тн	ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	MSD	MSD #PLATS: [ 11 ]		\$11,485.0
CONTRACTOR:			FY 27-28	\$9,350.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$77,850.0
INSPECTION:	MSD		FY 29-30	\$355,000.0
			FY 30-31	\$0.0
			FY 31-32	\$0.0
	ROJECT DESCRIPTION: This project is located in Woodfin. The existing line is approximately 1,165 L			\$0.0
of 6" VCP with known SSO's and I/I	due to structural defects.		FY 33-34	\$0.0
			FY 34-35	\$0.0




PROJECT:	Riverside Dr. @ Woodfin Ave.	LOCATION:	Woodfin		
TYPE:	General Sewer Rehab.	PIPE RATING:	13		
PROJECT NO.	2019005	TOTAL LF:	684		
PROJECT BUDGET:	\$293,000.00	PROJECT ORIGIN:	Work Orders, Line Condit	ion	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26	
55310 - PRELIM. ENGINEERING					
55320 - SURVEY - DESIGN	\$6,000.00				
55330 - DESIGN					
55340 - PERMITS	\$5,000.00				
55350 - SPECIAL STUDIES					
55360 - EASEMENT PLATS	\$2,000.00				
55370 - LEGAL FEES	\$2,500.00				
55380 - ACQUISITION SERVICES					
55390 - COMPENSATION 55400 - APPRAISAL	\$15,000.00				
55410 - CONDEMNATION					
55420 - CONSTRUCTION	***************************************				
55430 - CONST. CONTRACT ADM.	\$260,000.00				
55440 - TESTING	\$4,000,00				
55450 - SURVEY - ASBUILT	\$1,000.00 \$1,500.00				
TOTAL AMOUNT	\$293,000.00	i <del></del>	\$0.00	\$0.0	
	<b>\$200,000.00</b>	<u>,,                                   </u>	<del>                                      </del>	<b>V</b> 0.0	
ENGINEER:	MSD	MSD SA		ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 2 ]	FY 26-27	\$0.0	
CONTRACTOR:			FY 27-28	\$6,000.0	
CONSTRUCTION ADM:	MSD		FY 28-29	\$24,500.0	
INSPECTION:	MSD		FY 29-30	\$262,500.0	
			FY 30-31	\$0.0	
			FY 31-32	\$0.0	
	ject is located in Woodfin and is comprise structural condition with cracks and misalig			\$0.0	
potential overflows.	and a continuous conti	,, <del>gg = 111</del> 9	FY 33-34	\$0.0	
			FY 34-35	\$0.0	



PROJECT:	Riverview Drive	LOCATION:	Asheville	
	14110111011 21110		7.0.10 7.10	
TYPE:	General Sewer Rehab.	PIPE RATING:	54	
PROJECT NO.	2013104	TOTAL LF:	2,507	
PROJECT BUDGET:	\$1,566,080.00	PROJECT ORIGIN:	SSO's, Access, Line Con	dition
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		<u> </u>	l l	
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$17,380.00	\$17,380.00		
55330 - DESIGN				
55340 - PERMITS 55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,540,000.00			
55430 - CONST. CONTRACT ADM.	. //			
55440 - TESTING	\$4,000.00			
55450 - SURVEY - ASBUILT	\$4,700.00			
TOTAL AMOUNT	\$1,566,080.00	\$17,380.00	\$0.00	\$0.00
ENGINEER:	MSD	BD	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:	N/A	#PLATS: [ 0 ]	FY 26-27	\$1,548,700.00
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
PROJECT DESCRIPTION: This pro	oject is located in Asheville near the Haywood	d Rd. bridge. The project	FY 31-32	\$0.0
consists of replacing approx. 2,302	LF of existing 6-inch vitrified clay pipe with	8-inch ductile iron pipe.		\$0.0
The existing line is in poor condition	and has experienced multiple overflows.		FY 33-34 FY 34-35	\$0.0
<u> </u>			F 1 34-35	\$0.00




		W		
PROJECT:	Rosewood Ave. @ Riverside Cemetery	LOCATION:	Montford	
TYPE:	General Sewer Rehab.	PIPE RATING:	25	
PROJECT NO.	2019023	TOTAL LF:	180	
PROJECT BUDGET:	\$90,850.00	PROJECT ORIGIN:	Line condition, Access	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
FERMA DDELIM ENCINEEDING				
55310 - PRELIM. ENGINEERING 55320 - SURVEY - DESIGN	24.000.00			
55330 - DESIGN	\$1,300.00			\$1,300.00
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$3,450.00			
55370 - LEGAL FEES	\$4,000.00			
55380 - ACQUISITION SERVICES	. , , , , , , , , , , , , , , , , , , ,			
55390 - COMPENSATION	\$20,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$61,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$500.00			
55450 - SURVEY - ASBUILT	\$600.00			
TOTAL AMOUNT	\$90,850.00	\$0.00	\$0.00	\$1,300.00
ENGINEER:	MSD	BD	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 3 ]	FY 26-27	\$2,600.00
CONTRACTOR:			FY 27-28	\$24,850.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$62,100.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
PROJECT DESCRIPTION: This ar	roject is located off of Rosewood Avenue	in Montford adjacent to	FY 31-32	\$0.00
Riverside Cemetery. This project in	cludes the replacement of approximately 18	0 LF of 6-inch VCP pipe	FY 32-33	\$0.00
with new 8-inch DIP. The existing lir	ne is in poor structural condition and is locate	d next to a broken storm	FY 33-34	\$0.00
drain, causing heavy I&I.			FY 34-35	\$0.00
SPECIAL PROJECT NOTES:				




PROJECT:	Royal Pines Drive - PRP 47009	LOCATION:	Arden	
TYPE:	Pipe Rated Projects	PIPE RATING:	18	
PROJECT NO.	2007020	TOTAL LF:	7,050	
PROJECT BUDGET:	\$3,093,100.00	PROJECT ORIGIN:	Pipe Rating Program	
		<u> </u>		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING		<u> </u>		
55320 - SURVEY - DESIGN	\$40,100,00	\$10,100.00		
55330 - DESIGN	\$40,100.00	\$10,100.00		
55340 - PERMITS	\$5,000.00			
55350 - SPECIAL STUDIES	ψ3,000.00			
55360 - EASEMENT PLATS	\$8,000.00			
55370 - LEGAL FEES	\$9,000.00			
55380 - ACQUISITION SERVICES	,			
55390 - COMPENSATION	\$25,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$2,996,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$5,000.00			
55450 - SURVEY - ASBUILT	\$5,000.00			
TOTAL AMOUNT	\$3,093,100.00	\$10,100.00	\$0.00	\$0.00
ENGINEER:	MSD	SA	ESTIMATED BUDG	3FTS - FV 27 - 35
R.O.W. ACQUISITION:	MSD	#PLATS: [ 7 ]	FY 26-27	\$30,000.0
CONTRACTOR:			FY 27-28	\$14,000.0
CONSTRUCTION ADM.:	MSD		FY 28-29	\$33,000.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$3,006,000.0
			FY 31-32	\$0.0
PROJECT DESCRIPTION: This pro	ject is located in S. Asheville and is compris	sed of 7,050 LF of 8-inch	FY 32-33	\$0.0
ductile iron pipe. The existing line is	8-inch vitrified clay pipe which has had a his	tory of root problems.	FY 33-34	\$0.0
			FY 34-35	\$0.0




PROJECT:	Sand Hill Road @ Baker Place	LOCATION:	W. Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	56	
PROJECT NO.	2015223	TOTAL LF:	1,582	
PROJECT BUDGET:	\$943,000.00	PROJECT ORIGIN:	Work Orders, Line Condition	on
DESCRIPTION	ESTIMATED	TOTAL EXPENDS	EST. COST	BUDGET
DESCRIPTION	PROJECT COST	THRU 12/31/24	JAN - JUNE 2025	FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$11,300.00	\$11,300.00		
55330 - DESIGN				
55340 - PERMITS	\$1,000.00		\$1,000.00	
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$10,200.00	\$10,200.00		
55370 - LEGAL FEES	\$13,000.00	\$11,990.00	\$1,010.00	
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$116,000.00	\$51,865.00	\$64,135.00	
55400 - APPRAISAL	\$7,000.00		\$7,000.00	
55410 - CONDEMNATION	\$28,000.00		\$28,000.00	
55420 - CONSTRUCTION	\$750,000.00		\$562,500.00	\$187,500.0
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			\$1,000.0
55450 - SURVEY - ASBUILT	\$5,500.00			\$5,500.0
TOTAL AMOUNT	\$943,000.00	\$85,355.00	\$663,645.00	\$194,000.00
			1187	39
ENGINEER:	MSD	SA	ESTIMATED BUDGET	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 12 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
DDO IFOT DECODIFE TO THE		S4-64-500-1550-1	FY 31-32	\$0.0
PROJECT DESCRIPTION: This proje ductile iron pipe. The existing line is	ct is located in West Asheville and is compri s a 6-inch VCP with mulitple structural defec	sed of 1,582 LF of 8-inch	FY 32-33	\$0.0
to being located under several house		2 .22.22	FY 33-34	\$0.0
			FY 34-35	\$0.0




PROJECT:	Starmount Drive	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	19	
PROJECT NO.	2023007	TOTAL LF:	775	
PROJECT BUDGET:	\$275,100.00	PROJECT ORIGIN:	SSO's, Work Orders, Line	Condition
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$6,000.00			
55330 - DESIGN				
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS 55370 - LEGAL FEES	\$6,600.00			
55370 - LEGAL FEES 55380 - ACQUISITION SERVICES	\$7,000.00			
55390 - ACQUISITION SERVICES  55390 - COMPENSATION				
55400 - APPRAISAL	\$20,000.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$232,500.00			
55430 - CONST. CONTRACT ADM.	φ232,300.00			
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$1,000.00			
TOTAL AMOUNT	\$275,100.00	<u> </u>	\$0.00	\$0.00
ENGINEER:	MSD	SA	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 6 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$6,000.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$18,600.00
INSPECTION:	MSD		FY 29-30	\$16,000.00
			FY 30-31	\$0.00
PROJECT DESCRIPTION: This or	oject is located in West Asheville near N	. Louisiana Ave and is	FY 31-32	\$234,500.00
comprised of 775 LF of 8" ductile in	on pipe. The existing sewer line is 8" VCP ar	nd steel, with heavy roof	FY 32-33	\$0.00
instrusion and significant structural of for leaks, which will go undetected d	defects. There have been no SSO's, but the ue to the heavily wooded location.	line has a high potentia	FY 33-34	\$0.00
	,		FY 34-35	\$0.00




PROJECT:	Starnes Avenue	LOCATION:	Asheville	
ГҮРЕ:	General Sewer Rehab.	PIPE RATING:	7	
PROJECT NO.	2014154	TOTAL LF:	2,871	
PROJECT BUDGET:	\$1,297,700.00	PROJECT ORIGIN:	SSO's, Work Orders, Line	Condition
		<u> </u>		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
5310 - PRELIM. ENGINEERING		<u> </u>	T	
55320 - SURVEY - DESIGN	£47.500.00			
55330 - DESIGN	\$17,500.00			
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$4,250.00			
55370 - LEGAL FEES	\$4,850.00			
55380 - ACQUISITION SERVICES	\$4,000.00			
55390 - COMPENSATION	\$79,000.00			
55400 - APPRAISAL	Ţ.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,185,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$3,000.00			
55450 - SURVEY - ASBUILT	\$4,100.00			
TOTAL AMOUNT	\$1,297,700.00	\$0.00	\$0.00	\$0.
			<u> </u>	
ENGINEER:	MSD	BD	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	#PLATS: [ 4 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.
NSPECTION:	MSD		FY 29-30	\$0.
			FY 30-31	\$17,500.
	project is located near downtown Ashevi			\$3,400.
	i-inch VCP will be replaced with 8-inch DIP al			\$0.
Juliubelianu Ave., Starnes Ave., Ha	berland Ave., Starnes Ave., Harrison St., and Flint St. Portions of the existing pipe were installed 1900, and have numerous structural defects.			\$84,700.




PROJECT:	Stratford Road	LOCATION:	N. Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	13	
PROJECT NO.	2015013	TOTAL LF:	1,820	
PROJECT BUDGET:	\$834,500.00	PROJECT ORIGIN:	SSO's, Work Orders, Lin	e Condition
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING			T T	
55320 - SURVEY - DESIGN	\$40,000,00			
55330 - DESIGN	\$13,000.00			
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES	\$1,000.00			
55360 - EASEMENT PLATS	\$19,000.00			
55370 - LEGAL FEES	\$22,000.00			
55380 - ACQUISITION SERVICES	<del></del>			
55390 - COMPENSATION	\$122,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$650,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,500.00			
55450 - SURVEY - ASBUILT	\$6,000.00			
TOTAL AMOUNT	\$834,500.00	\$0.00	\$0.00	\$0.00
ENGINEER:	MSD	DP	ESTIMATED BUDG	ETC EV 27 25
R.O.W. ACQUISITION:	MSD	#PLATS: [ 20 ]	FY 26-27	
CONTRACTOR:	IVIOD	#1 LATO. [ 20 ]	FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$14,000.00
INSPECTION:	MSD		FY 29-30	\$60,150.00 \$102,850.00
			FY 30-31	\$0.00
			FY 31-32	\$657,500.00
	roject is located in N. Asheville along Stratfo			\$0.00
	ford Court. The lines run though properties poor structural condition which has allowed		FY 33-34	\$0.0
,,,,	•	•	FY 34-35	\$0.00




PROJECT:	Sulphur Springs Rd. @ Covington	LOCATION:	W. Asheville	
ГҮРЕ:	General Sewer Rehab.	PIPE RATING:	44	
PROJECT NO.	2014006	TOTAL LF:	1,350	
FROJECT NO.	2014000	TOTAL LF.	1,330	
PROJECT BUDGET:	\$774,200.00	PROJECT ORIGIN:	SSO's, Access, Line Cond	ition
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
5310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$7,500.00	\$7,500.00		
55330 - DESIGN	. ,	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		
55340 - PERMITS				
55350 - SPECIAL STUDIES				
5360 - EASEMENT PLATS	\$18,700.00			\$17,850.0
5370 - LEGAL FEES	\$22,000.00			
5380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$120,000.00			
5400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$600,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$5,000.00			
TOTAL AMOUNT	\$774,200.00	\$7,500.00	\$0.00	\$17,850.0
ENGINEER:	MSD	DP	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 20 ]	FY 26-27	\$50,850.0
CONTRACTOR:			FY 27-28	\$92,000.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$606,000.0
NSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
DO JECT DESCRIPTION. This are	ject begins in the area of the Sulphur Sp	oringe Pd /Dolowero Avo	FY 31-32	\$0.0
ntersection and runs through the ba	ck properties along Belmont Ave. The existir	ng 6-inch clay pipe will be	FY 32-33	\$0.0
eplaced with 8-inch ductile iron pipe	e. The 6-inch clay line has had numerous pr	oblems and runs under a	FY 33-34	\$0.0
nouse.			FY 34-35	\$0.0




PROJECT:	Sweeten Creek Rd. @ Buck Shoals Rd.	LOCATION:	S. Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	51	
PROJECT NO.	2014015	TOTAL LF:	790	
PROJECT BUDGET:	\$520,705.00	PROJECT ORIGIN:	SSO's, Access, Line Con	dition
I ROBERT BODGET.	<b>4020,700.00</b>	r Robert ordone.	OGO 3, ACCUSS, EINC CON	uition .
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING		<u> </u>		
55320 - SURVEY - DESIGN	40.070.0	40.070.00		
55330 - DESIGN	\$9,870.0	\$9,870.00		
55340 - PERMITS	\$12,000.0	\$9,050.00	\$2,950.00	
55350 - SPECIAL STUDIES	φ12,000.0	\$9,030.00	\$2,950.00	
55360 - EASEMENT PLATS	\$3,200.0	\$3,200.00		
55370 - LEGAL FEES	\$12,504.0			
55380 - ACQUISITION SERVICES	<b>V.2,66</b>	ψ12,00 H30		
55390 - COMPENSATION	\$13,555.0	\$13,555.00		
55400 - APPRAISAL				
55410 - CONDEMNATION	\$1,306.0	\$1,306.00		
55420 - CONSTRUCTION	\$462,000.0	\$96.00		\$461,904.0
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,000.0	00		\$2,000.0
55450 - SURVEY - ASBUILT	\$4,270.0	\$970.00		\$3,300.0
TOTAL AMOUNT	\$520,705.0	\$50,551.00	\$2,950.00	\$467,204.0
	1400			
ENGINEER:	MSD	BD # DI ATO: I. 4. 1	ESTIMATED BUDGI	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 4 ]	FY 26-27	\$0.0
CONTRACTOR: CONSTRUCTION ADM:	MSD		FY 27-28 FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
	52		FY 30-31	\$0.0 \$0.0
			FY 31-32	
PROJECT DESCRIPTION: This	project is located in Royal Pines on Buc	k Shoals Rd. between	FY 32-33	\$0.0
Hendersonville Rd. and Sweeten	Creek Rd. Approx. 790 LF of existing 6-inche. The existing line is in poor condition and is u	vitrified clay pipe will be	FY 33-34	\$0.0 \$0.0
	o. The existing line is in poor condition and is t		<u> </u>	φυ.υ




PROJECT:	Sweeten Creek Rd. @ Holiday Dr.	LOCATION:	Asheville		
	<u> </u>				
TYPE:	General Sewer Rehab.	PIPE RATING:	43		
PROJECT NO.	2022022	TOTAL LF:	3,053		
PROJECT BUDGET:	\$1,229,000.00	PROJECT ORIGIN:	SSO's, Work Orders, Line	Condition	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26	
55310 - PRELIM. ENGINEERING					
55320 - SURVEY - DESIGN	\$24,000.00			\$24,000.00	
55330 - DESIGN					
55340 - PERMITS	\$2,000.00				
55350 - SPECIAL STUDIES					
55360 - EASEMENT PLATS	\$20,000.00				
55370 - LEGAL FEES	\$22,000.00				
55380 - ACQUISITION SERVICES					
55390 - COMPENSATION	\$50,000.00				
55400 - APPRAISAL					
55410 - CONDEMNATION					
55420 - CONSTRUCTION 55430 - CONST. CONTRACT ADM.	\$1,100,000.00				
55440 - TESTING					
55450 - SURVEY - ASBUILT	\$1,000.00				
TOTAL AMOUNT	\$10,000.00	i <del></del>	\$ 000	****	
TOTAL AUTOURT	\$1,229,000.00	\$0.00	0  \$0.00	\$24,000.00	
ENGINEER:	MSD	DP	ESTIMATED BUDGETS - FY 27 - 35		
R.O.W. ACQUISITION:	MSD	#PLATS: [ 20 ]	FY 26-27	\$18,300.00	
CONTRACTOR:			FY 27-28	\$37,000.00	
CONSTRUCTION ADM:	MSD		FY 28-29	\$38,700.00	
INSPECTION:	MSD		FY 29-30	\$1,111,000.00	
			FY 30-31	\$0.00	
DRO IECT DESCRIPTION. This proje	ect is in south Asheville off of Sweeten Cre	ask Road. The project of	FY 31-32	\$0.00	
Sweeten Creek Road between Holida	ay Drive and Carrington Place and runs nort	th to Cedar Lane through	FY 32-33	\$0.00	
	nch and 8-inch clay pipes have numerous jo			\$0.0	
mat has led to root problems, illillita	aon, and Overnows.		FY 34-35	\$0.00	




PROJECT:	Sweeten Creek Rd. @ Mills Gap Rd.	LOCATION:	Asheville	
ricoscor.	Sweeten Creek Nu. @ Mills Gap Nu.	LOCATION.	ASHEVINE	
TYPE:	General Sewer Rehab.	PIPE RATING:	4	
PROJECT NO.	2014189	TOTAL LF:	2,572	
PROJECT BUDGET:	\$1,512,300.00	PROJECT ORIGIN:	SSO's, Work Orders, Lin	e Condition
		<u> </u>		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING		1		
55320 - PRELIM. ENGINEERING 55320 - SURVEY - DESIGN	#44.000.00	Ø44.000.00		
55330 - DESIGN	\$11,300.00	\$11,300.00		
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES	φ1,000.00			
55360 - EASEMENT PLATS	\$6,000.00			
55370 - LEGAL FEES	\$6,500.00			
55380 - ACQUISITION SERVICES	,			
55390 - COMPENSATION	\$153,000.00			
55400 - APPRAISAL	\$7,500.00			
55410 - CONDEMNATION	\$20,000.00			
55420 - CONSTRUCTION	\$1,300,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$5,000.00			
TOTAL AMOUNT	\$1,512,300.00	\$11,300.00	\$0.00	\$0.0
ENGINEER:	MSD	SA	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 5 ]	FY 26-27	\$0.0
CONTRACTOR:		<u> </u>	FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$65,000.0
			FY 31-32	\$101,500.0
PROJECT DESCRIPTION: This project	t is located in South Asheville near Mills Gap . The existing line is 6-inch and 8-inch vi	Rd. and is comprised of	FY 32-33	\$27,500.0
condition, with a history of SSO's.	. The existing line is o-men and o-men vi	amou day pipe ili pool	FY 33-34	\$0.0
			FY 34-35	\$1,307,000.0




PROJECT:	Tunnel Rd. @ Pleasant Ridge Dr.	LOCATION:	E. Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	22	
PROJECT NO.	2019006	TOTAL LF:	350	
PROJECT BUDGET:	\$127,750.00	PROJECT ORIGIN:	Access, Line Condition	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING		<u> </u>		
55320 - SURVEY - DESIGN	\$2,500.00			
55330 - DESIGN	\$2,500.00			
55340 - PERMITS	\$1,000.00			
55350 - SPECIAL STUDIES	ψ1,000.00			
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$122,500.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$750.00			
TOTAL AMOUNT	\$127,750.00	\$0.00	\$0.00	\$0.00
	MOD		T	
ENGINEER: R.O.W. ACQUISITION:	MSD MSD	#BLATS: C.O. 1	FY 26-27	
CONTRACTOR:	MOD	# PLATS: [ 0 ]	FY 27-28	\$2,500.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$1,000.00
INSPECTION:	MSD		FY 29-30	\$0.00
	mes -		FY 30-31	\$124,250.00 \$0.00
			FY 31-32	
	ect is located in East Asheville and is comprise		FY 32-33	\$0.0
inch DIP. The existing sewer lin	e is 4-inch Orangeburg and 8" vitrified cla			\$0.0
maintained.			FY 34-35	\$0.0 \$0.0




PROJECT:	US 70 @ Jordan Road	LOCATION:	Swannanoa		
ГҮРЕ:	General Sewer Rehab.	PIPE RATING:	23		
PROJECT NO.	2015014	TOTAL LF:	4,550		
PROJECT BUDGET:	\$2,048,500.00	PROJECT ORIGIN:	Access, Line Condition, V	/ork Orders	
		1			
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26	
		1			
5310 - PRELIM. ENGINEERING					
55320 - SURVEY - DESIGN	\$35,000.00				
55330 - DESIGN					
55340 - PERMITS	\$6,000.00				
55350 - SPECIAL STUDIES					
55360 - EASEMENT PLATS	\$30,000.00				
55370 - LEGAL FEES	\$33,000.00				
55380 - ACQUISITION SERVICES					
55390 - COMPENSATION 55400 - APPRAISAL	\$127,000.00				
55410 - CONDEMNATION					
55420 - CONSTRUCTION	#4 000 000 00				
55430 - CONST. CONTRACT ADM.	\$1,800,000.00				
55440 - TESTING	\$2,500,00				
55450 - SURVEY - ASBUILT	\$2,500.00 \$15,000.00				
TOTAL AMOUNT	\$2,048,500.00	1	\$0.00	\$0.0	
	\$2,010,000.00	<u>,,,                                  </u>	\$1.00	<b>\$61.0</b>	
ENGINEER:	MSD	MSD DP		ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 30 ]	FY 26-27	\$35,000.0	
CONTRACTOR:			FY 27-28	\$0.0	
CONSTRUCTION ADM:	MSD		FY 28-29	\$34,300.0	
NSPECTION:	MSD		FY 29-30	\$131,700.0	
			FY 30-31	\$30,000.0	
		) The	FY 31-32	\$1,817,500.0	
PROJECT DESCRIPTION: This proj McBrayer Ave., crosses under US 7	ect is located in Swannanoa along US 70 o at Martin Rd., and ends at Burgins Chape	o. The project begins a el Rd. The existing 8-inch	FY 32-33	\$0.0	
	cBrayer Ave., crosses under US 70 at Martin Rd., and ends at Burgins Chapel Rd. The existing 8-ind trified clay pipe is in poor condition. This is a potential lining project.			\$0.0	
			FY 34-35	\$0.0	




PROJECT:	Walnut St. @ N. Lexington Ave.	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	38	
PROJECT NO.	2017008	TOTAL LF:	1,300	
PROJECT BUDGET:	\$666,526.00	PROJECT ORIGIN:	Line Condition, Undersiz	ed Pipe
		<u> </u>		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1	I I	
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN 55330 - DESIGN	\$10,000.00			
55330 - DESIGN 55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES	\$40.00	\$40.00		
55380 - ACQUISITION SERVICES	φ40.00	\$40.00		
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$650,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,486.00	\$486.00		
55450 - SURVEY - ASBUILT	\$4,000.00			
TOTAL AMOUNT	\$666,526.00	\$526.00	\$0.00	\$0.0
ENGINEER:	MSD	DP	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION: CONTRACTOR:	MSD	# PLATS: [ 0 ]	FY 26-27 FY 27-28	\$10,000.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$656,000.0
			FY 30-31	\$0.0 \$0.0
			FY 31-32	\$0.0
PROJECT DESCRIPTION: This project begins in the area of the Sulphur Springs Rd./Delaware Aventersection and runs through the back properties along Belmont Ave. The existing 6-inch clay pipe will be				\$0.0
replaced with 8-inch ductile iron pipe	e. The 6-inch clay line has had numerous pr	oblems and runs under a		\$0.
house.			FY 34-35	\$0.0




PROJECT:	Waynesville Ave. @ Brownwood Ave.	LOCATION:	W. Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	28	
PROJECT NO.	2014183	TOTAL LF:	3,022	
PROJECT BUDGET:	\$1,465,650.00	PROJECT ORIGIN:	Access, Line Condition, S	SSO's
. Koolo i Bobol ii	¥ 1, 100,000.00	I RODE T CHICIN	7.00000, Ellio Collattion, C	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING		1	T T	
55320 - SURVEY - DESIGN	¢40,000,00			
55330 - DESIGN	\$19,000.00			\$19,000.00
55340 - PERMITS	\$500.00			
55350 - SPECIAL STUDIES	φοσο.σο			
55360 - EASEMENT PLATS	\$41,650.00			
55370 - LEGAL FEES	\$52,000.00			
55380 - ACQUISITION SERVICES	\$188,000.00			
55390 - COMPENSATION	\$250,000.00			
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$910,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$2,500.00			
TOTAL AMOUNT	\$1,465,650.00	\$0.00	\$0.00	\$19,000.00
ENGINEER:	MSD	SA	ESTIMATED BUDGI	FTS - FY 27 - 35
R.O.W. ACQUISITION:	Consultant	# PLATS: [ 47 ]	FY 26-27	\$500.00
CONTRACTOR:	-		FY 27-28	\$214,000.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$223,650.00
INSPECTION:	MSD		FY 29-30	\$1,008,500.00
			FY 30-31	\$0.00
DDG IFOT DEGODIDATION. This wasis			FY 31-32	\$0.00
and is comprised of 3.022 LF of 8-inc	ct is located in West Asheville between Hayoch ductile iron pipe. The existing line is 8-inc	h vitrified clav pipe that is	FY 32-33	\$0.00
in poor condition with heavy root intr	rusion, structural defects, and I&I problems,	resulting in a long history	FY 33-34	\$0.0
of SSO's.			FY 34-35	\$0.00




PROJECT:	Weaverville Rd. @ Reynolds Mtn.	LOCATION:	Weaverville	
TYPE:	General Sewer Rehab.	PIPE RATING:	13	
PROJECT NO.	2018036	TOTAL LF:	415	
PROJECT BUDGET:	\$159,000.00	PROJECT ORIGIN:	System Services, Unders	ized 6" line
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$6,000.00			
55330 - DESIGN				
55340 - PERMITS	\$500.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$150,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$1,500.00			
TOTAL AMOUNT	\$159,000.00	\$0.00	\$0.00	\$0.00
			11	
ENGINEER:	MSD	тн	ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$6,500.00
			FY 30-31	\$0.00
PROJECT DESCRIPTION: This Ger	PROJECT DESCRIPTION: This General Sewer Rehabilitation project is located in North Asheville along			\$0.00
Peaverville Rd. near the intersection of Reynolds Mountain Blvd. Currently this public system planned for enabilitation consists of approximately 415 LF of existing 6-inch VCP/PVC that is in poor condition with			FY 32-33	\$152,500.00
rehabilitation consists of approximat limited access. It will be replaced wi	ely 415 LF ot existing 6-inch VCP/PVC that th 8-inch DIP.	is in poor condition with	FY 33-34	\$0.00
2 decest. It will be replaced wi			FY 34-35	\$0.00



PROJECT:	W. City View Dr. @ Riverside Dr.	LOCATION:	Asheville	
TYPE:	General Sewer Rehab.	PIPE RATING:	13	
PROJECT NO.	2024020	TOTAL LF:	735	
PROJECT BUDGET:	\$364,630.00	PROJECT ORIGIN:	Line Condition, Undersized	d Pipe
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$7,500.00	\$7,500.00		
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$5,000.00	\$4,950.00	\$50.00	
55370 - LEGAL FEES	\$7,000.00	\$4,281.00	\$719.00	\$2,000.00
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$20,130.00		\$16,000.00	\$4,130.00
55400 - APPRAISAL	\$4,000.00			\$4,000.00
55410 - CONDEMNATION	\$16,000.00			\$16,000.00
55420 - CONSTRUCTION	\$300,000.00			\$300,000.00
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$1,000.00			\$1,000.00
55450 - SURVEY - ASBUILT	\$4,000.00			\$4,000.00
TOTAL AMOUNT	\$364,630.00	\$16,731.00	\$16,769.00	\$331,130.00
ENGINEER:		MSD DP		TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	MSD #PLATS: [ 7 ]		\$0.00
CONTRACTOR:	Men		FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD MSD		FY 28-29	\$0.00
INSPECTION:	MOD		FY 29-30	\$0.00
			FY 30-31	\$0.00
<b>PROJECT DESCRIPTION:</b> This project begins on the west side of Riverside Drive, runs east crossing Riverside Drive and continues on W. City View Drive. The existing 6-inch clay pipe will be replaced with 8-inch ductile iron pipe and 8-inch HDPE. The 6-inch clay line is undersized and has had numerous				
			FY 32-33	\$0.00
problems that has lead to a SSO.	5. E. The emon day line is undersized and has had half		EV 24 25	
<u> </u>			FY 34-35	\$0.00



PROJECT:	Weston Road @ Tampa Blvd.	LOCATION:	Skyland		
TYPE:	General Sewer Rehab	PIPE RATING:	9		
PROJECT NO.	2015208	TOTAL LF:	400		
PROJECT BUDGET:	\$156,000.00	PROJECT ORIGIN:	I&I, Protruding Taps, Und	ersized	
DESCRIPTION	ESTIMATED	TOTAL EXPENDS	EST. COST	BUDGET	
	PROJECT COST	THRU 12/31/24	JAN - JUNE 2025	FY 25-26	
		·			
55310 - PRELIM. ENGINEERING					
55320 - SURVEY - DESIGN	\$3,000.00				
55330 - DESIGN					
55340 - PERMITS					
55350 - SPECIAL STUDIES					
55360 - EASEMENT PLATS	\$3,400.00				
55370 - LEGAL FEES	\$3,500.00				
55380 - ACQUISITION SERVICES					
55390 - COMPENSATION	\$14,000.00				
55400 - APPRAISAL					
55410 - CONDEMNATION					
55420 - CONSTRUCTION	\$130,000.00				
55430 - CONST. CONTRACT ADM.					
55440 - TESTING	\$1,000.00				
55450 - SURVEY - ASBUILT	\$1,100.00				
TOTAL AMOUNT	\$156,000.00	\$0.00	\$0.00	\$0.0	
ENGINEER:	MSD	MSD BD		ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 3 ]	FY 26-27	\$0.0	
CONTRACTOR:			FY 27-28	\$0.0	
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0	
INSPECTION:	MSD		FY 29-30	\$3,000.0	
			FY 30-31	\$2,550.0	
			FY 31-32	\$0.0	
PROJECT DESCRIPTION: This project is located in Skyland, approx. 1/2 mile northeast of the US 25/US 25A intersection. It consists of replacing 400LF of existing 6-inch VCP with 8-inch DIP. The existing pipe			FY 32-33 \$18,35		
•	ntersection. It consists of replacing 400LF of existing 6-inch VCP with 8-inch DIP. The existing piperends and protruding taps in the line, is undersized, and is a source of I&I.		FY 33-34 \$132,1		
			FY 34-35	\$0.0	



#### **BUDGET DATA SHEET - FY 2025 - 2026**

PROJECT:	Wildwood Park	LOCATION:	Weaverville	
ГҮРЕ:	General Sewer Rehab.	PIPE RATING:	16	
PROJECT NO.	2015194	TOTAL LF:	2,300	
PROJECT BUDGET:	\$821,380.00	PROJECT ORIGIN:	Pipe Fractures, Roots, L	ocation
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
FEATA DEELIM ENGINEEDING			1	
55310 - PRELIM. ENGINEERING 55320 - SURVEY - DESIGN				
55320 - SURVET - DESIGN 55330 - DESIGN	\$12,380.00	\$2,380.00		
55330 - DESIGN 55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$800,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$7,000.00			
TOTAL AMOUNT	\$821,380.00	\$2,380.00	\$0.00	\$0.00
FNONEED	1100		FOTMATED DUDG	
ENGINEER: R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]	ESTIMATED BUDG	
CONTRACTOR:		#FLAI3. [ 0 ]	FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00 \$10,000.00
			FY 31-32	\$10,000.00
	ct is located in Weaverville at the corner of li from Wildwood Park to Coleman St and alon			\$809,000.00
pipe has multiple fractures, root pro	blems, and runs underneath multiple structu	res making maintenance		\$0.00
difficult.	difficult.		FY 34-35	\$0.00

#### BUDGET DATA SHEET - FY 2025 - 2026

PROJECT:		SSD Rehab. & Replacement	LOCATION:	Various	
FROJECT.		(Annual)	LOCATION.	various	
TVDE.		General Sewer Rehab.	DIDE DATING.	NI/A	
TYPE:		General Sewer Renab.	PIPE RATING:	N/A	
PROJECT NO.		2002101	TOTAL LF:	150,000	
				·	
PROJECT BUDGET:		\$51,425,000.00	PROJECT ORIGIN:	In-house Capital Improv	ements
DESCRIP	TION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGI	NEERING				
55320 - SURVEY - DES	IGN				
55330 - DESIGN					
55340 - PERMITS					
55350 - SPECIAL STUD	IES				
55360 - EASEMENT PL	ATS				
55370 - LEGAL FEES					
55380 - ACQUISITION S	SERVICES				
55390 - COMPENSATIO	DN				
55400 - APPRAISAL					
55410 - CONDEMNATIO	ON				
55420 - CONSTRUCTIO	N	\$51,425,000.0	0 \$1,296,355.83	\$3,846,144.17	\$5,142,500.00
55430 - CONST. CONTI	RACT ADM.	, , , ,	, , , , , , , , , , , , , , , , , , , ,	, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	, , , , , , , , , , , , , , , , , , , ,
55440 - TESTING					
55450 - SURVEY - ASB	UILT				
TOTAL AMOUNT		\$51,425,000.0	0 \$1,296,355.83	\$3,846,144.17	\$5,142,500.00
			•		15000
ENGINEER:		MSD	MS	ESTIMATED BUDG	GETS - FY 27 - 35
R.O.W. ACQUISITION:		MSD	#PLATS: [ ]	FY 26-27	\$5,142,500.00
CONTRACTOR:				FY 27-28	\$5,142,500.00
CONSTRUCTION ADM:		MSD		FY 28-29	\$5,142,500.00
INSPECTION:		MSD		FY 29-30	\$5,142,500.00
				FY 30-31	\$5,142,500.00
	- TI : "			FY 31-32	\$5,142,500.00
PROJECT DESCRIPTI construction crews a		item is for the replacement of capitalism includes new taps, small repairs,		FY 32-33	\$5,142,500.00
rehabilitation projects.	Also included is	paving when required for these repairs	and rehabilitation projects.	FY 33-34	\$5,142,500.00
The total estimated pr	oject cost shown i	s the total within the ten year window.		FY 34-35	\$5,142,500.00
SPECIAL PROJECT NO	TES:	Capitalized Labor & Misc.	\$1,628,416	Materials / Year	\$1,417,429.00

#### **BUDGET DATA SHEETS - FY 2025-2026**

PROJECT: SUMMARY - In-House Projects

ACCOUNT: GENERAL

DATE OF REPORT: January 2025

PROJECT BUDGET: Funded through 2002101

DESCRIPTION	PROJECT NO.	PROJECT LOCATION	WORK ORDER NO.	CONST. YEAR	TOTAL LINEAR FOOTAGE
73 Argyle Lane	2024000	Asheville 28806	219342	FY 25-26	755
Baker Place @ Carrier Street	2021267	Asheville 28806	284574	FY 25-26	1,300
	2021207	Blk Mtn 28711			785
Carver Avenue @ Owenby Lane		-	292540	FY 25-26	
48 Clarendon Road	2019009	Asheville 28806	258562	FY 25-26	446
Country Club Road Sewer Rehab.	2025022	Asheville 28805	307035	FY 25-26	113
526 Depot St. @ Livingston Street Ph. 2	2024002	Asheville 28801	280038	FY 25-26	500
Elkdale Drive @ Elkwood Avenue	2025017	Woodfin 28804	304581	FY 25-26	1,000
8 Ellenwood Drive	2025020	Asheville 28804	308431	FY 25-26	300
112 Enthoffer Street	2024212	Blk Mtn 28711	305189	FY 25-26	425
44 Galax Avenue	2022018	Asheville 28806	280827	FY 25-26	294
Knauth Street Phase 2	2015220	Asheville 28805	275867	FY 25-26	346
37 Lucerne Avenue	2025018	Asheville 28806	310196	FY 25-26	320
14 Mineral Springs Road	2025021	Asheville 28805	280241	FY 25-26	540
Old Asheland Avenue to Phifer Street	2015034	Asheville 28801	258560	FY 25-26	462
286 Old Haw Creek Road	2020224	Asheville 28805	275815	FY 25-26	100
Rhodes Street @ Union Street	2021268	Woodfin 28804	284578	FY 25-26	230
11 Shenandoah Road	2020215	Asheville 28805	275804	FY 25-26	1,600
Syrlin Street @ Edgewood Road	2025016	Asheville 28804	228045	FY 25-26	725
Upper Glendale Avenue	2024166	Asheville 28803	310029	FY 25-26	695
44 Vermont Court	2025023	Asheville 28806	306951	FY 25-26	200
Virginia Avenue @ Lufty Avenue	2021271	Asheville 28806	48988	FY 25-26	1,400
28 Vista Street	2024211	Asheville 28803	305205	FY 25-26	900
Wellington Street Phase 1	2021274	Asheville 28806	280245	FY 25-26	459
Wellington Street Phase 2	2021274	Asheville 28806	300947	FY 25-26	781
12 West Cotton Avenue	2025019	Blk Mtn 28711	309214	FY 25-26	320

TOTAL FOOTAGE 14,996

#### NOTES:

In addition to the projects identified above, an additional 1,000 linear feet of sewer rehabilitation footage is anticipated through completion of previously identified projects, emergency repairs, and other activities during FY 2025-2026.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	73 Argyle Lane	LOCATION:	Asheville 28806
TYPE:	In House General Sewer Rehab	WORK ORDER:	219342
PROJECT NO.	2024000	TOTAL LF:	755
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements




ENGINEER:	MSD - TH	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 755 LF of sewerline with 8-inch DIP, by dig and replace.

SPECIAL PROJECT NOTES:	Existing line is in very poor condition.

#### **BUDGET DATA SHEET - FY 2025-2026**

		_	
PROJECT:	Baker Place @ Carrier Street	LOCATION:	Asheville 28806
TYPE:	In House General Sewer Rehab	WORK ORDER:	284574
PROJECT NO.	2021267	TOTAL LF:	1,300
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements



ENGINEER:	MSD - MS	
R.O.W. ACQUISITION:	MSD	#PLATS: [0]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 1,300 LF of sewerline with 8-inch DIP, by dig and replace.

SPECIAL PROJECT NOTES: Existing line in poor condition and undersized.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	Carver Ave @ Owenby Lane	LOCATION:	Black Mountain 28711
TYPE:	In House General Sewer Rehab	WORK ORDER:	292540
PROJECT NO.	2022253	TOTAL LF:	785
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements




ENGINEER:	MSD - DP	
R.O.W. ACQUISITION:	MSD	# PLATS: [5]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 785 LF of sewer mainline with 8-inch DIP, by dig and replace.

SPECIAL PROJECT NOTES:	Existing line is in poor condition and undersized.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	48 Clarendon Rd	LOCATION:	Asheville 28806
TYPE:	In House General Sewer Rehab	WORK ORDER:	258562
PROJECT NO.	2019009	TOTAL LF:	446
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements



ENGINEER:	MSD - MS	
R.O.W. ACQUISITION:	MSD	# PLATS:[ 0 ]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 446 LF of existing sewer main with 8-inch DIP, by way of dig and replace construction.

SPECIAL PROJECT NOTES: Existing pipeline in very poor condition.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	Country Club Rd Sewer Rehab	LOCATION:	Asheville 28805
TYPE:	In House General Sewer Rehab	WORK ORDER:	307035
PROJECT NO.	2025022	TOTAL LF:	113
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements




ENGINEER:	MSD - MS	
R.O.W. ACQUISITION:	MSD	# PLATS: [1]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 113 LF of existing sewer main with 8-inch DIP, by dig and replace construction.

SPECIAL PROJECT NOTES: Existing line is plagued with structural defects.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	526 Depot St. @ Livingston St. Ph. 2	LOCATION:	Asheville 28801
TYPE:	In House General Sewer Rehab	WORK ORDER:	280038
PROJECT NO.	2024002	TOTAL LF:	500
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements



ENGINEER:	MSD - DP	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 500 LF of sewerline with 8-inch DIP, by dig and replace.

SPECIAL PROJECT NOTES:	Existing line is in poor condition and undersized.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	Elkdale Dr @ Elkwood Ave	LOCATION:	Woodfin 28804
TYPE:	In House General Sewer Rehab	WORK ORDER:	304581
PROJECT NO.	2025017	TOTAL LF:	1,000
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements



ENGINEER:	MSD - MS	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 1,000 LF of sewer mainline with 8-inch DIP, in roadway by dig and replace construction.

SPECIAL PROJECT NOTES: Existing line is in poor condition and undersized.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	8 Ellenwood Dr	LOCATION:	Asheville 28804
TYPE:	In House General Sewer Rehab	WORK ORDER:	308431
PROJECT NO.	2025020	TOTAL LF:	300
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements



ENGINEER:	MSD - MS	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 300 LF of sewermain with 8-inch DIP, by way of dig and replace construction.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	112 Enthoffer St	LOCATION:	Black Mountain 28711
TYPE:	In House General Sewer Rehab	WORK ORDER:	305189
PROJECT NO.	2024212	TOTAL LF:	425
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements




ENGINEER:	MSD - SA	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 425 LF of sewer mainline with 8-inch DIP, by dig and replace construction.

SPECIAL PROJECT NOTES:	Existing line is in poor condition and undersized.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	44 Galax Ave	LOCATION:	Asheville 28806
TYPE:	In House General Sewer Rehab	WORK ORDER:	280827
PROJECT NO.	2022018	TOTAL LF:	294
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements



ENGINEER:	MSD - MS	
R.O.W. ACQUISITION:	MSD	# PLATS: [0]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 294 LF of sewer mainline with 8-inch DIP, by dig and replace.

SPECIAL PROJECT NOTES: Existing line is in poor condition.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	Knauth St Ph 2	LOCATION:	Asheville 28805
TYPE:	In House General Sewer Rehab	WORK ORDER:	275867
PROJECT NO.	2015220	TOTAL LF:	346
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements




ENGINEER:	MSD - SA	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 6 ]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 346 LF of sewer mainline with 8-inch DIP, in roadway by dig and replace construction.

SPECIAL PROJECT NOTES: Existing line is in poor condition and undersized.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	37 Lucerne Ave	LOCATION:	Asheville 28806
TYPE:	In House General Sewer Rehab	WORK ORDER:	310196
PROJECT NO.	2025018	TOTAL LF:	320
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements




ENGINEER:	MSD - MS		Ī
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]	
CONTRACTOR:	MSD		
CONSTRUCTION ADM:	MSD In-House		
INSPECTION:	MSD In-House		

PROJECT DESCRIPTION: Project consists of replacing approximately 320 LF of existing mainline with 8-inch DIP, in roadway by dig and replace construction.

SPECIAL PROJECT NOTES: Existing sewer is undersized with multiple point repairs.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	14 Mineral Springs Rd	LOCATION:	Asheville 28805
TYPE:	In House General Sewer Rehab	WORK ORDER:	280241
PROJECT NO.	2025021	TOTAL LF:	540
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements




ENGINEER:	MSD - MS	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 4 ]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 540 LF of existing sewer main with 8-inch DIP, by way of dig and replace construction.

SPECIAL PROJECT NOTES: Existing line is plagued with structural defects.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	Old Asheland Ave. to Phifer St.	LOCATION:	Asheville 28801
TYPE:	In House General Sewer Rehab	WORK ORDER:	258560
PROJECT NO.	2015034	TOTAL LF:	462
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements



ENGINEER:	MSD - DP	
R.O.W. ACQUISITION:	MSD	#PLATS: [0]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 462 LF of sewerline with 8-inch DIP, by dig and replace.

SPECIAL PROJECT NOTES:	Project to be coordinated with City of Asheville Storm Drain project.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	286 Old Haw Creek Road	LOCATION:	Asheville 28805
TYPE:	In House General Sewer Rehab	WORK ORDER:	275815
PROJECT NO.	2020224	TOTAL LF:	100
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements




ENGINEER:	MSD - TH	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 100 LF of sewerline with 8-inch DIP, by dig and replace.

SPECIAL PROJECT NOTES:	Existing line is in poor condition.	

#### **BUDGET DATA SHEET - FY 2025-2026**

		_	
PROJECT:	Rhodes Street @ Union Street	LOCATION:	Woodfin 28804
TYPE:	In House General Sewer Rehab	WORK ORDER:	284578
PROJECT NO.	2021268	TOTAL LF:	230
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements



ENGINEER:	MSD - MS	
R.O.W. ACQUISITION:	MSD	#PLATS: [ 1]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 230 LF of sewerline with 8-inch DIP, by dig and replace.

SPECIAL PROJECT NOTES:	Existing line is in poor condition and undersized.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	11 Shenandoah Road	LOCATION:	Asheville 28805
TYPE:	In House General Sewer Rehab	WORK ORDER:	275804
PROJECT NO.	2020215	TOTAL LF:	1,600
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements




ENGINEER:	MSD - BD	
R.O.W. ACQUISITION:	MSD	#PLATS: [ 6]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 1,600 LF of sewerline with 8-inch DIP, by dig and replace.

SPECIAL PROJECT NOTES: Exisiting line is in poor condition and undersized.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	Syrlin Street @ Edgewood Rd	LOCATION:	Asheville 28804
TYPE:	In House General Sewer Rehab	WORK ORDER:	228045
PROJECT NO.	2025016	TOTAL LF:	725
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements



ENGINEER:	MSD - MS	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 725 LF of sewer mainline with 8-inch DIP, by dig and replace construction.

SPECIAL PROJECT NOTES:	Existing line is in poor condition and undersized.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	Upper Glendale Ave	LOCATION:	Asheville 28803
TYPE:	In House General Sewer Rehab	WORK ORDER:	310029
PROJECT NO.	2024166	TOTAL LF:	695
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements



ENGINEER:	MSD - BD	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing/relocating approximately 695 LF of sewer mainline with 8-inch DIP, by dig and replace.

SPECIAL PROJECT NOTES: Existing line is in poor condition.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	44 Vermont Court	LOCATION:	Asheville 28806
TYPE:	In House General Sewer Rehab	WORK ORDER:	306951
PROJECT NO.	2025023	TOTAL LF:	200
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements




ENGINEER:	MSD - MS	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 200 LF of existing sewer main with 8-inch DIP, by dig and replace construction.

SPECIAL PROJECT NOTES: Maintenance of existing line difficult due to stuctural defects.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	Virginia Avenue @ Lufty Avenue	LOCATION:	Asheville 28806
TYPE:	In House General Sewer Rehab	WORK ORDER:	48988
PROJECT NO.	2021271	TOTAL LF:	1,400
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements




ENGINEER:	MSD - MS	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 1,400 LF of sewerline with 8-inch DIP, by dig and replace.

SPECIAL PROJECT NOTES:	Existing line is in poor condition and undersized.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	28 Vista St	LOCATION:	Asheville 28803
TYPE:	In House General Sewer Rehab	WORK ORDER:	305205
PROJECT NO.	2024211	TOTAL LF:	900
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements




ENGINEER:	MSD - BD	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 7 ]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 900 LF of sewer mainline with 8-inch DIP, by dig and replace.

SPECIAL PROJECT NOTES: Existing line is in poor condition.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	Wellington Street Phase 1	LOCATION:	Asheville 28806
TYPE:	In House General Sewer Rehab	WORK ORDER:	280245
PROJECT NO.	2021274	TOTAL LF:	459
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements




ENGINEER:	MSD - MS	
R.O.W. ACQUISITION:	MSD	# PLATS: [0]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 459 LF of sewerline with 8-inch DIP, by dig and replace.

#### **BUDGET DATA SHEET - FY 2025-2026**

PROJECT:	Wellington Street Phase 2	LOCATION:	Asheville 28806
TYPE:	In House General Sewer Rehab	WORK ORDER:	300947
PROJECT NO.	2021274	TOTAL LF:	781
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements



ENGINEER:	MSD - MS	
R.O.W. ACQUISITION:	MSD	# PLATS: [0]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 781 LF of sewerline with 8-inch DIP, by dig and replace.

SPECIAL PROJECT NOTES:	Existing line is in poor condtion and undersized.

#### **BUDGET DATA SHEET - FY 2025-2026**


PROJECT:	12 W. Cotton Ave	LOCATION:	Black Mountain 28711
TYPE:	In House General Sewer Rehab	WORK ORDER:	309214
PROJECT NO.	2025019	TOTAL LF:	320
PROJECT BUDGET:	Funded through Project 2002101	PROJECT ORIGIN:	In-House Capital Improvements




ENGINEER:	MSD - MS	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]
CONTRACTOR:	MSD	
CONSTRUCTION ADM:	MSD In-House	
INSPECTION:	MSD In-House	

PROJECT DESCRIPTION: Project consists of replacing approximately 320 LF of existing mainline with 8-inch DIP, by dig and replace construction.


SPECIAL PROJECT NOTES: Existing pipe has multiple structured defects.





#### BUDGET DATA SHEET - FY 2025 - 2026

PROJECT:	Surveys for Design	LOCATION:	Various	
TYPE:	General Sewer Rehab.	PIPE RATING:	N/A	
			N/A	
PROJECT NO.	2002060	TOTAL LF:		
	4500 000 00			
PROJECT BUDGET:	\$500,000.00	PROJECT ORIGIN:	Surveys for future proje	ects
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$500,000.00			\$50,000.00
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION				
55430 - CONST. CONTRACT ADM.				
55440 - TESTING				
55450 - SURVEY - ASBUILT				
TOTAL AMOUNT	\$500,000.00	\$0.00	\$0.00	\$50,000.00
ENGINEER:		НС	ESTIMATED BUD	GETS - FY 27 - 35
R.O.W. ACQUISITION:		# PLATS: [ ]	FY 26-27	\$50,000.00
CONTRACTOR:			FY 27-28	\$50,000.00
CONSTRUCTION ADM:	FY 28-29	\$50,000.00		
INSPECTION:	FY 29-30	\$50,000.00		
			FY 30-31 \$50,0	
PROJECT DESCRIPTION: New rehab	FY 31-32	\$50,000.00		
This line item provides for surveying	V FY 32-33 \$50.0			
begin prior to being formally incorporations begin prior to being formally incorporations.	ated into the next year's CIP. This help	s to ensure projects are	FY 33-34	\$50,000.00
completed emolently.			FY 34-35	\$50,000.00
SPECIAL PROJECT NOTES:	Funds are transferred out to provide Survey	for Design for Future Projec	ts.	
	Total estimated project cost shown is the tot	al within the ten year window	· · · · · · · · · · · · · · · · · · ·	



#### **BUDGET DATA SHEET - FY 2025 - 2026**

PROJECT:	Future Projects - Non Critical		LOCATION:	Various	
TYPE:	General Sewer Rehab.		PIPE RATING:	N/A	
ITPE:	General Sewer Reliab.		PIPE RATING:	N/A	
PROJECT NO.	Various	TOTAL LF: 0			
PROJECT BUDGET:	Varies		PROJECT ORIGIN:	SSO's, Work Order	s, Line condition
Project	Engineer	Project Number	Pipe Rating	Project Footage	Estimated Cost
		1			
Craggy Street @ Old US 70	BD	2015209	2	1,000	\$424,120
McDowell St @ Short McDowell	TH	2024041	2	1,028	\$516,700
New Airport Rd. @ I-26	TH	2020021	2	223	\$99,000
Patton Ave. @ Piney Park Rd	BD	2024042	2	1,134	\$1,249,200
Riverside Dr @ Riverside Baptist	TH	2016251	2	510	\$235,000
Tunnel Rd @ Chunns Cove Rd	SA	2021289	2	1,850	\$821,000
Battery Park Alley	SA	2016107	3	250	\$110,000
Four Inch Main - College Street	SA	2012128	3	1,000	\$740,750
Lakeshore @ Merrimon	BD	2014177	3	362	\$250,100
Lionel Place	DP	2015009	3	308	\$170,000
Sweeten Creek Road @ Weston Road	SA	2014187	3	1,775	\$656,425
Tunnel Rd. @ White Pine Drive	TH	2016101	3	1,100	\$424,500
Cumberland Avenue	BD	2014014	4	5,011	\$2,164,350
Kenilworth @ Springdale Rd.	BD	2014010	4	1,458	\$793,181
Riverside Dr. @ Silverline Plastic	SA	2012007	4	400	\$168,670
Upper Grassy Branch @ Maxwell Rd.	SA	2010096	4	1,000	\$350,210
Wood Ave. @ Parker Road	SA	2014188	4	1,050	\$491,600
Calvin Trail @ Greybeard Trail	TH	2021284	5	780	\$380,870
Haw Creek WW (CDM #6)	BD	2001194	5	3,800	\$1,509,500
Oakley Road @ School Road	TH	2018031	6	600	\$254,000
AB Tech EQ Tank	BD	2019047	N/A	0	\$1,750
Mud Creek Interceptor - Ph. 3	BD	2020010	N/A	9,200	\$5,010,265
South French Broad Relief Int.	TH	2017070	N/A	36,330	\$46,490,860
TOTAL AMOUNT				70,169	\$63,312,051


PROJECT DESCRIPTION: This is a listing of projects which have low Pipe Ratings and are therefore less critical than other projects within the Ten Year CIP. All projects are reprioritized each year, and the schedule for the entire program is adjusted based on project criticality.


### Capital Improvement Program

Fiscal Years 2026—2035


### Private Sewer Rehabilitation Projects









PROJECT:	Carver Ave. @ Owenby Lane	LOCATION:	Asheville	
	<u> </u>			
TYPE:	Private Sewer Rehab.	PIPE RATING:	71	
PROJECT NO.	2022253	TOTAL LF:		
PROJECT BUDGET:	\$57,350.00	PROJECT ORIGIN:	Problematic Four and Six	Inch Lines
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
	PROJECT COST	THRU 12/31/24	JAN - JUNE 2025	F1 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	¢5 000 00	¢4.400.00	\$600.00	
55330 - DESIGN	\$5,000.00	\$4,400.00	\$600.00	
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$8,850.00			\$8,000.00
55370 - LEGAL FEES	\$11,000.00			\$9,000.00
55380 - ACQUISITION SERVICES	, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,			, ,,,,,,,,,,
55390 - COMPENSATION	\$30,000.00			\$30,000.00
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION				
55430 - CONST. CONTRACT ADM.				
55440 - TESTING				
55450 - SURVEY - ASBUILT	\$2,500.00			
TOTAL AMOUNT	\$57,350.00	\$4,400.00	\$600.00	\$47,000.0
ENGINEER	MOD		EQTIMATED BUILD	
ENGINEER:	MSD MSD	DP # DI ATS: 1 0 1	ESTIMATED BUDGI	
R.O.W. ACQUISITION:	Mad	# PLATS: [ 9 ]	FY 26-27	\$2,850.00
CONTRACTOR:  CONSTRUCTION ADM:	MSD		FY 27-28 FY 28-29	\$2,500.00
INSPECTION:	MSD		FY 29-30	\$0.00
INOI EOTION.	WOD		FY 30-31	\$0.00
			FY 31-32	\$0.00
	ect is located in Black Mountain just north gh residential properties. The existing 4-inc		FY 32-33	\$0.00
	gri residential properties. The existing 4-ind tructural condition. These issues have crea		FY 33-34	\$0.0° \$0.0°
service calls.			FY 34-35	\$0.00
			<u> </u>	ψ0.0




PROJECT:	Douglas Place PSR	LOCATION:	Asheville	
	2009.001.0001.01		7.00	
TYPE:	Private Sewer Rehab.	PIPE RATING:	12	
PROJECT NO.	2011116	TOTAL LF:	588	
PROJECT BUDGET:	\$240,230.00	PROJECT ORIGIN:	Problematic Four Inch P	rivate Sewer Main
		II.		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		ı		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$4,980.00	\$4,980.00		
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS 55370 - LEGAL FEES	\$1,500.00			
55370 - LEGAL FEES 55380 - ACQUISITION SERVICES	\$1,500.00			
55390 - ACQUISITION SERVICES  55390 - COMPENSATION				
55400 - APPRAISAL	\$5,000.00			
55410 - CONDEMNATION				
55420 - CONSTRUCTION	¢225 000 00			
55430 - CONST. CONTRACT ADM.	\$225,000.00			
55440 - TESTING	\$1,000.00			
55450 - SURVEY - ASBUILT	\$1,250.00			
TOTAL AMOUNT	\$240,230.00	\$4,980.00	\$0.00	\$0.00
ENGINEER:	MSD	SA	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 1 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$8,000.00
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
DDO IECT DESCRIPTION, This	sign is located in West Ashaville and in second	priced of 500 LE of 0 in the	FY 31-32	\$0.0
ductile iron pipe. The existing line is	oject is located in West Asheville and is comp s a problematic 4-inch private sewer line cor	ภาระน	1	\$0.0
with many defects.	•		FY 33-34	\$227,250.0
			FY 34-35	\$0.0



PROJECT:	Homeland Park	LOCATION:	Asheville	
TYPE:	Private Sewer Rehab.	PIPE RATING:	51	
PROJECT NO.	2016248	TOTAL LF:	921	
PROJECT BUDGET:	\$511,730.00	PROJECT ORIGIN:	Work Orders, Line Condit	ion
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$7,250.00	\$7,250.00		
55330 - DESIGN				
55340 - PERMITS	\$500.00			\$500.00
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$17,850.00			\$16,150.00
55370 - LEGAL FEES	\$21,500.00			
55380 - ACQUISITION SERVICES	\$76,000.00			
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION 55420 - CONSTRUCTION				
55430 - CONST. CONTRACT ADM.	\$385,130.00			
55440 - TESTING	24,000,00			
55450 - SURVEY - ASBUILT	\$1,000.00 \$2,500.00			
TOTAL AMOUNT	\$511,730.00		\$0.00	\$16,650.00
	<b>\$011,100.00</b>	<b>\$7,200.00</b>	\$0.00	ψ10,000.00
ENGINEER:	MSD	тн	ESTIMATED BUDGE	 ETS - FY 27 - 35
R.O.W. ACQUISITION:	CONSULTANT	# PLATS: [ 19 ]	FY 26-27	\$77,700.00
CONTRACTOR:			FY 27-28	\$410,130.00
CONSTRUCTION ADM.:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
PROJECT DESCRIPTION: This pro	oject is located in East Asheville just sou	ith of the intersection of	FY 31-32	\$0.00
Swannanoa River Road and Tunnel	Road in Homeland Park. This project consi	sts of 921 LF of existing	FY 32-33	\$0.00
4-inch VCP replacing with new 8-in subdivision and is full of roots, which	nch DIP. The existing 4-inch private sewel	is the main line for this	FY 33-34	\$0.00
Sasarrision and is full of foots, Willon	That inggered humerous service cans.		FY 34-35	\$0.00



PROJECT:	Old County Home Rd PSR	LOCATION:	W. Asheville	
TYPE:	Private Sewer Rehab.	PIPE RATING:	55	
PROJECT NO.	2015221	TOTAL LF:	4,592	
PROJECT BUDGET:	\$3,225,300.00	PROJECT ORIGIN:	Problematic Four Inch Line	,
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$18,800.00	\$18,800.00		
55330 - DESIGN				
55340 - PERMITS	\$1,000.00		\$1,000.00	
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS 55370 - LEGAL FEES	\$19,500.00	\$19,500.00		
55380 - ACQUISITION SERVICES	\$25,000.00	\$22,140.00	\$2,860.00	
55390 - COMPENSATION		*******	400 500 00	
55400 - APPRAISAL	\$80,000.00	\$46,418.00	\$33,582.00	
55410 - CONDEMNATION	\$7,000.00 \$28,000.00		\$7,000.00 \$28,000.00	
55420 - CONSTRUCTION	\$3,033,000.00		\$28,000.00	\$3,033,000.0
55430 - CONST. CONTRACT ADM.	\$5,033,000.00			ψ3,033,000.0
55440 - TESTING	\$3,000.00			\$3,000.0
55450 - SURVEY - ASBUILT	\$10,000.00			\$10,000.0
TOTAL AMOUNT	\$3,225,300.00	\$106,858.00	\$72,442.00	\$3,046,000.00
ENGINEER:	MSD	SA	ESTIMATED BUDGET	'S - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 21 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
PROJECT DESCRIPTION: This project	t is located in West Asheville and is comprised	of 507 LF of 18-inch ductile	FY 31-32	\$0.0
iron nine 2 293 I F 12-inch ductile iron n	oipe, and 1704 LF 8-inch ductile iron pipe. Addition om Erwin Hills Pump Station into the top of this	nally 88 LF of 8" PVC force	FY 32-33	\$0.0
existing line is a problematic 4" and 8" so	ewer line composed of PVC and VCP with many of	defects.		\$0.0
			FY 34-35	\$0.0




PROJECT:	Patton Mountain - PSR	LOCATION:	Asheville	
TYPE:	Private Sewer Rehab	PIPE RATING:	11	
PROJECT NO.	2000084	TOTAL LF:	3,500	
PROJECT BUDGET:	\$1,095,400.00	PROJECT ORIGIN:	Structural condition and re	oots
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		,		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$24,500.00			
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS	\$12,000.00			
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,050,000.00			
55430 - CONST. CONTRACT ADM.				
55440 - TESTING	\$2,000.00			
55450 - SURVEY - ASBUILT	\$6,900.00	i		
TOTAL AMOUNT	\$1,095,400.00	\$0.00	\$0.00	\$0.00
ENGINEER:	MSD	BD	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	#PLATS: [ 14 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$24,500.0
			FY 30-31	\$12,000.0
			FY 31-32	\$0.0
PROJECT DESCRIPTION: This pro	oject is located off of Patton Mountain Rd. on	Town Mountain, adjacent	FY 32-33	\$1,058,900.0
	ce. It consists of replacing approximately 3 The existing pipe is in poor structural condition		FY 33-34	\$0.0
	I said pipe is in poor off dotain contain		FY 34-35	\$0.0


## Capital Improvement Program

Fiscal Years 2026—2035

## Treatment Plant, Pump Stations, & General Capital Improvements









PROJECT:	Arc Flash Labeling	LOCATION:	District-Wide	
	, a o i laon Laboning	LOSATION.	D.O. HOLTHIGO	
TYPE:	General Cap. Improv Annual	PIPE RATING:	N/A	
	· · · · · · · · · · · · · · · · · · ·			
PROJECT NO.	2023008	TOTAL LF:	0	
PROJECT BUDGET:	\$355,225.00	PROJECT ORIGIN:	OSHA/NFPA Code require	ment
		<u> </u>		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
ESCALO PRELIM ENGINEERING				
55310 - PRELIM. ENGINEERING 55320 - SURVEY - DESIGN				
55330 - DESIGN				
55330 - DESIGN 55340 - PERMITS				
55350 - SPECIAL STUDIES	\$254.400.00	¢444.042.00	¢02 557 00	¢45,000,0
55360 - EASEMENT PLATS	\$354,400.00	\$111,843.00	\$92,557.00	\$15,000.0
55370 - LEGAL FEES	\$825.00	\$225.00	\$600.00	
55380 - ACQUISITION SERVICES	φ023.00	φ223.00	\$000.00	
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION				
55430 - CONST. CONTRACT ADM.				
55440 - TESTING				
55450 - SURVEY - ASBUILT				
TOTAL AMOUNT	\$355,225.00	\$112,068.00	\$93,157.00	\$15,000.00
ENGINEER:	Consultant	BD	ESTIMATED BUDGET	S - FY 27 - 35
R.O.W. ACQUISITION:		#PLATS: [ 0 ]	FY 26-27	\$15,000.00
CONTRACTOR:	MeD		FY 27-28	\$15,000.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$15,000.00
INSPECTION:	MSD		FY 29-30 FY 30-31	\$15,000.0
			FY 30-31	\$15,000.0
	n is for the replacement of arc flash labels on			\$15,000.0
	various MSD buildings, pump stations and tre ire Protection Assoc. (NFPA) and warn of po		FY 33-34	\$15,000.0
	(5) years per NFPA 70, Section 1160.16.		FY 34-35	\$15,000.0 \$15,000.0
SPECIAL PROJECT NOTES:				\$15,000.0




PROJECT:	Ash Lagoon Overflow Rehab	LOCATION:	MSD-Treatment Plant	
- NOSEOT.	Asii Lagooii Overilow Reliab	ECCATION.	MOD-Freatment Flant	
ГҮРЕ:	Treatment Plant	PIPE RATING:	N/A	
PROJECT NO.	2025031	TOTAL LF:	0	
PROJECT BUDGET:	\$185,000.00	PROJECT ORIGIN:	Aging Infrastructure	
	FOTIMATED	TOTAL EXPENDS	FOT 000T	PUPOET
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN				
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$185,000.00			\$185,000.0
55430 - CONST. CONTRACT ADM.				
55440 - TESTING				
55450 - SURVEY - ASBUILT				
TOTAL AMOUNT	\$185,000.00	\$0.00	\$0.00	\$185,000.0
TACINEED.	MSD	SA	ESTIMATED BUDGET	FC FV 27 25
ENGINEER: R.O.W. ACQUISITION:	N/A	# PLATS: [ 0 ]	FY 26-27	
CONTRACTOR:	TBD		FY 27-28	\$0.0
CONSTRUCTION ADM.:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0 \$0.0
			FY 30-31	\$0.0
			FY 31-32	\$0.0
PROJECT DESCRIPTION: This proje	ect includes rehabilitation of the ash lagoon over	erflow structure, originally	FY 32-33	\$0.0
constructed in the late 1960s. The condition.	concrete structure controls the water level in the	ash lagoon and is in poo	FY 33-34	\$0.0
Jonanion.				φυ.ι




	BODGET DATA SHEE			
PROJECT:	Biological Treatment	LOCATION:	MSD-Treatment Plant	
TYPE:	Treatment Plant	PIPE RATING:	N/A	
PROJECT NO.	2016063	TOTAL LF:	0	
PROJECT BUDGET:	\$247,821,725.00	PROJECT ORIGIN:	Future Regulatory Requir	ements
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING	\$650,000.00	\$334,702.00	\$115,298.00	\$200,000.00
55320 - SURVEY - DESIGN	\$50,000.00			
55330 - DESIGN	\$36,100,000.00			
55340 - PERMITS	\$320,000.00			
55350 - SPECIAL STUDIES	\$350,000.00		\$249,500.00	\$100,500.00
55360 - EASEMENT PLATS				
55370 - LEGAL FEES	\$1,725.00	\$225.00		
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$200,000,000.00			
55430 - CONST. CONTRACT ADM.	\$10,000,000.00			
55440 - TESTING	\$300,000.00			
55450 - SURVEY - ASBUILT	\$50,000.00			
TOTAL AMOUNT	\$247,821,725.00	\$334,927.00	\$364,798.00	\$300,500.00
ENGINEER:	Consultant	DP	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:		# PLATS: [ 0 ]	FY 26-27	\$0.00
CONTRACTOR:	TBD		FY 27-28	\$0.00
CONSTRUCTION ADM.:	TBD		FY 28-29	\$0.00
INSPECTION:	MSD & Consultant		FY 29-30	\$0.00
			FY 30-31	\$50,000.0
			FY 31-32	\$101,500.0
PROJECT DESCRIPTION: This proied	ct is the final and most significant recomm	nendation from the Plant	FY 32-33	\$25,160,000.00
Facilities Plan. It will replace the Ro	otating Biological Contactors (RBC's) with		FY 33-34	\$51,635,000.0
treatment technology. This project will	be driven by regulatory requirements.		FY 34-35	\$55,475,000.0
			Beyond FY 33-34	\$114,350,000.00
SPECIAL PROJECT NOTES:	This project will be design-build delivery met	thod. The budgetary breakdo	own is not similar to the typical	design, bid, build
method. Included in the design and const.	admin. budgets are the Owner's Adviser, Desig	gn Engineer, and Contractor	s Pre-construction fees.	




#### **BUDGET DATA SHEET - FY 2025 - 2026** PROJECT: LOCATION: **Building and Facility Rehabilitation MSD-Treatment Plant** TYPE: **Treatment Plant - Annual** PIPE RATING: N/A PROJECT NO. 2002068 TOTAL LF: 0 PROJECT BUDGET: \$600,000.00 PROJECT ORIGIN: Miscellaneous Building Repairs **TOTAL EXPENDS BUDGET ESTIMATED** EST. COST DESCRIPTION PROJECT COST THRU 12/31/24 **JAN - JUNE 2025** FY 25-26 55310 - PRELIM. ENGINEERING 55320 - SURVEY - DESIGN 55330 - DESIGN 55340 - PERMITS 55350 - SPECIAL STUDIES 55360 - EASEMENT PLATS 55370 - LEGAL FEES 55380 - ACQUISITION SERVICES 55390 - COMPENSATION 55400 - APPRAISAL 55410 - CONDEMNATION 55420 - CONSTRUCTION \$600,000.00 \$0.00 \$60,000.00 \$60,000.00 55430 - CONST. CONTRACT ADM. 55440 - TESTING 55450 - SURVEY - ASBUILT TOTAL AMOUNT \$600,000.00 \$0.00 \$60,000.00 \$60,000.00 ENGINEER: MSD **ESTIMATED BUDGETS - FY 27 - 35** R.O.W. ACQUISITION: MSD # PLATS: [ 0 ] FY 26-27 \$60,000.00 CONTRACTOR: FY 27-28 \$60,000.00 CONSTRUCTION ADM.: MSD FY 28-29 \$60,000.00 INSPECTION: MSD FY 29-30 \$60,000.00 FY 30-31 \$60,000.00 FY 31-32 \$60,000.00 PROJECT DESCRIPTION: This item is for the replacement of larger capital items such as roofing systems, FY 32-33 \$60,000.00 and subcontracts on buildings and structures within the MSD campus and treatment plant facility. Total FY 33-34 estimated project cost shown is the total within the ten year window. \$60,000.00 FY 34-35 \$60,000.00 SPECIAL PROJECT NOTES:




	BODGET DATA SHEET	-112020 - 2020		
PROJECT:	Carrier Bridge PS Replacement	LOCATION:	Asheville	
		-		
TYPE:	Pump Station Improvements	PIPE RATING:	N/A	
	· ·	-		
PROJECT NO.	2019045	TOTAL LF:	2,800	
		-	<u> </u>	
PROJECT BUDGET:	\$110,162,227.00	PROJECT ORIGIN:	CDM Preliminary Enginee	ring Report
		<u></u>		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING	\$1,025.00	\$1,025.00		
55320 - SURVEY - DESIGN	\$62,594.00	\$62,594.00		
55330 - DESIGN	\$2,159,577.00	\$1,837,989.00	\$321,588.00	
55340 - PERMITS	\$160,000.00	\$1,210.00	\$58,790.00	\$100,000.0
55350 - SPECIAL STUDIES	\$71,025.00	\$44,185.00	\$26,840.00	
55360 - EASEMENT PLATS	\$4,500.00		\$3,000.00	\$1,500.
55370 - LEGAL FEES	\$8,220.00	\$1,920.00	\$1,500.00	\$4,800.0
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$121,546.00	\$91,546.00		\$30,000.0
55400 - APPRAISAL	\$7,000.00			\$7,000.0
55410 - CONDEMNATION	\$35,000.00			
55420 - CONSTRUCTION	\$104,000,000.00			\$14,000,000.0
55430 - CONST. CONTRACT ADM.	\$3,200,000.00			\$500,000.0
55440 - TESTING	\$301,740.00	\$1,740.00		\$50,000.0
55450 - SURVEY - ASBUILT	\$30,000.00			
TOTAL AMOUNT	\$110,162,227.00	\$2,042,209.00	\$411,718.00	\$14,693,300.0
			1	
ENGINEER:	HDR	DP	ESTIMATED BUDGET	S - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 4 ]	FY 26-27	\$34,135,000.
CONTRACTOR:			FY 27-28	\$31,100,000
CONSTRUCTION ADM.:	MSD		FY 28-29	\$27,780,000
INSPECTION:	MSD		FY 29-30	\$0.
			FY 30-31	\$0
DDO IFOT DECODIDATION. This project	t will increase the capacity of the Carrier	Bridge Pump Station to	FY 31-32	\$0
PROJECT DESCRIPTION: This project			(IIIII)	00
40MGD to accommodate future grow	th in south and west Asheville, as well a tion, screening, odor control, electrical bui			\$0
40MGD to accommodate future grow includes replacement of the pump sta		lding, and an emergency	/ =>/ 00 04	\$0. \$0.




PROJECT:	Collection System Master Plan Update	LOCATION:	District-Wide	
TYPE:	General Capital Improvement	PIPE RATING:	N/A	
PROJECT NO.	2020011	TOTAL LF:	0	
PROJECT BUDGET:	\$299,500.00	PROJECT ORIGIN:	Master Plan Update/CCWS	D Merger
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN				
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES	\$299,500.00	\$49,500.00	\$0.00	\$0.00
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION				
55430 - CONST. CONTRACT ADM.				
55440 - TESTING				
55450 - SURVEY - ASBUILT TOTAL AMOUNT		<u> </u>		
TOTAL AMOUNT	\$299,500.00	\$49,500.00	\$0.00	\$0.00
ENGINEER:	Consultant	нс	ESTIMATED BUDGETS	S - FY 27 - 35
R.O.W. ACQUISITION:		#PLATS: [ 0 ]	FY 26-27	\$125,000.00
CONTRACTOR:			FY 27-28 \$125,000	
CONSTRUCTION ADM.:			FY 28-29	\$0.00
INSPECTION:			FY 29-30	\$0.00
			FY 30-31	\$0.00
			FY 31-32	\$0.00
PROJECT DESCRIPTION: The Description of the Project of The Market	District's Collection System Master Plan was	completed in 2008 and	FY 32-33	\$0.00
needs to be updated. The Master District and any updates from MSD	Plan Update will include the merger with Can member agencies.	ie Greek vvater & Sewer	FY 33-34	\$0.00
			FY 34-35	\$0.00
SPECIAL PROJECT NOTES:	This project has been delayed due to impacts	of Hurricana Halana, inclus	ding damage to flow monitoring s	tations




PROJECT:	Flow Monitoring	LOCATION:	MSD-Treatment Plant	
	-			
TYPE:	Treatment Plant	PIPE RATING:	N/A	
PROJECT NO.	2008013	TOTAL LF:	0	
PROJECT BUDGET:	\$1,000,000.00	PROJECT ORIGIN:	Maintenance of Permanent	Flow Monitors
DESCRIPTION	ESTIMATED	TOTAL EXPENDS	EST. COST	BUDGET
BEGGIAN FIGH	PROJECT COST	THRU 12/31/24	JAN - JUNE 2025	FY 25-26
		*		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN				
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,000,000.00		\$75,000.00	\$100,000.00
55430 - CONST. CONTRACT ADM.				
55440 - TESTING				
55450 - SURVEY - ASBUILT				
TOTAL AMOUNT	\$1,000,000.00	\$0.00	\$75,000.00	\$100,000.00
ENGINEER:	MSD	SA	ESTIMATED BUDGETS	S - FY 27 - 35
R.O.W. ACQUISITION:	N/A	# PLATS: [ 0 ]	FY 26-27	\$100,000.0
CONTRACTOR:			FY 27-28	\$100,000.0
CONSTRUCTION ADM.:	MSD		FY 28-29	\$100,000.0
INSPECTION:	MSD		FY 29-30	\$100,000.0
			FY 30-31	\$100,000.0
			FY 31-32	\$100,000.0
	ect is for expenses related to the continued	operation, maintenance,	FY 32-33	\$100,000.0
and improvements of the District's flo	ow monitoring program.		FY 33-34	\$100,000.0
			FY 34-35	\$100,000.0
SPECIAL PROJECT NOTES:				




	BODGET DATA SHEE	1 - 1 1 2023 - 202	<u> </u>		
PROJECT:	Headworks-HRPT Facility Improv	LOCATION:	MSD-Treatment Plant		
	, ·				
TYPE:	Treatment Plant	PIPE RATING:	N/A		
PROJECT NO.	2025028	TOTAL LF:	0		
PROJECT BUDGET:	\$325,000.00	PROJECT ORIGIN:	Operations efficiency		
		-11			
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26	
55310 - PRELIM. ENGINEERING			T T		
55320 - SURVEY - DESIGN					
55330 - DESIGN	#00.000.00			#00.000.00	
55340 - PERMITS	\$20,000.00			\$20,000.00	
55350 - SPECIAL STUDIES					
55360 - EASEMENT PLATS					
55370 - LEGAL FEES					
55380 - ACQUISITION SERVICES					
55390 - COMPENSATION					
55400 - APPRAISAL					
55410 - CONDEMNATION					
55420 - CONSTRUCTION	\$305,000.00			\$305,000.00	
55430 - CONST. CONTRACT ADM.				, ,	
55440 - TESTING					
55450 - SURVEY - ASBUILT					
TOTAL AMOUNT	\$325,000.00	\$0.00	\$0.00	\$325,000.00	
ENGINEER:	MSD	HC	ESTIMATED BUDGI	ETS - FY 27 - 35	
R.O.W. ACQUISITION:	N/A	# PLATS: [ 0 ]	FY 26-27	\$0.00	
CONTRACTOR:	TBD		FY 27-28	\$0.0	
CONSTRUCTION ADM.:	MSD		FY 28-29	\$0.0	
INSPECTION:	MSD		FY 29-30	\$0.0	
			FY 30-31	\$0.0	
PROJECT DESCRIPTION: This project	ect includes improvements at the Headworks	s and High Rate Primary	FY 31-32	\$0.0	
Treatment (HRPT) facilities. At the h	Headworks. industrial vinvl curtain walls will be	e installed around the fine	FY 32-33	\$0.0	
screens for wind and freeze protecting	ction in the winter. At the HRPT, a new m nd ballast loading into the treatment process.	nonorail and hoist will be	FY 33-34 \$0		
	2		FY 34-35	\$0.0	




PROJECT:	HVAC Rehabilitation	LOCATION:	MSD-Treatment Plant		
TYPE:	Treatment Plant - Annual	PIPE RATING:	N/A		
			_		
PROJECT NO.	2020051	TOTAL LF:	0		
PROJECT BUDGET:	\$110,000.00	PROJECT ORIGIN:	Misc HVAC Repairs/Replac	ement	
		I	<u> </u>		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26	
55310 - PRELIM. ENGINEERING					
55320 - SURVEY - DESIGN					
55330 - DESIGN					
55340 - PERMITS					
55350 - SPECIAL STUDIES					
55360 - EASEMENT PLATS					
55370 - LEGAL FEES					
55380 - ACQUISITION SERVICES					
55390 - COMPENSATION					
55400 - APPRAISAL					
55410 - CONDEMNATION					
55420 - CONSTRUCTION	\$110,000.00	\$0.00	\$70,000.00	\$20,000.00	
55430 - CONST. CONTRACT ADM.					
55440 - TESTING					
55450 - SURVEY - ASBUILT					
TOTAL AMOUNT	\$110,000.00	\$0.00	\$70,000.00	\$20,000.00	
ENGINEER:	MSD	HC		ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]	FY 26-27	\$10,000.0	
CONTRACTOR:	MCD		FY 27-28	\$10,000.00	
CONSTRUCTION ADM.:	MSD		FY 28-29	\$10,000.00	
INSPECTION:	MSD		FY 29-30 FY 30-31	\$10,000.0	
				\$10,000.0	
PROJECT DESCRIPTION: This item is for replacement of HVAC systems within the MSD campus			FY 31-32 \$10,000.		
treatment plant facility, and pump s	atment plant facility, and pump stations. Total estimated project cost shown is the total within th		en \$10,00		
year window.			FY 33-34 FY 34-35	\$10,000.0	
EDECIAL DEGLECT NOTES:			1 1 34-30	\$10,000.0	
SPECIAL PROJECT NOTES:					




PROJECT:	Hydroelectric Power Plant I	Rehab	LOCATION:	MSD-Treatment Plant	
	<u> </u>				
TYPE:	Treatment Plant		PIPE RATING:	N/A	
PROJECT NO.	2021016		TOTAL LF:	0	
PROJECT BUDGET:	\$3,641,350.00		PROJECT ORIGIN:	Aging Equipment, Condition	on
DESCRIPTION	ESTIMATED PROJECT COST		TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING		1		l I	
55310 - PRELIM. ENGINEERING 55320 - SURVEY - DESIGN					
55330 - DESIGN		£220 000 00		¢400,000,00	¢400,000,00
55340 - PERMITS		\$220,000.00		\$100,000.00	\$120,000.00
55350 - SPECIAL STUDIES		\$200,000.00	\$162,262.00	\$37,738.00	
55360 - EASEMENT PLATS	,	φ200,000.00	φ102,202.00	\$37,730.00	
55370 - LEGAL FEES		\$1,350.00	\$1,350.00		
55380 - ACQUISITION SERVICES		ψ1,000.00	ψ 1,000.00		
55390 - COMPENSATION					
55400 - APPRAISAL					
55410 - CONDEMNATION					
55420 - CONSTRUCTION	\$3	3,180,000.00			\$165,000.00
55430 - CONST. CONTRACT ADM.		\$40,000.00			
55440 - TESTING					
55450 - SURVEY - ASBUILT					
TOTAL AMOUNT	\$3	3,641,350.00	\$163,612.00	\$137,738.00	\$285,000.00
ENGINEER:	MSD	TH		ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	MSD		# PLATS: [ 0 ]	FY 26-27	\$375,000.0
CONTRACTOR:				FY 27-28	\$335,000.0
CONSTRUCTION ADM.:	MSD			FY 28-29	\$335,000.0
INSPECTION:	MSD			FY 29-30	\$335,000.0
				FY 30-31	\$335,000.0
PROJECT DESCRIPTION: This pro	piect includes an evaluation of the	existing by	droelectric plant and its	FY 31-32	\$335,000.0
<b>PROJECT DESCRIPTION</b> : This project includes an evaluation of the existing hydroelectric plant and i aging infrastructure. The study will consider the cost benefit of replacing various components with mo			s components with more	\$555,000.	
efficient technology. The project al	so includes rehabilitation of the influ	uent bar scre	een structure.	FY 33-34 FY 34-35	\$335,000.0 \$335,000.0




PROJECT:	Incinerator Ash Line Replacement	LOCATION:	MSD-Treatment Plant		
TYPE:	Treatment Plant	PIPE RATING:	N/A		
PROJECT NO.	2025030	TOTAL LF:	500		
PROJECT BUDGET:	\$400,000.00	PROJECT ORIGIN:	Aging Infrastructure		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26	
55310 - PRELIM. ENGINEERING					
55320 - SURVEY - DESIGN					
55330 - DESIGN					
55340 - PERMITS					
55350 - SPECIAL STUDIES					
55360 - EASEMENT PLATS					
55370 - LEGAL FEES					
55380 - ACQUISITION SERVICES					
55390 - COMPENSATION					
55400 - APPRAISAL					
55410 - CONDEMNATION					
55420 - CONSTRUCTION	\$400,000.00			\$400,000.00	
55430 - CONST. CONTRACT ADM.					
55440 - TESTING					
55450 - SURVEY - ASBUILT					
TOTAL AMOUNT	\$400,000.00	\$0.00	\$0.00	\$400,000.00	
ENGINEER:	MSD	ISD HC		ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	N/A	# PLATS: [ 0 ]	FY 26-27	\$0.00	
CONTRACTOR:	TBD		FY 27-28	\$0.00	
CONSTRUCTION ADM.:	MSD		FY 28-29	\$0.00	
INSPECTION:	MSD		FY 29-30	\$0.00	
			FY 30-31	\$0.00	
			FY 31-32	\$0.00	
	ct includes replacement of the 4" ash line tha . Most of the line was installed in the early 19			\$0.00	
multiple breaks over the years. The			FY 33-34	\$0.00	
			FY 34-35	\$0.00	
SPECIAL PROJECT NOTES:					



PROJECT:	Incinerator Rehabilitation	LOCATION:	MSD-Treatment Plant	
TYPE:	Treatment Plant	PIPE RATING:	N/A	
PROJECT NO.	2022057	TOTAL LF:	0	
PROJECT BUDGET:	\$5,383,225.00	PROJECT ORIGIN:	Aging Equipment, IFCO Re	commendation
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN				
55330 - DESIGN 55340 - PERMITS				
55350 - SPECIAL STUDIES				
55350 - SPECIAL STUDIES 55360 - EASEMENT PLATS				
55370 - LEGAL FEES	\$225.00	\$225.00		
55380 - ACQUISITION SERVICES	\$225.00	\$225.00		
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$5,383,000.00	\$2,105,073.00	\$1,277,927.00	\$2,000,000.00
55430 - CONST. CONTRACT ADM.	\$0,000,000.00	Ψ2,100,010.00	Ψ1,Σ11,0Σ1.00	Ψ2,000,000.00
55440 - TESTING				
55450 - SURVEY - ASBUILT				
TOTAL AMOUNT	\$5,383,225.00	\$2,105,298.00	\$1,277,927.00	\$2,000,000.00
			1	
ENGINEER:	MSD	DP	ESTIMATED BUDGETS - FY 27 - 35	
R.O.W. ACQUISITION:	N/A	# PLATS: [ 0 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM.:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
PROJECT DESCRIPTION: This project is for the rehabilitation of the incinerator and includes replacement on the heat exchanger, preheat burner system, and high temperature refractory lining inside the fluidizing becoming incinerator. The refractory was last replaced in 2004 and protects the steel shell of the incinerator from			FY 31-32 \$0.	
			1	
high temps and corrosive gases. To wear and need to be replaced.	he heat exchanger and preheat burner both	show signs of significant	FY 33-34 FY 34-35	\$0.0
SPECIAL PROJECT NOTES:	This project was previously named Incinerato	r Rehabilitation EV 24	<u>  -                                   </u>	\$0.0
	mis project was previously named incinerato	i iveriabilitatioti FT 24.		



PROJECT:	Incinerator Sand Transport System	LOCATION:	MSD Treatment Plant	
TYPE:	Treatment Plant	PIPE RATING:	N/A	
PROJECT NO.	2024036	TOTAL LF:	0	
PROJECT BUDGET:	\$400,125.00	PROJECT ORIGIN:	Aging Equipment and Cond	lition
		Tr.		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		·		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN				
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES	\$125.00	\$125.00		
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$400,000.00	\$30,509.00	\$244,491.00	\$125,000.00
55430 - CONST. CONTRACT ADM.				
55440 - TESTING				
55450 - SURVEY - ASBUILT		<u> </u>		
TOTAL AMOUNT	\$400,125.00	\$30,634.00	\$244,491.00	\$125,000.00
ENGINEER:	MSD	TH	ESTIMATED BUDGETS	S - FY 27 - 35
R.O.W. ACQUISITION:	MSD	#PLATS: [ 0 ]	FY 26-27	
CONTRACTOR:			FY 27-28	\$0.00 \$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
			FY 31-32	\$0.00
PROJECT DESCRIPTION: Existing sys	stem is undersized and reequires routine mainane	ence visits. Replacement of	FY 32-33	\$0.00
the Incinerator Sand Transport System and integrated controls, and sand reclain	will conisist of replacing the sand silo, new dust	collector, transport system	FY 33-34	\$0.00
·	<del></del>		FY 34-35	\$0.00
SPECIAL PROJECT NOTES:			0	



#### **BUDGET DATA SHEET - FY 2025 - 2026** Interceptor Line Assess and Cleaning LOCATION: PROJECT: **District Wide** TYPE: Interceptor and Wet Weather PIPE RATING: N/A PROJECT NO. 2025029 TOTAL LF: 143,000 PROJECT BUDGET: \$5,180,000.00 PROJECT ORIGIN: **Hurricane Helene** TOTAL EXPENDS EST. COST BUDGET **ESTIMATED** DESCRIPTION PROJECT COST THRU 12/31/24 **JAN - JUNE 2025** FY 25-26 55310 - PRELIM, ENGINEERING 55320 - SURVEY - DESIGN 55330 - DESIGN 55340 - PERMITS 55350 - SPECIAL STUDIES 55360 - EASEMENT PLATS 55370 - LEGAL FEES 55380 - ACQUISITION SERVICES 55390 - COMPENSATION 55400 - APPRAISAL 55410 - CONDEMNATION 55420 - CONSTRUCTION \$2,590,000.00 \$5,180,000.00 55430 - CONST. CONTRACT ADM. 55440 - TESTING 55450 - SURVEY - ASBUILT TOTAL AMOUNT \$5,180,000.00 \$0.00 \$0.00 \$2,590,000.00 ENGINEER: MSD **ESTIMATED BUDGETS - FY 27 - 35** R.O.W. ACQUISITION: N/A # PLATS: [ 0 ] FY 26-27 \$2,590,000.00 CONTRACTOR: TBD FY 27-28 \$0.00 CONSTRUCTION ADM.: MSD FY 28-29 \$0.00 INSPECTION: MSD FY 29-30 \$0.00 FY 30-31 \$0.00 FY 31-32 \$0.00 PROJECT DESCRIPTION: This project includes CCTV, sonar inspection, and line cleaning of approximately FY 32-33 143,000LF of interceptor sewers ranging in size from 12" to 60" diameter. As a result of Hurricane Helene, \$0.00

FY 33-34

FY 34-35

Phase 1 will be completed in FY25/26 and consist of CCTV and sonar inspection. Phase 2 will be completed in

FY26/27 and consists of line cleaning. MSD will seek FEMA reimbursement for this project


\$0.00

\$0.00


debris (e.g. rock, dirt) was introduced into much of the collection system, reducing pipe capacity. Sonar

inspection will identify debris levels within the pipes and dictate the scope of cleaning.


SPECIAL PROJECT NOTES:




	BODGET BATA SHEE			
PROJECT:	Int. Clarifier Eff. Trough Rehab	LOCATION:	MSD - Treatment Plant	
TYPE:	Treatment Plant	PIPE RATING:	N/A	
PROJECT NO.	2022024	TOTAL LF:	0	
PROJECT BUDGET:	\$4,753,849.00	PROJECT ORIGIN:	Aging Infrastructure, Poo	r condition
NOOLOT BODGET.	ψ+,1 00,0+0.00	TROCEST CRIGHT.	Aging illiastractare, i co	- condition
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	<u> </u>			
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES	\$113.00	\$113.00		
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$4,753,736.00	\$674,144.00	\$979,592.00	\$2,750,000.0
55430 - CONST. CONTRACT ADM.				
55440 - TESTING				
55450 - SURVEY - ASBUILT		<u> </u>		
TOTAL AMOUNT	\$4,753,849.00	\$674,257.00	\$979,592.00	\$2,750,000.0
ENGINEER:	MSD	SA	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD		FY 26-27	\$350,000.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM.:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
PROJECT DESCRIPTION: The interm	ediate clarifier was placed into service in 19	90. Clarified water flows	FY 31-32	\$0.0
upward through one of four clarifier ba	asins and overflows into a series of aluminun	n effluent troughs. These		\$0.0
		e aluminum clarifiers with	FY 33-34	
troughs are in poor condition and are fiber reinforced polymer (FRP) troug	hs, which are believed to be less affected	by wastewater chemistry	F1 33-34	\$0.0
		by wastewater chemistry	FY 34-35	\$0.0 \$0.0




PROJECT:	ITT Pump Station Upgrade	LOCATION:	Henderson County	
r ROULOT.	111 Fullip Station Opgrade	ECCATION.	Tienderson County	
TYPE:	Pump Station Improvement	PIPE RATING:	N/A	
PROJECT NO.	2020061	TOTAL LF:	2,750 F	Y 26-27
PROJECT BUDGET:	\$5,779,411.00	PROJECT ORIGIN:	Aging Infrastructure	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		n-		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN				
55330 - DESIGN	\$284,411.00	\$219,411.00	\$50,000.00	\$15,000.00
55340 - PERMITS	\$9,000.00		\$9,000.00	
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES	\$25,000.00	\$238.00	\$18,000.00	\$6,762.00
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION	\$70,000.00			\$70,000.00
55400 - APPRAISAL	\$6,000.00			\$6,000.00
55410 - CONDEMNATION	\$35,000.00			\$35,000.00
55420 - CONSTRUCTION	\$5,110,000.00			\$650,000.00
55430 - CONST. CONTRACT ADM.	\$205,000.00			\$40,000.00
55440 - TESTING	\$15,000.00			\$3,000.00
55450 - SURVEY - ASBUILT	\$20,000.00			
TOTAL AMOUNT	\$5,779,411.00	\$219,649.00	\$77,000.00	\$825,762.00
ENGINEER:	MSD	SA	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 8 ]	FY 26-27	\$4,425,000.00
CONTRACTOR:			FY 27-28	\$232,000.00
CONSTRUCTION ADM.:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
PROJECT DESCRIPTION: The ITT p	oump station is located near the Broadpointe	Industrial Park in south	FY 31-32	\$0.00
Asheville. The station is generally in	fair to poor condition and in need of a capac flow of 0.8 MGD, and the forcemain will be	city increase. The station	FY 32-33	\$0.00
forcemain. The project will involve	a new access route through nearby parce		FY 33-34	\$0.00
upgrade.			FY 34-35	\$0.00
SPECIAL PROJECT NOTES:				




		11		
PROJECT:	MSD Fleet/Warehouse Resurface	LOCATION:	Asheville	
TYPE:	Water Reclamation Facility	PIPE RATING:	N/A	
PROJECT NO.	2025035	TOTAL LF:	0	
PROJECT BUDGET:	\$1,500,000.00	PROJECT ORIGIN:	Failing asphalt in parking I	lot
		II		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
FEO.40 DDELIM ENGINEEDING		1		
55310 - PRELIM. ENGINEERING 55320 - SURVEY - DESIGN				
55330 - DESIGN 55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,500,000.00			\$1,500,000.00
55430 - CONST. CONTRACT ADM.	Ψ1,500,000.50			Ψ1,300,000.00
55440 - TESTING				
55450 - SURVEY - ASBUILT				
TOTAL AMOUNT	\$1,500,000.00	\$0.00	\$0.00	\$1,500,000.00
ENGINEER:	MSD	SA	ESTIMATED BUDGET	S - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]	FY 26-27	\$0.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.00
			FY 30-31	\$0.00
PROJECT DESCRIPTION: This promaterial in the parking lot areas to	ject will include removing and replacing the west of its Fleet and warehouse build	ne asphalt and subgrade ings. MSD Staff believe	FY 31-32	\$0.00
flooding during Hurricane Helene de	egraded the subsurface conditions, exacerba	tina previously observed	FY 32-33	\$0.00
surficial cracking, and impacting the	asphalt's ability to support the heavy truck a remove the existing asphalt and subgrade	and equipment loads it is	FY 33-34	\$0.00
approximately 46,000 square foot are	ea and build back up with proper drainage sto		FY 34-35	\$0.00
SPECIAL PROJECT NOTES:				




PROJECT:	Mud Creek PS Replacement	LOCATION:	Henderson County	
TYPE:	Pump Station Improvement	PIPE RATING:	N/A	
PROJECT NO.	2021073	TOTAL LF:	0	
PROJECT BUDGET:	\$830,000.00	PROJECT ORIGIN:	Capacity Improvements	
		<u> </u>		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$15,000.00			
55330 - DESIGN	\$90,000.00			
55340 - PERMITS	\$5,000.00			
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$720,000.00	\$7,142.00	\$112,858.00	
55430 - CONST. CONTRACT ADM.				
55440 - TESTING				
55450 - SURVEY - ASBUILT		1		
TOTAL AMOUNT	\$830,000.00	\$7,142.00	\$112,858.00	\$0.00
ENGINEER:	TBD	TH	ESTIMATED BUDGE	TS - FV 27 - 35
R.O.W. ACQUISITION:	N/A	# PLATS: [ 0 ]	FY 26-27	\$15,000.00
CONTRACTOR:			FY 27-28	\$15,000.00
CONSTRUCTION ADM.:	TBD		FY 28-29	\$95,000.00
INSPECTION:	TBD		FY 29-30	\$0.00
			FY 30-31	\$0.00
			FY 31-32	\$0.00
PROJECT DESCRIPTION: This proje	ct is to increase firm capacity of the Mud Cre	ek Pumping System and	FY 32-33	\$0.00
to consolidate the two existing pur include upgrades to pump controls a	np stations into a single station. The repland	cement project will also	FY 33-34	\$0.0
	2 gono, saonap ponor suppry.		FY 34-35	\$0.00
SPECIAL PROJECT NOTES:			11	ψ0.00




PROJECT:	Plant NPW Filter System	LOCATION:	Asheville	
TYPE:	Water Reclamation Facility	PIPE RATING:	N/A	
PROJECT NO.	2023011	TOTAL LF:	0	
PROJECT BUDGET:	\$325,000.00	PROJECT ORIGIN:	Failing Equipment	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
FERMA DEEL IM ENGINEERING			1	
55310 - PRELIM. ENGINEERING 55320 - SURVEY - DESIGN	_			
55330 - DESIGN				
55330 - DESIGN 55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$325,000.00		\$100,000.00	
55430 - CONST. CONTRACT ADM.				
55440 - TESTING				
55450 - SURVEY - ASBUILT				
TOTAL AMOUNT	\$325,000.00	\$0.00	\$100,000.00	\$0.00
			1	
ENGINEER:	MSD	SA	ESTIMATED BUDGETS	S - FY 27 - 35
R.O.W. ACQUISITION:	MSD	# PLATS: [ 0 ]	FY 26-27	\$0.0
CONTRACTOR:	MOD		FY 27-28	\$225,000.0
CONSTRUCTION ADM: INSPECTION:	MSD MSD		FY 28-29 FY 29-30	\$0.0
INSPECTION.	IVIOU		FY 30-31	\$0.0
			FY 31-32	\$0.0
PROJECT DESCRIPTION: This proje	ect will install a filtration system ahead of the r	non-potable water pumps	FY 32-33	\$0.0
at the Water Reclamation Facility,	and is intended to mitigate problems with	silt and debris clogging	FY 33-34	\$0.0
individual filters at various processes	s throughout the WKF.		FY 34-35	\$0.0
SPECIAL PROJECT NOTES:			54-55	\$0.0




PROJECT:	RBC Removal and Replacement	LOCATION:	MSD-Treatment Plant	
TYPE:	Treatment Plant	PIPE RATING:	N/A	
PROJECT NO.	2023029	TOTAL LF:	0	
PROJECT BUDGET:	\$2,357,750.00	PROJECT ORIGIN:	Aging Equipment	
	<u> </u>			
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
ES240 DDELIM ENCINEEDING		1		
55310 - PRELIM. ENGINEERING 55320 - SURVEY - DESIGN				
55330 - SURVEY - DESIGN 55330 - DESIGN				
55330 - DESIGN 55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$2,357,750.00	\$677,750.00	\$0.00	\$840,000.0
55430 - CONST. CONTRACT ADM.	<b>\$2,001,100</b>	ψσ. τ ,τ σσ. σσ	40.00	φο.ο,οσο.ο
55440 - TESTING				
55450 - SURVEY - ASBUILT				
TOTAL AMOUNT	\$2,357,750.00	\$677,750.00	\$0.00	\$840,000.0
			ii	
ENGINEER:	MSD	НС	ESTIMATED BUDGET	rs - FY 27 - 35
R.O.W. ACQUISITION:	N/A	# PLATS: [ 0 ]	FY 26-27	\$840,000.0
CONTRACTOR:	TBD		FY 27-28	\$0.0
CONSTRUCTION ADM.:	MSD		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
PROJECT DESCRIPTION. This project	ct is for the removal and repalcement of broken,	non-functional RRC units	FY 31-32	\$0.0
at the treatment plant. The broken ι	ınits do not provide any biological treatment and	create a damming effect		\$0.
in the basin that negatively impacts of	operation.		FY 33-34	\$0.
			FY 34-35	\$0.
SPECIAL PROJECT NOTES:	RBC removal was completed in FY23/24. RBC to	units from Basin #3 will be re	elocated into Basins #1 and #2	in FY24/25 and




PRO IFOT	Onlide Handling Organity Insurance and	LOCATION	MOD Treatment Blank	
PROJECT:	Solids Handling Capacity Improvements	LOCATION:	MSD-Treatment Plant	
TYPE:	Treatment Plant	PIPE RATING:	N/A	
PROJECT NO.	2019087	TOTAL LF:	0	
PROJECT BUDGET:	\$171,156,500.00	PROJECT ORIGIN:	Capacity Improvements	
		1		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
			1 1	
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$30,000.00			
55330 - DESIGN	\$27,550,000.00			
55340 - PERMITS	\$220,000.00			
55350 - SPECIAL STUDIES	\$25,000.00			
55360 - EASEMENT PLATS				
55370 - LEGAL FEES 55380 - ACQUISITION SERVICES	\$1,500.00			
55390 - ACQUISITION SERVICES 55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$407.000.000.00			
55430 - CONST. CONTRACT ADM.	\$137,000,000.00			
55440 - TESTING	\$6,000,000.00			
55450 - SURVEY - ASBUILT	\$300,000.00 \$30,000.00			
TOTAL AMOUNT	\$171,156,500.00	\$0.00	\$0.00	\$0.00
	ψ111,100,000.00	<u>,                                      </u>	<del>                                     </del>	<del>             \</del>
ENGINEER:	Consultant	DP	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	NA	# PLATS: [ 0 ]	FY 26-27	\$5,976,500.00
CONTRACTOR:	TBD		FY 27-28	\$34,900,000.00
CONSTRUCTION ADM.:	TBD		FY 28-29	\$75,100,000.00
INSPECTION:	MSD		FY 29-30	\$36,100,000.00
			FY 30-31	\$19,080,000.00
PROJECT DESCRIPTION: This proje	ct will increase the capacity of the solids ha	indling processes at the	FY 31-32	\$0.00
treatment plant. Additional capacity generation from the High Rate Prima	is needed to accomodate future flow ratery. Treatment process and future biological pro	s and increased sludge cess upgrade. A Prelim	FY 32-33	\$0.00
Engineering Report will confirm exact	ntion from the High Rate Primary Treatment process and future biological process upgrade. A Prelim sering Report will confirm exact timing and costs of these capital investments. The project will include a			\$0.00
new solids disposal system and dewar	ering equipment.		FY 34-35	\$0.00
SPECIAL PROJECT NOTES:	This project will be design-build delivery method.	The budgetary breakdown i	s not similar to the typical des	ign, bid, build
method. Included in the design and const.	admin. budgets are the Owner's Adviser, Design En	gineer, and Contractor's Pr	e-construction fees.	



PROJECT:	South Storage Building	LOCATION:	Arden	
TYPE:	General Capital Imp.	PIPE RATING:	N/A	
PROJECT NO.	2023009	TOTAL LF:	0	
PROJECT BUDGET:	\$1,646,000.00	PROJECT ORIGIN:	Existing Building Unusab	le
		ll en		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
TOTAL DESIGN ENGINEEDING		1		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN				
55330 - DESIGN	\$120,000.00			\$120,000.00
55340 - PERMITS	\$10,000.00			\$10,000.00
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS 55370 - LEGAL FEES				
55370 - LEGAL FEES 55380 - ACQUISITION SERVICES				
55390 - ACQUISITION SERVICES 55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	£4 500 000 00			
55430 - CONST. CONTRACT ADM.	\$1,500,000.00			
55440 - TESTING	\$10,000.00 \$2,500.00			
55450 - SURVEY - ASBUILT	\$3,500.00			
TOTAL AMOUNT	\$1,646,000.00	\$0.00	\$0.00	\$130,000.00
ENGINEER:		DP	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:		# PLATS: [ ]	FY 26-27	\$1,516,000.00
CONTRACTOR:			FY 27-28	\$0.00
CONSTRUCTION ADM:	MSD		FY 28-29	\$0.00
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
DDO IDOT DECORPTION. This board	ing will be legated at MCD's south attended	facility in Arden The -it-	FY 31-32	\$0.0
<b>PROJECT DESCRIPTION:</b> This build used to be the location of an old v	ing will be located at MSD's south storage is vastewater treatment plant that was abando	lacility in Arden. The site oned in the 1990's. The	∍⊩	\$0.0
	ole in it's current condition. The new building		FY 33-34	\$0.0
			FY 34-35	\$0.0
SPECIAL PROJECT NOTES:				



PROJECT:	Weaverville PS Replacement	LOCATION:	Weaverville	
TYPE:	Pump Station Improvements	PIPE RATING:	N/A	
PROJECT NO.	2019080	TOTAL LF:	18,174	
			•	
PROJECT BUDGET:	\$24,479,509.00	PROJECT ORIGIN:	Capacity Improvements	
		<u></u>		
	ESTIMATED	TOTAL EXPENDS	EST. COST	BUDGET
DESCRIPTION	PROJECT COST	THRU 12/31/24	JAN - JUNE 2025	FY 25-26
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN	\$155,342.00	\$155,342.00		
55330 - DESIGN	\$1,100,000.00	\$982,643.00	\$117,357.00	
55340 - PERMITS	\$15,000.00	\$787.00	\$14,213.00	
55350 - SPECIAL STUDIES	\$20,000.00	\$19,750.00	\$250.00	
55360 - EASEMENT PLATS	\$73,000.00	\$51,905.00	\$21,095.00	
55370 - LEGAL FEES	\$38,717.00	\$36,217.00		\$2,500.00
55380 - ACQUISITION SERVICES	\$105,000.00	\$87,500.00	\$17,500.00	
55390 - COMPENSATION	\$90,000.00	\$64,984.00	\$25,016.00	
55400 - APPRAISAL	\$7,000.00		\$7,000.00	
55410 - CONDEMNATION	\$28,000.00		\$28,000.00	
55420 - CONSTRUCTION	\$21,986,375.00	\$1,722,370.00	\$8,264,005.00	\$12,000,000.00
55430 - CONST. CONTRACT ADM.	\$841,075.00	\$233,782.00	\$241,218.00	\$366,075.00
55440 - TESTING	\$20,000.00			\$20,000.00
55450 - SURVEY - ASBUILT				
TOTAL AMOUNT	\$24,479,509.00	\$3,355,280.00	\$8,735,654.00	\$12,388,575.00
			6174	1200
ENGINEER:	CDM-Smith	SA	ESTIMATED BUDGE	TS - FY 27 - 35
R.O.W. ACQUISITION:	Consultant	# PLATS: [ 30 ]	FY 26-27	\$0.0
CONTRACTOR:			FY 27-28	\$0.0
CONSTRUCTION ADM.:	Consultant		FY 28-29	\$0.0
INSPECTION:	MSD		FY 29-30	\$0.0
			FY 30-31	\$0.0
	ct is for the replacement of Weaverville Pum			\$0.0
Heavy growth has led to an increas stations are low on available capacit	ed demand for sewer allocations in Weaver y. This project includes replacing PS No. 1,	ville and as a result both replacing the existing 12	FY 32-33	\$0.0
inch force main with 18-inch, and cor	nverting PS No. 2 into a smaller residential			\$0.0
1 will be designed to pump directly to	othe WRF.		FY 34-35	\$0.0




PROJECT:	General Capital Equipment	LOCATION:	Varies	
<u> </u>				
TYPE:	General Capital	PIPE RATING:	N/A	
PROJECT NO.	2016072	TOTAL LE	0	
PROJECT NO.	2010072	TOTAL LF:	0	
PROJECT BUDGET:	\$1,550,000.00	PROJECT ORIGIN:	General Manager	
		IL		
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
		ir.		
55310 - PRELIM. ENGINEERING				
55320 - SURVEY - DESIGN				
55330 - DESIGN				
55340 - PERMITS				
55350 - SPECIAL STUDIES				
55360 - EASEMENT PLATS				
55370 - LEGAL FEES				
55380 - ACQUISITION SERVICES				
55390 - COMPENSATION				
55400 - APPRAISAL				
55410 - CONDEMNATION				
55420 - CONSTRUCTION	\$1,550,000.00	\$22,000.00	\$128,000.00	\$200,000.00
55430 - CONST. CONTRACT ADM.				
55440 - TESTING				
55450 - SURVEY - ASBUILT				
TOTAL AMOUNT	\$1,550,000.00	\$22,000.00	\$128,000.00	\$200,000.00
ENGINEER:	MSD	HC	ESTIMATED BUDGE	TO EV 27 25
R.O.W. ACQUISITION:	N/A	# PLATS: [ 0 ]	FY 26-27	
CONTRACTOR:	N/A	". EATO. [ V ]	FY 27-28	\$150,000.00
CONSTRUCTION ADM.:	MSD		FY 28-29	\$150,000.00
INSPECTION:	MSD		FY 29-30	\$150,000.00 \$150,000.00
			FY 30-31	\$150,000.00 \$150,000.00
			FY 31-32	
DDO IECT DESCRIPTION. This is f	or the purchase of capital equipment in	evenes of \$15,000,00		\$150,000.0 \$150,000.0
Examples include pumps, plant equip	ment, computer servers, large concrete saw	/s, etc.	FY 33-34	\$150,000.0 \$150,000.0
			FY 34-35	\$150,000.0 \$150,000.0
SPECIAL PROJECT NOTES:	Total Estimated project cost shown is the tot	al within the ten year windo	JL	ψ150,000.0
	Total Estimated project cost shown is the tot	ai witiiii tile tell year willuot	ν.	


### Capital Improvement Program

Fiscal Years 2026—2035

# Design, Right of Way, & Construction Management Expenses








PROJECT:	Design, ROW, & Const. Mgmt. Exp.	LOCATION:	MSD/ENG	
FUND:	F01	PIPE RATING:	N/A	
ACCOUNT CODE:	N/A	TOTAL LF:	0	
PROJECT BUDGET:	\$39,301,241	PROJECT ORIGIN:	CIP Expenses	
DESCRIPTION	ESTIMATED PROJECT COST	TOTAL EXPENDS THRU 12/31/24	EST. COST JAN - JUNE 2025	BUDGET FY 25-26
SALARIES & BENEFITS	\$35,470,057	\$1,545,030.50	\$1,545,031	\$3,094,071.00
(Includes Proj. Mgmt., ROW, Const.				
and a portion of GIS and Plan. & Dev.)				
SUPPLIES	\$2,019,626	\$80,972.50	\$80,973	\$176,173.00
(Includes Proj. Mgmt., ROW, Const.				
and a portion of GIS and Plan. & Dev.)				
FLEET	\$221,711	\$9,670.00	\$9,670	\$19,340.00
CAPITAL EQUIPMENT	\$0			
DEBT EXPENSE	\$1,589,847	\$66,746.00	\$66,746	\$125,643.00
(Bond Debt Expenses)				
TOTAL AMOUNT	\$39,301,241	\$1,702,419.00	\$1,702,419.00	\$3,415,227.00
			1	
ENGINEER:	N/A	нс	ESTIMATED BUDG	ETS - FY 27 - 35
R.O.W. ACQUISITION:	N/A	PLATS: [ ]	FY 26-27	\$3,550,454.52
CONTRACTOR:	N/A		FY 27-28	\$3,645,319.67
CONSTRUCTION ADMINISTRATION:	N/A		FY 28-29	\$3,742,990.26
INSPECTION:	N/A		FY 29-30	\$3,907,761.77
			FY 30-31	\$4,002,864.45
			FY 31-32	\$4,100,723.33
	is for expenses related to the District's Capil P Division, capital equipment, and bond debi		FY 32-33	\$4,201,326.39
financing of the CIP program.	,	,	FY 33-34	\$4,304,779.59
			FY 34-35	\$4,429,793.99
SPECIAL PROJECT NOTES:	Future years assume 3.0% increase per year fo	or all items except Debt Expe	enses. Estimated Debt Exp	enses provided
	by the Finance Department. Total Estimated P	roject Cost shown is the total	al within the ten year window	<i>I</i> .


### Capital Improvement Program

Fiscal Years 2026—2035


### **Reimbursement Projects**







		W			
PROJECT:	Black Mtn. Annex Craigmont Rd.	LOCATION:	Black Mountain		
TYPE:	Reimbursement				
PROJECT NO.	1992173	TOTAL LF:	0		
PROJECT BUDGET:	\$0.00	PROJECT ORIGIN:	Consolidation Agreements		
DESCRIPTION	ESTIMATED	TOTAL EXPENDS	EST. COST	BUDGET	
	PROJECT COST	THRU 12/31/24	JAN - JUNE 2025	FY 25-26	
55310 - PRELIM. ENGINEERING					
55320 - SURVEY - DESIGN					
55330 - DESIGN					
55340 - PERMITS					
55350 - SPECIAL STUDIES					
55360 - EASEMENT PLATS					
55370 - LEGAL FEES					
55380 - ACQUISITION SERVICES					
55390 - COMPENSATION					
55400 - APPRAISAL					
55410 - CONDEMNATION					
55420 - CONSTRUCTION					
55430 - CONST. CONTRACT ADM.					
55440 - TESTING					
55450 - SURVEY - ASBUILT					
TOTAL AMOUNT	\$0.00	\$0.00	\$0.00	\$	\$0.00
ENGINEER:	Administered by Town of Black Mountain HC		ESTIMATED BUDGETS - FY 27 - 35		
R.O.W. ACQUISITION:			FY 26-27		\$0.00
CONTRACTOR:			FY 27-28		\$0.00
CONSTRUCTION ADM:	Administered by Town of Black Mountain		FY 28-29		\$0.00
INSPECTION:	MSD/Black Mountain		FY 29-30		\$0.00
			FY 30-31		\$0.00
PROJECT DESCRIPTION: Reimbursement project in accordance with Consolidation Agreement.			FY 31-32 \$0.00		\$0.00
					\$0.00
Estimated project cost was \$420,	UUU III FYU7.		FY 33-34		\$0.00
			FY 34-35		\$0.00
SPECIAL PROJECT NOTES:	MSD Share is 35% in accordance with Consoli				
	Project will be budgeted when town decides to construct it				



#### **BUDGET DATA SHEET - FY 2025 - 2026** PROJECT: LOCATION: **Developer Reimbursements** Various TYPE: Reimbursement - Annual PROJECT NO. 2004051 TOTAL LF: n PROJECT BUDGET: \$1,083,000.00 PROJECT ORIGIN: **Developer Reimbursement Policy ESTIMATED TOTAL EXPENDS BUDGET** EST. COST DESCRIPTION THRU 12/31/24 **JAN - JUNE 2025** FY 25-26 PROJECT COST 55310 - PRELIM. ENGINEERING 55320 - SURVEY - DESIGN 55330 - DESIGN 55340 - PERMITS 55350 - SPECIAL STUDIES 55360 - EASEMENT PLATS 55370 - LEGAL FEES 55380 - ACQUISITION SERVICES 55390 - COMPENSATION 55400 - APPRAISAL 55410 - CONDEMNATION 55420 - CONSTRUCTION \$1,083,000.00 \$0.00 \$183,000.00 \$100,000.00 55430 - CONST. CONTRACT ADM. 55440 - TESTING 55450 - SURVEY - ASBUILT TOTAL AMOUNT \$1,083,000.00 \$0.00 \$183,000.00 \$100,000.00 ESTIMATED BUDGETS - FY 27 - 35 ENGINEER: R.O.W. ACQUISITION: # PLATS: [ FY 26-27 \$100,000.00 CONTRACTOR: FY 27-28 \$100,000.00 CONSTRUCTION ADM: FY 28-29 \$100,000.00 INSPECTION: FY 29-30 \$100,000.00 FY 30-31 \$100,000.00 FY 31-32 \$100,000.00 PROJECT DESCRIPTION: This is for reimbursements for extensions that qualify under the District's \$100,000.00 Extension Policy. Refer to the "Policy and Procedures for the Extension of Sewer Service" for further FY 33-34 \$100,000.00 information. FY 34-35 \$100,000.00 SPECIAL PROJECT NOTES: