

SCHEDULE OF ESTIMATED QUANTITIES AND BID PRICES

Buchanan Avenue Sewer Rehabilitation, Project No. 2014023 METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY

ITEM NO.	DESCRIPTION	QTY	UNITS	BID	TOTAL
MP-5.01	MOBILIZATION (3% MAX)	1	LS	\$	\$
MP-5.02.8(d)	8" DIP (CLASS 350) ALL DEPTHS	2,204	LF	\$	\$
MP-5.02.4(p)	4" PVC (SCH 40) ALL DEPTHS, INCLUDING BEDDING	460	LF	\$	\$
MP-5.03.4(s)	4' DIAMETER STANDARD MANHOLE 0-6 FT.	21	EA	\$	\$
MP-5.04.4(s)	4' ADDITIONAL STANDARD MANHOLE DEPTH	13	VF	\$	\$
MP-5.05.4	8" X 8" X 4" DUCTILE IRON WYE	28	EA	\$	\$
MP-5.06.4	4" CLEANOUT ASSEMBLY	32	EA	\$	\$
MP-5.07	PLUG AND ABANDON SEWERLINE	7	EA	\$	\$
MP-5.10	CONNECT TO EXISTING MANHOLE	2	EA	\$	\$
MP-5.12	PIPE EMBEDMENT MATERIAL	22	CY	\$	\$
MP-5.13	COMPACTED AGGREGATE BASE COURSE	219	CY	\$	\$
MP-5.14	SELECT BACKFILL MATERIAL	784	CY	\$	\$
MP-5.15	ROCK EXCAVATION	980	CY	\$	\$
MP-5.20	SERVICE LINE EXPLORATORY DIG	32	EA	\$	\$
MP-5.21.6(b)	BITUMINOUS PAVEMENT REPAIRS TYPE I-19.0 B) 6" DEPTH	1,175	SY	\$	\$
MP-5.21.2(s)	BITUMINOUS ASPHALT RESURFACING (TYPE SF 9.5A) 2" MIN. DEPTH	4,500	SY	\$	\$
MP-5.25	HAND PLACED ASPHALT CURB	2,000	LF	\$	\$
MP-5.27	PAVEMENT MILLING 2"	4,500	SY	\$	\$

SCHEDULE OF ESTIMATED QUANTITIES AND BID PRICES

Buchanan Avenue Sewer Rehabilitation, Project No. 2014023
METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY

ITEM NO.	DESCRIPTION	QTY	UNITS	BID	TOTAL
MP-5.30	REPLACEMENT OF EXISTING PROPERTY MONUMENTS DISTURBED BY CONSTRUCTION	3	EA	\$	\$
	TOTAL BID PRICE			\$	
TOTAL WRITTEN BID PRICE _____ <div style="text-align: right;">and _____/100 dollars.</div>					