

SCHEDULE OF ESTIMATED QUANTITIES AND BID PRICES
ELK MOUNTAIN PLACE SANITARY SEWER REHABILITATION
PROJECT NO. 2010094
METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY

| ITEM NO. | DESCRIPTION | QTY | UNITS | BID | TOTAL |
|--------------|---|-------|-------|-----|-------|
| MP-5.01 | MOBILIZATION (3% MAX) | 1 | LS | \$ | \$ |
| MP-5.02.8(d) | 8" DIP (CLASS 350) ALL DEPTHS | 4,137 | LF | \$ | \$ |
| MP-5.02.6(p) | 6" PVC ALL DEPTHS, INCLUDING BEDDING | 120 | LF | \$ | \$ |
| MP-5.02.4(d) | 4" DIP (CLASS 350) ALL DEPTHS | 40 | LF | \$ | \$ |
| MP-5.02.4(p) | 4" PVC (SCH 40) ALL DEPTHS, INCLUDING BEDDING | 900 | LF | \$ | \$ |
| MP-5.03.4(s) | 4' DIAMETER STANDARD MANHOLE 0-6 FT. | 29 | EA | \$ | \$ |
| MP-5.03.4(d) | 4' DIAMETER DROP MANHOLE 0-6 FT. | 1 | EA | \$ | \$ |
| MP-5.04(s) | ADDITIONAL STANDARD MANHOLE DEPTH | 33 | VF | \$ | \$ |
| MP-5.04(d) | ADDITIONAL DROP MANHOLE DEPTH | 6 | VF | \$ | \$ |
| MP-5.05.4 | 8" X 8" X 4" DI WYE | 43 | EA | \$ | \$ |
| MP-5.06.4 | 4" CLEANOUT ASSEMBLY | 49 | EA | \$ | \$ |
| MP-5.06.6 | 6" CLEANOUT ASSEMBLY | 6 | EA | \$ | \$ |
| MP-5.07 | PLUG AND ABANDON SEWERLINE | 15 | EA | \$ | \$ |
| MP-5.08 | ABANDON MANHOLE, INCLUDING PLUGS | 10 | EA | \$ | \$ |
| MP-5.10 | CONNECT TO EXISTING MANHOLE | 1 | EA | \$ | \$ |
| MP-5.11 | MISCELLANEOUS CONCRETE | 10 | CY | \$ | \$ |
| MP-5.12 | PIPE EMBEDMENT MATERIAL | 100 | CY | \$ | \$ |
| MP-5.13 | COMPACTED AGGREGATE BASE COURSE | 12 | CY | \$ | \$ |
| MP-5.14 | SELECT BACKFILL MATERIAL | 920 | CY | \$ | \$ |
| MP-5.15 | ROCK EXCAVATION | 185 | CY | \$ | \$ |

SCHEDULE OF ESTIMATED QUANTITIES AND BID PRICES
ELK MOUNTAIN PLACE SANITARY SEWER REHABILITATION
PROJECT NO. 2010094
METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY

| ITEM NO. | DESCRIPTION | QTY | UNITS | BID | TOTAL |
|---------------|--|-------|-------|-----|-------|
| MP-5.16 | RIP-RAP STREAMBANK PROTECTION | 150 | SY | \$ | \$ |
| MP-5.18.1 | SILT FENCE | 2,525 | LF | \$ | \$ |
| MP-5.18.3 | EROSION CONTROL - COIR MATTING | 3,840 | SY | \$ | \$ |
| MP-5.19 | GRAVEL SURFACE DRIVEWAY REPAIR | 240 | CY | \$ | \$ |
| MP-5.20 | SERVICE LINE EXPLORATORY DIG | 5 | EA | \$ | \$ |
| MP-5.21.11(b) | BITUMINOUS PAVEMENT REPAIRS TYPE I-19.0 B) 11" DEPTH | 12 | SY | \$ | \$ |
| MP-5.21.4(b) | BITUMINOUS PAVEMENT REPAIRS TYPE I-19.0 B) 4" DEPTH | 40 | SY | \$ | \$ |
| MP-5.21.2(s) | BITUMINOUS ASPHALT RESURFACING (TYPE SF 9.5A) 2" MIN. DEPTH | 370 | SY | \$ | \$ |
| MP-5.22.1 | CONCRETE ANTI-SEEP COLLAR | 1 | EA | \$ | \$ |
| MP-5.24 | CONCRETE CURB & GUTTER REPLACEMENT, TO MATCH EXISTING | 20 | LF | \$ | \$ |
| MP-5.26 (c) | SIDEWALK REPLACEMENT | 10 | SY | \$ | \$ |
| MP-5.27 | PAVEMENT MILLING 2" | 370 | SY | \$ | \$ |
| MP-5.29 | CONCRETE ENCASEMENT | 90 | LF | \$ | \$ |
| MP-5.30 | REPLACEMENT OF EXISTING PROPERTY MONUMENTS DISTURBED BY CONSTRUCTION | 4 | EA | \$ | \$ |
| MP-5.34 | TREE REPLACEMENT - 6' (GENERAL) | 4 | EA | \$ | \$ |
| MP-5.36.1 | SPECIAL PROVISION - TREE PROTECTION FENCING | 50 | LF | \$ | \$ |
| | TOTAL BID PRICE | | | \$ | |

TOTAL WRITTEN BID PRICE _____

_____ **and** _____ **/100 dollars.**