

SCHEDULE OF ESTIMATED QUANTITIES AND BID PRICES
KIMBERLY AVE @ SEDLEY AVE
MSD PROJECT NO. 2018029
METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY

ITEM #	DESCRIPTION	AMOUNT	UNIT	UNIT PRICE	TOTAL
	MOBILIZATION (3%)	1	LS	\$	\$
MP-5.02.8(pb)	8" HDPE DIPS (DR 17) ALL DEPTHS (PNEUMATIC)	1631	LF	\$	\$
MP-5.02.8(pbs)	8" HDPE DIPS (DR 17) ALL DEPTHS (STATIC)	523	LF	\$	\$
MP-5.02.8(d)	8" DIP (CLASS 350) ALL DEPTHS	42	LF	\$	\$
MP-5.02.8(p)	8" SDR26 HEAVY WALL PVC, INCLUDING BEDDING, ALL DEPTHS	514	LF	\$	\$
MP-5.02.6(p)	6" PVC (SCH 40) ALL DEPTHS, INCLUDING BEDDING	40	LF	\$	\$
MP-5.02.4(p)	4" PVC (SCH 40) ALL DEPTHS, INCLUDING BEDDING	280	LF	\$	\$
MP-5.03.4(s)	4' DIAMETER STANDARD MANHOLE 0-6 FT.	11	EA	\$	\$
MP-5.03.4(w)	4' DIAMETER STANDARD MANHOLE 0-6 FT. (WATERTIGHT & LOCKDOWN)	1	EA	\$	\$
MP-5.03.4(sh)	4' DIAMETER SHALLOW MANHOLE TYPE I	2	EA	\$	\$
MP-5.04.4(s)	4' ADDITIONAL MANHOLE DEPTH	8	VF	\$	\$
MP-5.05.4	8" X 8" X 4" DI WYE	1	EA	\$	\$
MP-5.05.4(p)	8" X 8" X 4" PVC WYE	3	EA	\$	\$
MP-5.06.4	4" CLEANOUT ASSEMBLY	23	EA	\$	\$
MP-5.06.6	6" CLEANOUT ASSEMBLY	3	EA	\$	\$
MP-5.07	PLUG AND ABANDON SEWERLINE	1	EA	\$	\$
MP-5.08	ABANDON MANHOLE, INCLUDING PLUGS	1	EA	\$	\$
MP-5.10	CONNECT TO EXISTING MANHOLE	1	EA	\$	\$
MP-5.13	COMPACTED AGGREGATE BASE COURSE	125	CY	\$	\$
MP-5.14	SELECT BACKFILL MATERIAL	50	CY	\$	\$
MP-5.15	ROCK EXCAVATION	50	CY	\$	\$
MP-5.20	SERVICE LINE EXPLORATORY DIG	1	EA	\$	\$
MP-5.21.5(b)	BITUMINOUS PAVEMENT REPAIRS TYPE I-19.0 B 5" DEPTH	450	SY	\$	\$
MP-5.21.2(s)	BITUMINOUS ASPHALT RESURFACING (TYPE SF 9.5A) 2" MIN. DEPTH	2105	SY	\$	\$
MP-5.23	CONCRETE DRIVEWAY REPAIR OR REPLACEMENT, TO MATCH EXISTING	13	SY	\$	\$
MP-5.24.1	CONCRETE CURB REPLACEMENT, TO MATCH EXISTING	150	LF	\$	\$
MP-5.26.(c)	SIDEWALK REPLACEMENT	45	SY	\$	\$
MP-5.27	PAVEMENT MILLING 2"	2105	SY	\$	\$
MP-6.04	SERVICE RECONNECTION BY EXCAVATION INCLUDING SADDLE OR COMP. FITTING TO PIPELINE OR CORED CONNECTION TO A MANHOLE, ALL COMPLETE	24	EA	\$	\$
TOTAL BID PRICE					\$
TOTAL WRITTEN BID PRICE _____					
_____ and _____/100 dollars.					