

SCHEDULE OF ESTIMATED QUANTITIES AND BID PRICES
MONTFORD AVE. @ MONTFORD PARK, PROJECT 2017144
METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY

ITEM NO.	DESCRIPTION	QTY	UNITS	BID	TOTAL
MP-5.01	MOBILIZATION (3% MAX)	1	LS	\$	\$
MP-5.02.8(d)	8" DIP (CLASS 350) ALL DEPTHS	804	LF	\$	\$
MP-5.02.8(pb)	8" HDPE DIPS (DR 17) ALL DEPTHS BY PIPE BURSTING METHOD	325	LF	\$	\$
MP-5.02.4(p)	4" PVC (SCH 40) ALL DEPTHS, INCLUDING BEDDING	440	LF	\$	\$
MP-5.03.4(s)	4' DIAMETER STANDARD MANHOLE 0-6 FT.	6	EA	\$	\$
MP-5.03.4(d)	4' DIAMETER DROP MANHOLE	1	EA	\$	\$
MP-5.04(s)	ADDITIONAL STANDARD MANHOLE DEPTH	10	VF	\$	\$
MP-5.04.4(d)	4' ADDITIONAL DROP MANHOLE DEPTH	13	VF	\$	\$
MP-5.05.4	8" X 8" X 4" DI WYE	13	EA	\$	\$
MP-5.06.4	4" CLEANOUT ASSEMBLY	22	EA	\$	\$
MP-5.07	PLUG AND ABANDON SEWERLINE	1	EA	\$	\$
MP-5.08	ABANDON MANHOLE, INCLUDING PLUGS	5	EA	\$	\$
MP-5.10	CONNECT TO EXISTING MANHOLE	1	EA	\$	\$
MP-5.12	PIPE EMBEDMENT MATERIAL	20	CY	\$	\$
MP-5.13	COMPACTED AGGREGATE BASE COURSE	49	CY	\$	\$
MP-5.14	SELECT BACKFILL MATERIAL	179	CY	\$	\$
MP-5.15	ROCK EXCAVATION	215	CY	\$	\$
MP-5.18	SILT FENCE	297	LF	\$	\$
MP-5.18.3	EROSION CONTROL - COIR MATTING	84	SY	\$	\$
MP-5.19	GRAVEL SURFACE DRIVEWAY REPAIR	9	CY	\$	\$
MP-5.20	SERVICE LINE EXPLORATORY DIG	1	EA	\$	\$
MP-5.21.8(b)	BITUMINOUS PAVEMENT REPAIRS TYPE I-19.0 B 8" DEPTH	230	SY	\$	\$
MP-5.21.2(s)	BITUMINOUS ASPHALT RESURFACING (TYPE SF 9.5A) 2" MIN. DEPTH	1630	SY	\$	\$

SCHEDULE OF ESTIMATED QUANTITIES AND BID PRICES
MONTFORD AVE. @ MONTFORD PARK, PROJECT 2017144
METROPOLITAN SEWERAGE DISTRICT OF BUNCOMBE COUNTY

ITEM NO.	DESCRIPTION	QTY	UNITS	BID	TOTAL
MP-5.23	CONCRETE DRIVEWAY REPAIR OR REPLACEMENT, TO MATCH EXISTING	10	SY	\$	\$
MP-5.26.(c)	SIDEWALK REPLACEMENT	52	SY	\$	\$
MP-5.27	PAVEMENT MILLING 2"	1630	SY	\$	\$
MP-5.29	CONCRETE ENCASEMENT	12	LF	\$	\$
MP-5.30	REPLACEMENT OF EXISTING PROPERTY MONUMENTS DISTURBED BY CONSTRUCTION	1	EA	\$	\$
MP-5.31.3	REPLACEMENT OF EXISTING STORM DRAIN 36"-48"	10	LF	\$	\$
MP-5.32	ORANGE CONSTRUCTION BARRIER FENCE	180	LF	\$	\$
MP-5.34.2	6' TALL REPLACEMENT MAPLE TREE (TRIDENT MAPLE)	1	EA	\$	\$
MP-5.34.10	3 - 5 GALLON SHRUB/PLANT REPLACEMENT	5	EA	\$	\$
MP-5.34.12	REPLACEMENT CRAPE MYRTLE 7-10 GAL	3	EA	\$	\$
MP-6.04	SERVICE RECONNECTION BY EXCAVATION INCLUDING SADDLE OR COMP. FITTING TO PIPELINE OR CORED CONNECTION TO A MANHOLE, ALL COMPLETE	8	EA	\$	\$
	TOTAL BID PRICE				\$
TOTAL WRITTEN BID PRICE _____					
_____ and _____ /100 dollars.					